

**DAM SAFETY ASSURANCE PROGRAM
EVALUATION REPORT AND
ENVIRONMENTAL IMPACT STATEMENT**

**APPENDIX C – TAB II
GEOTECHNICAL**

**DOVER DAM, OH
TUSCARAWAS RIVER**

TABLE OF CONTENTS

1	Purpose and Scope	1
1.1	References.....	1
2	Geology.....	2
2.1	Regional Geology	2
2.2	Local Geology.....	2
2.3	Foundation Conditions.....	3
2.4	Seismicity.....	5
3	Stability Re-analysis	5
4	Geological Investigations to Date	6
4.1	1982-83 Investigations.....	6
4.2	2004 Investigations	7
4.2.1	Rock Coring.....	7
4.2.2	Overburden Drilling, Sampling and Testing.....	7
5	Rock Testing.....	8
5.1	Sliding Shear Strength	8
5.2	Cross Bed Shear Strength	9
5.3	Smooth Sawn Surface Shear Strength	10
5.4	Grout on Rock Shear Strength	10
5.5	Elastic Modulus	11
5.6	Allowable Bearing Capacity	11
5.7	Failure Plane Selection	11
5.8	Unit Weight.....	11
6	Soil Characterization.....	11
6.1	General.....	13
6.2	Existing Soils	14
6.2.1	In Situ Soils.....	14
6.2.2	Compacted Backfill	15
6.2.3	Rolled Embankment.....	16
6.2.4	Upstream (US) North Abutment Slide Backfill.....	16
6.2.5	Rock Fill.....	17

6.2.6	Uncompacted Backfill	17
6.3	Groundwater Conditions	17
7	Soil Design Considerations.....	17
7.1	General.....	17
7.2	Abutment Soil Stability.....	18
7.3	Parapet Wall.....	18
7.4	State Route 800 Gate Closure	19
7.5	Streambank Erosion Protection.....	19
7.5.1	Stone Slope Protection.....	19
7.5.2	Environmental Design Consideration	20
8	Uplift.....	20
9	Effect of Anchors on Uplift	23
10	Breach Assumptions	24
11	Anchor Designs.....	24
11.1	Corrosion Protection	24
11.2	Anchor Depth Calculation	25
11.3	Bond Length Calculation	27
12	Future Explorations and Investigations	28
12.1	Rock	28
12.2	Soil	28
12.3	Seismic	28

LIST OF FIGURES, TABLES, PHOTO AND EXHIBITS

<u>Figure No.</u>	<u>Title</u>
Figure II-1	Drain Efficiency (EM1110-2-2100)
Figure II-2	Anchor Embedment (EM110-1-2908)
Figure II-3	3-D Anchor Embedment Check
<u>Table No.</u>	<u>Title</u>
Table II-1	Summary of Dover Dam Rock Strengths
Table II-2	Typical Coefficients of Lateral Earth Pressure At-Rest (from Clough and Duncan, 1991)
Table II-3	Approximate values of undrained shear strength for cohesive soils based on SPT blow count N-values (from Terzaghi and Peck, 1967)
Table II-4	Empirical values for Φ , D_r , and unit weight of granular soils based on the standard penetration number with correction for depth and for fine saturated sands (from Bowles, 1968)
Table II-5	Soil Properties
Table II-6	Foundation Drain Data
<u>Photo No.</u>	<u>Title</u>
Photo II-1	Foundation Report Photo of Fault
<u>Exhibit No.</u>	<u>Title</u>
Exhibit II-1	Boring Location Plan
Exhibit II-2	Rock Profiles and Sections
Exhibit II-3	Geology and Soils Legend
Exhibit II-4	Graphic Logs of Borings
Exhibit II-5	Overburden Sections
Exhibit II-6	Rock Laboratory Test Data
Exhibit II-7	Uplift
Exhibit II-8	Mapping of Faults and Joints
Exhibit II-9	Anchor Embedment

1 Purpose and Scope

This evaluation report documents project foundation characteristics and geotechnical strength parameters used for the stability reevaluation. It also describes the required subsurface investigations, geotechnical testing, and methods used to establish bedrock and soil strength parameters, drain efficiency, and preliminary seismic parameters. For general information regarding the dam and when it was constructed see paragraph 1.3 (“Existing Project Description”) of the main report.

1.1 References

- | | |
|----------------|---|
| ASTM D1586-99 | Standard Test Method for Penetration Test and Split Barrel Sampling of Soils, 10 January 1999 |
| ASTM D 2488 | Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), 10 February 2000 |
| EM 1110-1-1804 | Geotechnical Investigations, 1 January 2001 |
| EM 1110-2-1902 | Slope Stability, 31 October 2003 |
| EM 1110-2-1906 | Laboratory Soils Testing, 20 August 1986 |
| EM 1110-2-2502 | Retaining and Flood Walls, 29 September 1989 |
| EM 1110-1-2908 | Rock Foundations, 30 November 1994 |
| EM 1110-2-6050 | Response Spectra and Seismic Analysis for Concrete Hydraulic Structures, 30 June 1999 |
| ER 1110-2-1806 | Earthquake Design and Evaluation for Civil Works Projects, 31 July 1995 |

Addenda to the Analysis of Design, Dover Dam, 1939.

Dover Dam Periodic Inspection Report No. 1, U.S. Army Corps of Engineers, Huntington District, March 1970

Bowles, J., 1968. *Foundation Analysis and Design*. McGraw-Hill, New York.

Clough, G.W. and Duncan, J.M., 1991. *Earth pressures*, chapter in *Foundation Engineering Handbook*, 2nd edition, edited by Hsai-Yang Fang, van Nostrand Reinhold, New York, NY.

Das, B.M., 1998. *Principles of Geotechnical Engineering, Fourth Edition*. PWS Publishing Company, Boston, MA.

Fuller, Mossbarger Scott & May, 1999. *Seismic Analysis Report for the Muskingum River Basin*.

Goodman, Richard, E., 1980. *Introduction to Rock Mechanics*. John Wiley & Sons.

McGregor, J.A. and Duncan, J.M., *Performance and Use of the Standard Penetration Test in Geotechnical Engineering Practice*, Virginia Polytechnic Institute Center for Geotechnical Practice and Research, October 1998.

Post-Tensioning Institute, *Recommendations for Prestressed Rock and Soil Anchors, Fourth Edition*, Post-Tensioning Institute Phoenix, AZ , 2004.

Terzaghi, K. and Peck, R.B., 1976. *Soil Mechanics in Engineering Practice*. John Wiley, New York, NY.

2 Geology

2.1 Regional Geology

Dover Dam is located in the Fairfield Township of Tuscarawas County, which is part of the Appalachian Basin.

About 2 miles upstream from the dam site, the Tuscarawas River leaves a broad, deeply filled pre-glacial valley and flows for 6 miles through a narrow steep-walled gorge of post-glacial origin. The river throughout most of the length of the gorge flows on bedrock or on a very shallow cover of alluvial sand and gravel over bedrock. Bedrock consists of nearly horizontal beds of shale, siltstone, sandstone, limestone and coal. These beds are part of the Pottsville Group of the Lower Pennsylvanian System.

The Lower Mercer limestone forms most of the foundation of the dam, with shale, sandstone, and coal over- and underlying the limestone. Below the limestone is shale into which several of the monoliths are keyed. The crystalline basement in Tuscarawas County is greater than 1,818 m (6,000') below the top of ground.

2.2 Local Geology

At the dam site prior to construction, the river had a width of 350 feet and a low water surface elevation of 865. The valley walls rise on steep slopes from the water's edge to an upland whose general elevation ranges from 1100 to 1200 feet. The valley consists of approximately 7 feet of alluvial sand and gravel to top of bedrock. At the dam site, the walls are of the Pennsylvanian age bedrock units of the Allegheny and Pottsville Series.

The abutments are composed primarily of shales with one 35 foot thick sandstone unit and 1 to 2 foot thick seam of coal. Bedrock is deeply weathered in the abutments but, according to the foundation reports, weathered rock was removed to ensure that all concrete monoliths were founded on sound bedrock. The groundwater surface was high in the abutments prior to construction of the dam, see paragraph 6.3 “Groundwater Conditions” for existing conditions.

The bedrock surface in the valley bottom is controlled by the upper surface of one of the limestone units. This 4-foot thick, Lower Mercer Limestone became the primary founding unit for the dam. The limestone is immediately underlain by a carbonaceous shale, ranging from 3 to 7 feet thick. Beneath this shale is a 20 to 25-foot thick, sandy siltstone which coarsens with depth into a thicker micaceous and silty sandstone unit. Due to minor local flexures, the contacts between the various bedrock units appear to form an irregular surface of an undulating nature.

Some stress-relief related fracturing and associated weathering in the dam abutments is noted in the construction foundation reports. Fracturing (slickensided joints) and some associated minor faulting is apparent in the limestone founding unit and continues thru the underlying shales and siltstones. One thrust fault of major consequence was encountered in the foundation although there were multiple minor faults too. The fault strike varies from N80°W to N75°E, dipping from 45°SW to 45°SE.

2.3 Foundation Conditions

The abutment monoliths are founded on various bedrock units. Monoliths 4 and 20 are founded on sandy shale. Monolith 3 is founded, partly on limestone and partly on sandstone. Monoliths 1, 2, 21, 22, and 23 are founded on this massive sandstone. Monolith 5 was founded on the Lower Mercer Limestone unit. All of the abutment monoliths are embedded into bedrock excavations with confinements both upstream and downstream by weathered rock which was deemed during design, suitable to provide the necessary sliding stability.

All of the spillway monoliths (Monoliths 7 through 15) along with non-overflow monoliths 16 through 19 are founded on top of the Lower Mercer Limestone, see Exhibit II-8 “Rock Profiles and Sections.” This approximately four-foot thick limestone is continuous across the valley bottom and is underlain by a less competent carbonaceous shale of similar thickness. The logs from the 1982-83 exploration program describe moderate to severely broken zones in the carbonaceous shale. The limestone serves as the primary founding unit for the monoliths including the associated stilling basin monoliths and retaining walls. Founding elevations vary from 847 to 855. At the upstream heel of the dam a 20 foot deep rebar reinforced key was formed through the carbonaceous shale and into an underlying sandy-siltstone. The reinforced key was necessary to provide the required factor of safety against sliding failure.

After the limestone was exposed, the above mentioned fault was observed trending approximately east to west across Monoliths 14, 14A and 15, see Exhibit II-8 “Mapping

of Faults and Joints.” The fault extends through the limestone and into the underlying shales. It is further described in the Addenda to the Analysis of Design, Dover Dam (1939): "Two types of displacement have occurred. The limestone capping the north side of the fault was pushed over that on the south side forming a "thrust" fault. On the other hand, the shale on the north side moved downward in relation to the shale on the south side, resulting in a typical "reverse" fault. Both movements are due to compression but a thrust fault dips less than 45° and a reverse dips greater than 45°. This faulting resulted in a 2 foot thick opening between the limestone and shale and severe broken conditions in the shale along the fault." Because of this faulting the foundations for Monoliths 14, 14A and 15 were lowered to the sandy-siltstone at the elevation of the originally planned key. Extensive grouting was performed under the foundation along both sides of the fault and in Monoliths 12 and 13 to fill the opening between the limestone and the siltstone.

A fault striking N-S and dipping about 70° E was seen in the limestone in monoliths 13B and 13C. It was a normal fault with about 2 ½ feet of displacement. It cut a second fault that was striking E-W. It showed about 3 feet of offset on an overthrust.

Smaller faults, striking N-E to N25°E, all nearly vertical, with displacements of 1 to 2 feet were also reported to the north of the major fault. All cut the limestone and shale, but were not readily traceable in the underlying sandstone except in a grout hole in monolith 11. The sandstone from elevation 800' MSL to 810' MSL was "shattered" and severely broken. This may be a fault, but it was only intercepted by one boring and never excavated, so no more is known about it.

A number of other minor faults were encountered in the foundation of the dam and stilling basin monoliths. The faults and joints were mapped and reported in each monolith foundation report, these were compiled and are shown in Exhibit No. II-8. These faults and major joints and fractures in the foundation were treated with special grout lines placed in the discontinuity.

At the upstream face of Spillway Monoliths 7 through 15 and Non-Overflow Monoliths 16 through 19, a cutoff trench was excavated 20 feet deep and 10.5 feet wide at the bottom with a downstream face sloped 2 vertical on 1 horizontal. The trench extended to elevation 830 for Monoliths 7 through 12 and to elevation 835 for Monoliths 13 through 19. Grouting was performed on the upstream and downstream sides of the cutoff trench prior to beginning rock excavation. Final grouting was performed through 3-1/2-inch diameter preformed vertical holes on 5-foot centers at the base of the cutoff trench. Grouting was performed from the top of the first pour. The grout holes were drilled 30 feet into rock and were grouted with 30 psi pressure in the top 15 feet and 80 psi in the bottom 15 feet of grout hole.

The upper surface of the founding limestone member slopes more steeply at the downstream limit of the stilling basin thus less erosion resistant shales form the bedrock surface at that location. In order to prevent scouring of the channel bottom downstream from the end of the apron, a 20-foot strip of derrick stone was placed against the apron end sill over about one-half the width of the stilling basin. A 15-foot stepped slab of

concrete was placed against the downstream face of the apron and doweled into the limestone and the concrete over the remaining (north) one-half of the basin.

2.4 Seismicity

ER 1110-2-1806 Earthquake Design and Evaluation for Civil Works Projects (1995), Appendix C, Uniform Building Code Zone Map shows Dover Dam in seismic zone 1.

In May of 1999 AE Contractors Fuller, Mossbarger Scott & May, (FMSM) submitted the "Seismic Analysis Report for the Muskingum River Basin". The objective of this study was to evaluate and develop seismic ground motions for use as the basis for future studies in the Muskingum River Basin. As the need for analyses, designs and/or remediation projects arise at each of the 16 dams or their appurtenances, this study will serve as the basis for the development of site specific ground motions. This report is intended to partially satisfy requirements in ER 1110-2-1806 Earthquake Design and Evaluation for Civil Works Projects (1995) and ER 1110-2-1155 Dam Safety Assurance (1997) for a Phase 1 seismic study. Other references such as Engineering Circular 1110-2-6050 and "Fundamentals of Earthquake Resistant Construction" by Krinitzsky, Gould and Edinger, Published by Wiley, 1993 were utilized as guides in completion of the study.

The recommended Operation Basis Earthquake (OBE) consists of a magnitude 5.2 m_b event having an epicentral distance of 15 km and a focal depth of 5 km. The resulting peak horizontal acceleration (PHA), peak horizontal velocity (PHV) and duration are 98 cm/sec^2 , 6.1 cm/sec and 3.9 seconds, respectively. The recommended Maximum Credible Earthquake (MCE) consist of a magnitude 5.5 m_b event having an epicentral distance of 20 km and a focal depth of 5 to 10 km. The resulting PHA, PHV and duration are 147 cm/sec^2 , 11.2 cm/sec and 6.8 seconds, respectively. The recommended acceleration values for the OBE and MCE are believed to roughly correspond to the mean plus one standard deviation hazard for return periods of 144 and 500 years, respectively. Alternatively, the OBE and MCE correspond to the 400 and 3000 year return interval events respectively, when compared to the mean hazard. The equal hazard spectra indicate the highest spectral acceleration is realized at frequencies ranging from 5 to 20 Hz which is expected for this region of the United States.

The FMSM 1999 report concludes that for most structures, the motions supplied with the report could be used without alteration. However, other structures, such as Dover Dam, may be sensitive to a narrow range of frequencies not investigated because of the general nature of the study. Consequently, it is recommended that a future study be done that reviews the motions supplied in the FMSM 1999 report and alters them, as necessary, for Dover Dam's site specific conditions.

3 Stability Re-analysis

Concerns over project stability have been documented in past periodic inspection reports. These concerns, due primarily to changes in analysis methodology and foundation

uncertainties, have resulted in recommendations for reanalysis, and programs of subsurface investigation.

Typical non-overflow and spillway monoliths were reanalyzed for structural stability after the second periodic inspection. The analyses are documented in Appendix V of that inspection report, transmitted 17 June 1977. For the 1977 reanalysis, parameters such as compressive strength, cohesion, and shear friction angle for certain foundation lithologies were assumed, based on engineering judgment. Strengths for other members were derived as weighted averages from the test data used for the original design. (See Appendix III of Periodic Inspection Report No. 1, for the original test results).

For the 1977 reanalysis, the stability was evaluated using full uplift over 100% of the base area. The rock properties used in the original design were adopted. These strengths discounted cohesion on the bedding planes. Resistance to sliding was dependent upon passive resistance due to embedment of the monoliths into rock. The stability was analyzed using the "Sliding Resistance Method" which looks at the ratio of horizontal forces to vertical forces. Results of the analyses indicated that all monoliths appeared to be safe against overturning, sliding, and bearing failure except Monoliths 7 through 9. The factor of safety against sliding for Monoliths 7 through 9 was found to be 0.75. The report went on to recommend a program of foundation exploration and further analyses.

The Endorsements to the 2nd Periodic Inspection Report concurred with the above recommendation (refer to 1st Endorsement, subject "Dover Dam, Ohio, Periodic Inspection Report No. 2," dated 4 October 1977; and OCE letter, subject same, dated 2 November 1977). Ohio River Division directed the District to submit a completed plan, schedule and cost estimate for the foundation exploration program. The drilling, completed in 1983, is discussed in the next section.

4 Geological Investigations to Date

The site geology was investigated during the design and construction of the dam by drilling forty-two core borings located along seven ranges across the valley bottom. These ranges are located from 600 feet upstream of the dam axis to 600 feet downstream. Four 6-inch diameter holes were drilled for test samples. In addition to the core borings, four test pits were dug to depths ranging from 25 to 61 feet. Two investigative programs have been carried out since the third periodic inspection.

4.1 1982-83 Investigations

The first program consisted of 15 NX borings, 3 vertical and 12 angled drilled from inside the operations gallery. The borings were logged by a Huntington District Geologist and the strike and dip of the prominent joints were calculated from the angled borings (see Exhibit II-10). Core loss was 5.6% or 17.7 feet for 316.5 feet of drilling. A boring plan and logs are included in Exhibits II-1 and II-4 respectively.

4.2 2004 Investigations

4.2.1 Rock Coring

The drilling program consisted of 14, 4-inch core borings located on each abutment. See Exhibit II-1 and II-4 for the location and logs of these borings. The exploration program's main purpose was to characterize the foundation conditions in the abutments which had not been considered in the earlier drilling program. Another facet of this drilling program was to obtain and test materials lithologically similar to those in the valley bottom, and attempt to interpolate rock strengths across the valley between the abutments. Core recovery, was higher than the earlier exploration program with only 0.3% or 2.8 feet lost in 839.8 feet of drilling. The core barrel used was a 5ft Hoffman double tube with a split inner barrel. The core was sealed in plastic to maintain moisture content, and placed in core boxes padded with sawdust to keep the core in good condition during shipping and handling and prior to test sample selection. The borings were re-logged by Huntington District geologists.

4.2.2 Overburden Drilling, Sampling and Testing

Fifteen (15) borings (C-04-1 to C-04-14 & C-04-5A) were drilled in 2004, primarily to obtain rock core samples for testing. Overburden was sampled in each boring using the Standard Penetration Test (SPT) method (2-inch slit spoon), in accordance with ASTM D 1586, with blow counts taken continuously. No undisturbed sampling was performed. Borings were drilled at the upstream and downstream sides of both abutments. Four (4) borings were drilled downstream of the dam in/near the right abutment, and two (2) were drilled upstream of the dam near the right abutment.

Of the four borings drilled in the right downstream area, one boring (C-04-5) was abandoned at a depth of 35.5 feet due to the presence of petroleum odors. This was encountered in a zone of weathered sandstone and shale. Drillers placed the auger cuttings into two (2) fifty-five (55) gallon drums, as noted on the field logs. A "slight petroleum-like odor" was noted on the drilling field log in a zone of silty clay (depth: 25.5 to 31 feet) near the ambient groundwater level of this boring. As a result, boring C-04-5A was drilled approximately 50-feet upstream of C-04-5. Similar to the right abutment, two (2) borings were drilled upstream of the dam near the left abutment, and three (3) borings were drilled just downstream of the dam near the left abutment. No borings were drilled in the river. Locations and graphic logs of these borings are shown in Exhibits II-1 and II-4, respectively.

Jar samples from split spoons were collected and were visually described using the Unified Soil Classification System (USCS), in accordance with ASTM D 2488. Natural moisture contents were also determined on most (173 out of 176) of the overburden samples. Sieve analyses were completed on approximately 15% of all jar samples, and representative samples of the fine-grained soil samples were tested to determine Atterberg Limits. No testing, beyond standard index testing to classify the soil types, was performed. These test results are included on the graphic logs in Exhibit II-4.

5 Rock Testing

For the 2005 rock testing program, all samples were taken from the 2004 drilling program and sample selections were done by Huntington District personnel. Sample preparation and testing was carried out by FMSM Engineers, Inc. of Lexington, Kentucky, an Army Engineer Research and Development Center (ERDC) validated lab, in accordance with the applicable provisions of the "Rock Testing Handbook," WES Geotechnical Laboratory Publication, March 1990.

The main goal of the 2005 testing program was to provide shear strengths and bearing capacities for the reanalysis of the dam.

TABLE II-1 Summary of Dover Dam Rock Strengths

	Cross Bed Shear Intact Peak (ϕ) (c) psi	Shear Parallel to Bedding Natural Fracture Peak (ϕ) (c) psi	Basic phi angle Smooth Sawn Surface (ϕ) (c) psi	Bedrock Dam Interface Grout on Rock Peak (ϕ) (c) psi	Allowable Bearing psi	E ₁₅₀ Elastic Modulus (x10 ⁶)	Unit Weight
Limestone	65 150 psi***	39 7 psi	29 0 psi	50 33 psi****	2191	24.740	168.5 pcf
Upper Sandstone	64 88 psi***	28 3 psi	26 0 psi	50 70 psi****	522	2.050	148 pcf
Sandy Siltstone	46 20 psi***	26 2 psi	21 0 psi	50 60 psi****	829	2.970	159.7 pcf
Siltstone	31 15 psi***	25 1.5 psi	14 0 psi	31 60 psi****	873	2.750	165.8 pcf
Shale	29 5 psi***	19 .5 psi	12.5 0 psi	30 50 psi****	300	1.750	161.5 pcf
Fault/Slickensided Joint*	19* 0 psi						
Concrete Key Lift Joint**		38 Controlled by Rebar**					

Shear Parallel to Bedding when used with the key should be reduced by 50% due to strain incompatibility with the rebar

*The cross bed shear strength assigned to the (Fault / Slickensided Joint) is the average of the basic phi angle for all of the materials except the Upper Sandstone.

The Upper Sandstone was excluded because it is not a component in the passive wedge of the 3 monoliths analyzed.

**The cohesion value used in the concrete key is assigned by structural section and is not published here.

***The cross bed shear cohesion was taken directly from the intact peak lower bound plot except cohesion was then reduced by 50 percent to account for scaling effects.

****The cohesion was taken directly from the lower bound plot of the grout on rock peak except cohesion was reduced by 66 percent to represent portions in the monolith where the contact is not bonded.

5.1 Sliding Shear Strength

Sliding shear strength is used to represent the shear strength of the rock where the direction of the shear is parallel to the discontinuity. The majority of the discontinuities in the foundation of Dover Dam are oriented nearly horizontal.

A total of forty-two (42) direct shear tests were run on core samples which represent natural fractures. Normal loads varied from 40 to 120 psi. Similar tests were also run on smooth-sawn samples to determine the basic phi angle of the materials (additional discussion on smooth-sawn sample testing in section below). The peak strengths of these natural fracture tests were plotted, and were taken into consideration along with the smooth-sawn tests to effectively establish an upper and lower bound of the appropriate values for sliding strength along open natural fractures in the foundation. The upper and

lower bounds, the chosen natural fracture sliding strengths, and cohesion of the rock mass were chosen as follows:

- **Upper Bound.** The linear regression plot of the peak strengths was assumed to represent an upper bound of this sliding strength because it includes the resistance of both the basic ϕ angle of the material, and the additional resisting influence of the “second-order” irregularities within the sample itself. The second-order irregularities are normally at a higher angle than the “first-order” irregularities (or “ i ” angle) within the overall rock mass; therefore, the angle of the linear regression for these natural fracture peak strengths can be used as an upper limit of the natural fracture sliding strength envelope.
- **Lower Bound.** The plot of the smooth-sawn surfaces, without the influence of the first- or second-order irregularities, is assumed to represent the lower bound of the natural fracture sliding strengths. Post-peak (residual) natural fracture plots are not presented in this report since smooth-sawn surface tests were available.
- **Rock Mass Sliding Strength.** The rock mass shear strength along natural fractures is represented by the basic ϕ angle of the material plus the additional strengthening influence of “first-order” irregularities within the rock mass. The first-order “ i ” angle was chosen based on engineering judgment. As expected, the rock mass sliding strength line plotted between the upper and lower bounds described above. (A selection of plots and the associated shear strength data are included in Exhibit II-6 .)

Cohesion. The linear regression plots of the natural fracture peak shear strengths are plotting at or near the xy intercept. The cohesion values used for design are based on engineering judgment, taking into account the apparent cohesion intercept at zero normal load and the characteristics of the natural fracture.

5.2 Cross Bed Shear Strength

Cross bed shear strength is used to represent the shear strength of the rock where the direction of the shear is not parallel to the bedding but crosses through the bedding. In the sliding stability analysis the cross bed shear strength of the rock is used to characterize the base of the passive wedge except where the foundation reports or exploration indicate faults or slickensided joints (see Photo II-1) are present along the base of the passive wedge, in these cases the base of the passive wedge is better characterized by the basic ϕ angle obtained from the smooth sawn surface shear strength.

A total of forty-five (45) direct shear tests were run on intact foundation rock at normal loads varying from 40 to 120 psi. Subsequent to failure at peak strength the tests were continued to obtain sliding resistance. The lower bound plot of the peak strength was used to characterize cross bed shear. The ϕ angle and cohesion were taken directly from the lower bound plot except cohesion was then reduced by 50 percent to account for scaling effects. The intact rock strengths selection was based on engineering judgment and in accordance with Corps guidance (EM 1110-1-2908).

5.3 Smooth Sawn Surface Shear Strength

Smooth sawn surface shear strength is used to represent a slickensided plane and to check the phi angle of the natural fracture (minus the first-order i angle).

A total of thirty (30) direct shear tests were run on sawn surfaces of foundation rock at normal loads varying from 40 to 120 psi. Typically the phi angle can be calculated from the plot of the peak shear stress, but the lab was unable to discern any peak shear stresses for the limestone or the upper sandstone, however post peak shear stresses were obtained for all rock types. To be consistent the post peak shear stresses for all of the rock types were used to calculate the phi angle, but instead of plotting a lower bound the phi angle is closer to the linear regression and any apparent cohesion plotted is ignored.



Photo II-1 Scanned photo from monolith 7 foundation report. The photo was taken from monolith 7 looking down stream at monolith 7A. Notice the bar that is resting on what is described as a fault. The fault or slickensided joint is dipping upstream.

5.4 Grout on Rock Shear Strength

Grout on rock shear strength is used to represent the interface of the monolith and the bedrock.

A total of forty-five (45) direct shear tests were run on sawn foundation rock surfaces bonded to grout at normal loads varying from 40 to 120 psi. The lower bound plot of the peak strength was used to characterize the contact of the monolith and the bedrock. The Phi angle and cohesion were taken directly from the lower bound plot except cohesion was reduced by 66 percent to represent portions in the monolith where the contact is not bonded. Of the three (3) vertical 1982-1983 gallery borings one (1) describes the

concrete to rock interface as intact with the remainder being open. The angled borings do not describe the condition of the concrete to rock interface.

5.5 Elastic Modulus

A total of thirty-eight (38) unconfined compression tests were performed on abutment bedrock samples. Axial and diametrical deformations were measured to allow derivation of elastic constants. The elastic modulus was derived from the slope of a line constructed tangent to the stress-strain curve at 50 percent of the peak stress.

5.6 Allowable Bearing Capacity

The allowable bearing capacity was calculated using Goodman's (Introduction to Rock Mechanics, page 311, Eq. 9.8) for ultimate bearing capacity and applying a factor of safety of 5. Goodman's equation uses the unconfined compressive strength, vertical joint spacing, monolith width, and intact rock Phi angle to calculate the ultimate bearing capacity. Goodman's equation was chosen over those given in EM 1110-1-2908 because it was more consistent, see exhibit II-6 for a comparison.

5.7 Failure Plane Selection

Multiple failure scenarios are shown in cross section with each monolith (see Exhibit No. 2) based on the stratification, location and orientation, frequency and distribution of discontinuities of the foundation material, and the configuration of the base. Each segment of the failure path is assigned a strength based on the material type, its condition and orientation. The angle of the base of the passive wedge was defined by the classical Coulomb passive failure plane equation ($45 - \phi/2$). Monoliths 5 and 7 show faults in the area of the passive wedge and are characterized using a smooth sawn surface shear strength. Monolith 17 shows no faulting in the passive wedge and therefore uses cross bed shear strength. The multiple failure options were then analyzed by the structural engineer, who selected the most critical potential plane of failure.

5.8 Unit Weight

The unit weight of each rock type was calculated from material leftover from the unconfined compressive tests. The specimens were prepared and tested in accordance with guidelines established in RTH 109-93. The test data from each rock type was averaged and the average is published in TABLE II-1.

6 Soil Characterization

Overburden characteristics are needed for soils found around the abutments and immediately upstream and downstream of dam monoliths. Soils in and around the abutments have been categorized as in situ soils, compacted backfill, rolled embankment, rock fill, and upstream north abutment slide backfill. Soils placed immediately upstream and downstream of dam monoliths have been termed compacted backfill. The

aforementioned categorizations are consistent with naming conventions shown on project as-built drawings.

Overburden characteristics are needed for two design purposes for this project. First, the soils along each downstream abutment offer resistance to sliding of monoliths 1-6 and 16-23. Therefore, engineering properties of these soils are needed to determine the amount of resistance they provide. Secondly, fills placed upstream of abutment monoliths add both vertical and horizontal stresses on the upstream face of abutment monoliths. Engineering properties have been selected to quantify these stresses for sliding stability analyses. The following discussion explains the selection of engineering properties of these materials.

Engineering properties for all known soils at this project have been selected using 2004 drilling and testing data, published correlations, and engineering judgment based on experience. At-rest earth pressure coefficients for use in structural analyses have been selected based on empirical relationships to shear strength parameters for granular soils, and published correlations for cohesive soils as shown in Table II-2. Tables II-3 and II-4 were utilized for correlating soil properties at the project based on SPT blow counts (N-values) obtained during drilling. Table II-3 below was used for cohesive soils (>50% passing the #200 sieve), while Table II-4 on the following page was used for granular (cohesionless) soils.

Table II-2 – Typical Coefficients of Lateral Earth Pressure At-Rest (from Clough and Duncan, 1991)

Coefficient of Lateral Earth Pressure At-Rest (K_o)					
Soil Type	Φ_f (deg)	OCR = 1	OCR = 2	OCR = 5	OCR = 10
Loose Sand	33.5	0.45	0.65	1.10	1.50
Medium Sand	36.5	0.40	0.60	1.05	1.55
Dense Sand	40.5	0.35	0.55	1.00	1.50
Silt	29.5	0.50	0.70	1.10	1.60
Lean Clay, CL	23.5	0.60	0.80	1.20	1.65
Highly Plastic Clay, CH	20.5	0.65	0.80	1.10	1.40

Table II-3 – Approximate values of undrained shear strength for cohesive soils based on SPT blow count N-values (from Terzaghi and Peck, 1967)

Soil Consistency	SPT N	S_u (psf)
Very Soft	< 2	< 250
Soft	2 - 4	250 - 500

Medium	4 - 8	500 - 1000
Stiff	8 - 15	1000 - 2000
Very Stiff	15 - 30	2000 - 4000
Hard	> 30	> 4000

Table II-4 – Empirical values for Φ , D_r , and unit weight of granular soils based on the standard penetration number with correction for depth and for fine saturated sands (from Bowles, 1968)

Description	Very loose	Loose	Medium	Dense	Very dense	
Relative density D_r	0	0.15	0.35	0.65	0.85	1.00
Standard penetra- tion no. N		4	10	30	50	
Approx. angle of internal friction ϕ^\dagger	25°-30°	27-32°	30-35°	35-40°	38-43°	
Approx. range of moist unit weight, (γ) pcf	70-100‡	90-115	110-130	110-140		130-150

† After Meyerhof [9]. $\phi = 25 + 0.15D_r$ with more than 5 percent fines and $\phi = 30 + 0.15D_r$ with less than 5 percent fines. Use larger values for granular material with 5 percent or less fine sand and silt.

‡ It should be noted that excavated material or material dumped from a truck will weigh 70 to 90 pcf. Material must be quite dense and hard to weigh much over 130 pcf. Values of 105 to 115 pcf for nonsaturated soils are common.

6.1 General

Extents of soils have been determined and correlated from as-built project drawings and construction notes contained in Dover Dam Periodic Inspection Report No. 1, as well as 2004 LRH boring data. Project As-Built drawings show that the original ground surface on the right abutment sloped riverward at about 1V:2H from old State Road No. 8 (Sta. 1+50) to the former Ohio Canal (Sta. 3+00) at about El. 879, and continued at a gentle slope to the river. As-built drawings also show a depth of approximately 30 feet to rock below these cohesive, in situ soils. Original dam construction (started 1935) included placement of fill, termed rolled embankment in project as-built drawings, over these in situ soils to current elevations. Rolled embankment was placed to a 1V:1.5H slope from the top of the right abutment (El. 933.7), to the middle of Monolith 6 at El. 885. Two 9.5 foot wide berms interrupt the slope at El. 918.3 and El. 902. Therefore, about 18-20 feet of rolled embankment fill was placed in the right abutment area.

Due to a landslide in the upstream right abutment during construction, in situ soils were removed to rock and replaced with rolled embankment. Twenty to thirty feet of rock fill consisting of sandstone from an upstream quarry was placed over the rolled embankment to current elevations. The original ground surface of the left abutment sloped riverward at about 1V:3H. Approximately 20 feet of in situ soil was removed and graded to 1:2 and 1:3 slopes with benches at El. 902 and El. 885. Immediately downstream and upstream of the dam monoliths starting at the top of rock and monolith contact point and rising at a

1:1 slope to the existing ground, is of compacted backfill. An exception to this is uncompacted backfill on the downstream side of monoliths 20 and 21.

Based on as-built drawings and confirmed by 2004 boring data, the soil column along the downstream right abutment at Monolith 5 consists of in situ soils from the top of rock approximate El. 867 to El. 883, and rolled embankment from El. 883 to El. 902. Upstream of Monolith 5 consists of US north abutment slide backfill from top of rock to El. 883, rolled embankment from El. 883 to El. 894, and rock fill from El. 894 to El. 915. Compacted backfill is located immediately upstream and downstream of the dam at the right abutment from the top of rock to the existing ground surface. Along the left abutment at Monolith 17, the soil column is believed to consist of in situ soils from top of rock to the ground surface (El. 886). Borings drilled in 2004 in the left abutment downstream of the dam (C-04-8, 9, and 11) were located in areas of uncompacted backfill. See Exhibit II-5 for sections showing soil stratigraphies at Monoliths 5 and 17. Engineering properties for all of these materials were needed for stability analyses and for evaluating construction alternatives. Table II-5 below lists selected engineering properties for all these soils.

Table II-5 – SOIL PROPERTIES

Material	K_o	Short-term Condition				Long-term Condition			
		γ_{sat} (pcf)	γ_{mst} (pcf)	Φ (deg)	S_u (psf)	γ_{sat} (pcf)	γ_{mst} (pcf)	Φ (deg)	S_u (psf)
Rock Fill	0.45	130	120	35	0	130	120	35	0
*Compacted Backfill	0.45	125	120	35	0	125	120	35	0
Rolled Embankment	0.45	125	120	33	0	125	120	33	0
In situ soils	0.70	128	125	0	1500	128	125	31	0
+US North Abut. Slide Backfill	0.55	120	110	28	0	120	110	28	0
Uncompacted Backfill	0.60	125	120	0	800	125	120	30	0

* Compacted backfill is located adjacent to upstream and downstream sides of monoliths #5 & #17 and behind the right training and retaining walls.

+ See Periodic Inspection Report No. 1, Appendix IV, pg. 13, Section 8. Construction Notes.

6.2 Existing Soils

6.2.1 In Situ Soils

Borings C-04-5, C-04-5A, and C-04-6, located on the right abutment, show that soil samples taken below El. 883 generally contain 60-75% clays and silts, 10-25% sand, and

5-15% gravel, by weight. In situ soils found along the left abutment in boring C-04-10 generally contain 50-60% silt and clay, 15-20% sand, and 20-25% gravel, so they are generally classified as sandy clays with gravel.

These soils generally exhibit medium plasticity with liquid limits of 35-40% and plasticity indices of 21-23 (See Exhibit II-4 for Atterberg Limits test data). Penetration resistances observed during drilling are indicative of a stiff consistency (N-values of 8-20 blows/foot). N-values within the anticipated in situ soil layer in borings C-04-5A, 5, 6, and 10 averaged 11 to 16 blows/foot.

As noted previously, no undisturbed sampling was performed. Published correlations were reviewed to obtain approximations of the at-rest earth pressure coefficient and undrained shear strength parameter. These correlations are shown in Tables II-2 and II-3 and were used to select the parameters shown in Table II-5. Engineering judgment and past testing results for similar soils from other District projects was used to determine the drained shear strength parameter.

Using Table II-2, in situ soil was assigned an at-rest earth pressure coefficient (K_0) of 0.70. This is considered reasonable because although consolidation testing was not performed it is estimated that these soils, which fall under the lean clay (CL) category in the table, are overconsolidated. An overconsolidated soil is defined as a soil whose present effective overburden pressure is less than that which the soil experienced in the past. Since overlying soils were removed from the present in situ soils of the left abutment during construction, these soils are considered overconsolidated. Due to a landslide during construction, the in situ soils upstream of the right abutment were removed and backfilled with granular soils. The downstream right abutment in situ soils were covered with about 20 feet of granular rolled embankment during construction. Project in situ soils are estimated to fall between an overconsolidation ratio (OCR) of 1 and 2 in Table II-2. Using Table II-2, a lean clay with an OCR midway between 1 and 2 would have a value of $K_0=0.70$.

As noted previously, N-values for in situ soils averaged 11 to 16 blows/foot.; 11 blows/foot is roughly in the middle of the N-value range of stiff clay in Table II-3. As a result, in situ soil was assigned an undrained shear strength value of 1500 psf, which is midpoint in the range of 1000 to 2000 psf as shown in Table II-3 for stiff clay.

6.2.2 Compacted Backfill

Compacted backfill was placed between excavated soil and the dam monoliths on both their upstream and downstream sides, with the exception of the downstream side of monoliths 20 and 21. Compacted backfill was also placed between excavated rock and structural concrete for the right retaining (upstream) and training (downstream) walls.

As previously noted, no project specifications are available. As a result, little is known of the composition and requirements for compacted backfill. The 2004 borings (C-04-5A and C-04-6) show that in areas of compacted backfill, the soils typically contain approximately 15% fine-grained materials (% passing the #200 sieve) with wide

variations in sand and gravel proportions. The natural moisture contents of these soils ranged from 5 to 12%. Based on 2004 boring data, compacted backfill is characterized by about 15% fines, whereas in situ soils contain about 50-70% of fines. Compacted backfill is generally classified as silty sands and gravels.

Areas of compacted backfill in borings C-04-5A and C-04-6, averaged N-values of 20-25 blows/foot, correlating to a medium dense granular soil in Table II-4. By using Table II-4, compacted backfill with average N-value of 20 blows/foot was assigned an internal angle of friction (Φ) of 35° and moist unit weight of 120 pcf, which correspond to Φ and unit weight values midway between N-values of 10 and 30 blows/foot. Effective shear strength parameters and unit weights for compacted backfill and rolled embankment were estimated to be relatively similar based on blow counts (N-values) and gradations. Table II-5 lists all selected parameters for compacted backfill soils.

6.2.3 Rolled Embankment

Rolled embankment was placed over in situ soils in the downstream right abutment and upstream left abutment, as well as over the slide backfill in the upstream right (north) abutment. The exact composition and compaction placement procedures for rolled embankment are unknown. 2004 borings show that areas of rolled embankment soils typically contain approximately 15% of fine grained materials and varying amounts of sand and gravel percentages. Rolled embankment is generally classified as silty sands and gravels. Areas of rolled embankment in borings C-04-5 and 5A averaged 16 blows/foot. An area of rolled embankment in boring C-04-4 shows about 5% fines and average of 20-25 blows/foot. These correlate to a medium dense granular soil and though similar in gradation to compacted backfill they were assigned lower strength values due to lower blows counts. By using Table II-4, rolled embankment with average N-value of 16 blows/foot was assigned an internal angle of friction (Φ) of 33° which corresponds to a Φ value roughly one third of the way between the Φ value range of 30° to 40° associated with the N-values range of 10 to 30 blows/foot.

6.2.4 Upstream (US) North Abutment Slide Backfill

As-built construction notes, contained in Periodic Inspection Report No. 1, state that due to heavy rains during construction a slide developed in the right upstream abutment. This material was removed to rock and replaced with “rolled embankment.” This slide backfill is approximately 10 feet thick, and lies below 10 to 30 feet of rock fill. This area has been differentiated from rolled embankment due to significantly lower blow counts (N-values) encountered during 2004 drilling. There is no information available in regards to the placement procedures for this material.

Blow counts in boring C-04-14 in the area of this slide backfill averaged 8 blows/foot. This boring was located behind the upstream right retaining wall. Upstream north abutment slide backfill contains less than 15% fines and can be characterized as poorly graded sands with gravel. By using Table II-4, US north abutment backfill with average N-value of 6 blows/foot was assigned an internal angle of friction (Φ) of 28° which

corresponds to the lower end of the blow count range for loose granular soils (N-value= 4 to 10).

6.2.5 Rock Fill

Rock fill was placed over slide backfill to the existing grade in the upstream right abutment, most likely due to steep slope geometry and prior slope failure during construction. The rock fill consists of sandstone and limestone from required excavation and ranges from 10 to 30 feet in thickness. Blow counts in the area of rock fill varied, but typically averaged greater than 50 blows/foot. Its assigned shear strength value was based on typical friction angles for angular rock.

6.2.6 Uncompacted Backfill

Uncompacted backfill was placed between excavated soil and the left training wall and between excavated soil and structural concrete on the downstream side of Monoliths 20 and 21. This material was encountered in borings C-04-9 and C-04-11, and generally consisted of 50-60% fines (silts and clays) and N-values that averaged 6-8 blows/foot, correlating to a medium consistency. Uncompacted backfill is similar in soil classification to the in situ soils, and is generally characterized as sandy clays with gravel.

By using Table II-3, uncompacted backfill with N-value of 6 blow/foot was assigned an undrained shear strength value of 800 psf, which roughly midpoint in the range of 500 to 1000 psf as shown in Table II-3 for medium consistency (N-value= 4 to 8). Using Table II-2, uncompacted backfill was assigned an at-rest earth pressure coefficient (K_o) of 0.60, corresponding to lean clay (CL) with overconsolidation ratio (OCR) of 1. Table II-5 lists all selected parameters for uncompacted backfill soils.

6.3 Groundwater Conditions

Groundwater levels found during the 2004 drilling program generally coincide with the river elevation just above the soil and bedrock interface, which rises in elevation with distance from the river. Groundwater readings were taken upon completion of each boring; 24-hours readings were recorded in about half of the borings. Installation of several piezometers to evaluate groundwater levels in the abutments is planned following proposed FY-07 undisturbed drilling.

7 Soil Design Considerations

7.1 General

Engineering properties of soils in both abutments were determined for use in stability analyses for the recommended plan. As stated previously, no shear strength testing was

performed on soil samples obtained during the 2004 drilling program. Engineering properties for all known soils at this project have been selected using 2004 drilling and testing data, published correlations involving SPT blow counts, and engineering judgment. At-rest earth pressure coefficients for use in structural analyses have been selected based on empirical relationships to shear strength parameters for granular soils, and engineering judgment for cohesive soils. Six (6) borings are proposed in FY-07 to obtain undisturbed soil samples for testing in order to better define soil strength parameters and stratigraphies necessary for completion of analyses during the design phase of this project.

7.2 Abutment Soil Stability

Fill soils placed just upstream and downstream of abutment monoliths enhance monolith stability. As a result, it is necessary to assess the potential for loss of these fills due to slope instability. Slope stability calculations have not been performed during this phase of the project because possible modification of the existing stilling basin and associated training walls which may affect the future abutment slope configurations have not been determined. These will be determined in the design phase following hydraulic physical modeling of the dam by the U.S. Army Engineer Research and Development Center's (ERDC) Coastal and Hydraulics Laboratory.

In reviewing the abutments soils, the following observations have been made:

- Abutment slopes have been stable since completion of construction, spanning a period of about 70 years.
- Abutment fill soils are generally pervious and are likely to provide adequate drainage to prevent slope failures during drawdown following high pools. Exposed impervious in situ soils located on the downstream left abutment are not believed to be pervious due to their percentage of fines (50-60%); however, downstream left abutment slopes are at a 1% grade from the top of the training/retaining wall to El. 885.5, 1V:4H to a berm at El. 902 and 1V:2H slope to the south end of the dam.
- The pool of record (El. 907.35) and subsequent drawdown did not cause slope failures in these areas.
- The upstream right abutment has the steepest slope, but contains approximately 20 feet of rock fill and is buttressed by a retaining wall founded on rock.

For these reasons, it is anticipated that the upstream abutment slopes are stable. However, data from proposed hydraulic physical modeling at ERDC's Coastal and Hydraulics Laboratory is needed to define hydraulic conditions during a PMF level event. Abutment soil stability analyses will be completed during the design phase.

7.3 Parapet Wall

Due to pervious subsurface conditions in the upstream right abutment area, underseepage concerns with the proposed upstream parapet wall along its alignment surrounding the

parking area were evaluated. Due to the size and density of these granular soils (poorly graded sands and gravels), piping of material and consequential instability of the wall foundation is not a concern, and thus formal seepage calculations were not performed. A toe drain is proposed to intercept potential seepage and decrease uplift pressures that may damage the asphalt pavement on the dry side of the wall.

The proposed parapet wall on the right abutment is a typical I-wall except for the sub grade portion which is proposed to be founded on drilled H-piles encased in concrete spaced on 6 feet centers. The use of sheet piling may not be practical in this area due to the dense granular soils. Blow counts from boring C-04-4 located near the center of the adjacent parking area ranged from 18-39 blows/foot from the ground surface to a depth of 15 feet and averaged 8 blows/foot from a depth of 15 feet to bedrock.

The proposed parapet wall on left abutment follows along the upstream side of abutment monoliths before heading upstream, paralleling the existing abandoned railway line/walking trail. The elevation of the trail in this area is roughly El. 934 and thus the wall height will be about 4 feet above the existing ground surface. A handicap access ramp is proposed to allow access along the trail where the I-wall crosses to tie into high ground. The random fill required for construction of this ramp will be purchased from a commercial source or possibly onsite excavations.

Borings C-04-13 and C-04-14 drilled along the southeast edge of the trail at the end of the left abutment showed fairly shallow depths to bedrock. An approximate 5-foot thick stratum of heavily weathered shale was encountered at depths of 14 feet and 13 feet in borings C-04-13 and C-04-14, respectively. This is underlain by hard sandstone that extends to approximately El. 890. The overburden in these holes is predominately silty clays with sands and gravels, and exhibited an average N-value of 8 blows/foot correlating to medium stiff to stiff in terms of soil consistency. Underseepage does not pose a threat due to the short wall height and depth of sheet piling for the I-wall. Slope stability was not a concern as the ground slopes at approximate 1V:5H toward the river for about 20 feet from the wall centerline. From there the slope changes to 1V:2.5H. As stated previously, analyses will be performed during the design phase to verify stability.

7.4 State Route 800 Gate Closure

Foundation conditions for the proposed State Route 800 gate closure are unknown at this time. Conditions must be determined to properly design the abutment monoliths and sill as well as prepare plans and specifications. Borings C-04-1 and C-04-2, drilled about 25 feet to the north of the roadway centerline, indicate a relatively shallow bedrock depth beneath the road surface. However, project as-built drawings show that rock dips steeply toward the river. Drilling consisting of overburden sampling and rock coring is planned for the gate closure monolith locations.

7.5 Streambank Erosion Protection

7.5.1 Stone Slope Protection

Bank protection is needed to protect park facilities, SR 800 and abutments against erosion from high flow velocities during significant high water events, which could result in slope instability. High flow velocities during a potential PMF event could undermine the stability of downstream abutment soils which provide resistance to sliding of adjacent monoliths.

The feasibility-level design is to replace the existing riverbank stone slope protection downstream of the stilling basin with graded 36-inch top size stone since the existing stone is estimated to be undersized for a PMF event. This conventional stone slope protection will consist of excavation of existing stone and soil to a stable geometry, installation of a geotextile, and then placement of stone to a thickness of approximately one and a half times its top size or approximately 4.5 feet. The stone shall be keyed in at both the toe and top of the protection and end transitions to prevent outflanking.

As stated previously, hydraulic conditions during a PMF event are unknown at this time but will be determined following hydraulic modeling using scaled physical replicas of the dam by ERDC. Extent and technique of bank treatment will be verified during the design phase. See Appendix C, Tab I, Hydrology and Hydraulics for more detail.

7.5.2 Environmental Design Consideration

The proposed project lies within the range of the clubshell mussel (*Pleurobema clava*), a Federally-listed endangered species. Existence of mussel populations are unknown at this time but will be determined prior to construction following commissioned mussel surveys in partnership with the U.S. Fish and Wildlife Service. Alternative approaches to bank protection are available that would not significantly affect the feasibility or cost assumptions of this report should mussel populations affect the current design. As stated previously, extent and technique of bank treatment will be verified during the design phase. See Section 2.5.3 (Wildlife and Endangered Species) of the main report for more detail.

8 Uplift

The original design assumed uplift of full reservoir head at the heel varying linearly to full tail water head at the toe, but the uplift pressure was assumed to be acting on only 40% of the base. Current guidance assumes uplift acts over 100% of the base and the only reduction allowed is at the line of the drains, called drain efficiency. Drain efficiency represents a reduction in uplift pressures acting upon the base of the dam due to the interception of charged discontinuities by the drains. Current Corps guidance for dams with drains assumes a bi-linear distribution, full reservoir head at the heel varying linearly to a percent reduction at the line of the drains then to full tail water head at the toe (see Figure II-1).




Figure II-1 (from EM 1110-2-2100)

For the 1977 stability reanalysis, the drains at Dover were assumed to be nonfunctional, for this current Evaluation Report it was decided to take a fresh look at the drainage curtain and drain efficiency.

The reduction in uplift due to the drainage curtain (drain efficiency) is based on many factors, some of these include: top of drain elevation, drain spacing, drain depth, and angle of the drain. The following paragraphs compare and contrast the drains at Dover Dam to the ideal, modern drainage system design.

A modern concrete gravity dam is typically designed with two galleries, an upper gallery to facilitate operation of the dam's gates, etc., and a lower inspection (or "drainage" or "grouting") gallery from which the upstream grout curtain and the downstream drainage curtain are constructed, and where uplift pressures are monitored through instrumentation. The ideal drainage curtain would be located in an inspection gallery near the upstream face, and as near the rock surface (in elevation) as feasible to provide the maximum reduction in overall uplift. By locating the inspection gallery at the lowest possible elevation, the drains are more permeable, and by locating it near the upstream face, the reduction in uplift provided by the drains is optimized. Dover Dam has 22 drains located in the Dam's single (operations) gallery in monoliths 4 through 15 with top

of drain elevations of 882.25 and 886.25 (see Table II-6.). It should be noted that drain 11 was not drilled into bedrock. The drains in monoliths 7 through 15 intercept bedrock on the downstream bottom of the concrete key, and their top elevations are 53.5 feet above bedrock. Monoliths 4 through 6 (which have no key) have top of drain elevations that average 29.5 feet above bedrock. Due to their location high up in the operations gallery, the drains have a greatly increased head to overcome to reduce uplift. Also, the drains have not been well maintained, in that they have only been cleaned once, during the flood of 2005, by high pressure jetting. The uplift cells were also cleaned at this time in a similar fashion. The uplift-cell data at Dover Dam is questionable. The earliest available records of uplift-cells readings are from a flood event of (elevation 905.0) July 12 of 1969, some 28 years after the dam was constructed. Up until January of 2005 when Dover Dam reached a pool of 907.3 (current pool of record) the 1969 flood was the pool of record. During the 1969 flood, uplift cell number 8 stayed dry, but during the 2005 flood it gave readings near 100% theoretical uplift, and, after being cleaned during the 2005 flood event, this cell gave readings above 100% theoretical uplift. Uplift cells 4 and 5 both showed higher readings in 2005 than in 1969 but not as dramatic. Uplift pressure plots from the 1969 and 2005 flood can be found in Exhibit II-7.

Drains in modern concrete gravity dams are from 3 to 5 inches in diameter, typically spaced at 10-foot intervals, with depths up to 70% of the height of the dam, and are drilled at a slight angle (typically downstream) to increase the likelihood of intercepting near-vertical, open bedrock joints—the most common conduits to the reservoir in relatively flat-lying sedimentary bedrock strata. The drains at Dover are vertical, and are therefore much less likely to intercept vertical bedrock joints. Dover's drains have an average spacing of 20.1 feet and a maximum spacing (between drains 1 and 2) of 35.8 feet; on average, the drains are two times the currently recommended spacing, and in some areas over three times.

Drains must be well maintained to ensure continued functionality. In a modern dam, a maintenance plan would be developed to clean the drains by over-reaming or re-drilling to ensure elimination of mineral crusts, algal slimes, and other blocking materials on a regular interval. The drains at Dover are not considered “well maintained” because they have only been cleaned once in the dams life time, in 2005 (by high pressure jetting), but not followed up with a down-hole imagery to confirm the results.

Drain efficiency. Funding has not been made available to devise or execute an investigative program to estimate the drains' actual contribution to uplift reduction over the base of the dam. If funding was made available, the task would be difficult because the drains at Dover are (elevation 882 and 886) 17 to 21 feet higher than the typical pool elevation of 865.0 and therefore they don't start functioning as drains until the pool is higher than their top elevation. Maintenance of the drains is discussed above. Also, no down-hole imagery has been run down the drains to determine the actual degree to which incrustation has impacted the drains' intersections with bedrock discontinuities. However, as stated earlier the drains were cleaned using high pressure water-jetting in 2005, and 9 of the drains flowed during the pool of record. Therefore, it was deemed prudent to assume that the drains provide some minimal uplift reduction. For this phase

of study, a 5% drain efficiency for each drain has been chosen for use in the structural analyses; therefore a monolith with two (2) drains would have 10% drain efficiency, and so on.

Monolith	Drain Number	Top of Drain Elevation	Concrete to Rock Contact Elevation	Drain Hole Depth From Top of Drain (feet)	Drain in Concrete (feet)	Drain in Rock (feet)
4	1	882.25	865	56.8	17.25	39.55
5	2	882.25	848	68.6	34.25	34.35
6	3	882.25	849	69.5	33.25	36.25
	4	882.25	830	69.8	52.25	17.55
7	5	882.25	830	69.7	52.25	17.45
	6	882.25	830	70.5	52.25	18.25
8	7	882.25	830	70.1	52.25	17.85
	8	882.25	830	69.1	52.25	16.85
9	9	882.25	830	69.9	52.25	17.65
10	10	886.25	830	72.7	56.25	16.45
	11	886.25	830	50.5	56.25	-5.75
	12	886.25	830	73.8	56.25	17.55
11	13	886.25	830	73.0	56.25	16.75
	14	886.25	830	73.7	56.25	17.45
12	15	886.25	830	71.7	56.25	15.45
	16	886.25	830	71.5	56.25	15.25
13	17	886.25	835	70.0	51.25	18.75
	18	886.25	835	67.5	51.25	16.25
14	19	886.25	835	74.1	51.25	22.85
	20	886.25	835	71.8	51.25	20.55
15	21	886.25	835	70.0	51.25	18.75
	22	886.25	835	68.5	51.25	17.25

Table II-6 Foundation Drain Data

9 Effect of Anchors on Uplift

The remediation at Dover Dam will require significant anchoring in the spillway and apron for stabilization. The procedure of anchoring will introduce grout into the foundation in quantities that cannot be predetermined. This grout in the foundation can, if added at the right location, help the grout curtain reduce the permeability at the heel, but if injected at or downstream of the drains, such as the multiple rows of anchors needed in the apron, can cause a build up of pressure under the foundation. For the level of study appropriate for this Evaluation Report the drain efficiency will be reduced to 0 percent in those monoliths with anchored aprons, but as part of the Design Document Report, (DDR) the anchoring system of each monolith will be evaluated and the drain efficiency reduced, if deemed appropriate. The anchoring system will be evaluated based on the following parameters:

- 1) Number of anchors per monolith
- 2) Location in the foundation of each anchor

- 3) Diameter of bore hole
- 4) Grout penetration
- 5) Monolith width

For design purposes, the monolith foundations will be divided into zones depending upon the degree to which grouted anchors would influence the drain efficiency in that particular area of the foundation. The zones are depicted in Exhibit No. 10. Grout penetration around the anchors is estimated at 8 inches. A drain efficiency reduction factor is calculated for each zone based on the number of anchors, bore hole diameter, grout penetration, and monolith width. Subsequently these per zone reductions (if any) are combined to determine the total reduction for the entire monolith. This percentage value is then applied to the originally assumed drain efficiency to establish the appropriate reduced total efficiency for the monolith.

10 Breach Assumptions

Some of the hydraulics analyses performed for this study required assumptions of the size of breach which might occur during failure. This depends upon several factors: the founding lithology; the depth of the critical sliding plane below the concrete-rock contact, the lateral continuity of open bedding planes and structural discontinuities, and their likelihood of intersection with adversely oriented joints. Based upon the current understanding of the bedrock foundation, it was determined that sliding would occur in the spillway section and could initiate over as little as two to three monoliths, but would quickly spread to include the total width of the spillway due to the highly erodible nature of the shale and siltstone below the limestone. The shale has an average RQD of 51 (see Exhibit II-6

11 Anchor Designs

The anchors needed for stabilizing Dover Dam range up to 61-strand. The project's design currently calls for twenty seven (27) multi-strand anchors and one hundred forty (140) 1-3/8" bar anchors. These anchors are only needed in the spillway monoliths and the apron.

11.1 Corrosion Protection

Because of the serious consequences of failure and the expected service life (50+ years), corrosion protection for the anchors will be Class I, Encapsulated Tendons, as described in the 2004 Post-Tensioning Institute, RECOMMENDATIONS FOR PRESTRESSED ROCK AND SOIL ANCHORS. The tendons shall be 0.6" diameter, 7-wire pre-stressed bare strand throughout the bond length with corrosion inhibiting grease and

polypropylene extruded sheathing throughout the stressing length. The anchors shall be fully encapsulated with corrugated HDPE. The 10" corrugated HDPE shall be 90 mil minimum thickness, and all smaller diameter corrugated HDPE to be used for the anchors shall be 60 mil minimum thickness.

11.2 Anchor Depth Calculation

"The anchor depth is taken as the anchor length necessary to develop the anchor force required for stability" (EM 1110-1-2908, 30 Nov 94). Simply stated this is the depth below the failure plane at which the potential rock mass failure cones start. For the Dover DSA Project these cones are assumed to start at the mid-point of the bond zone. EM 1110-1-2908 gives multiple formulas for calculating anchor depths, based on the rock mass conditions. There are two formulas given for competent rock that incorporate rock mass cohesion, a single anchor in competent rock (formula 9-1) and a row of anchors in competent rock (formula 9-2). There are three formulas given for fractured rock that incorporate the weight of the rock mass, a single anchor in fractured rock (formula 9-4), and a row of anchors in fractured rock (formula 9-5). Regardless of the condition of the rock mass, there is only one formula for multiple rows of anchors (formula 9-3) and it uses only the weight of the rock mass for the resisting force. The anchors on the Dover DSA Project will be designed on a monolith-by-monolith basis. All of the anchored monoliths will have multiple rows of anchors. Lessons learned from previous anchoring projects show that using formula 9-3 can give anchor depths that are unreasonably long and extremely difficult to construct (see Bluestone Dam example, length 535 feet, in figure II-2). Accepting the lengths required by this formula, the hole alignment specifications would have to be written such that the bore hole could only vary 0.75 of a foot for every 100 feet drilled to ensure that the borings do not intercept. The design team therefore decided to look at other methods of calculating anchor depth which would incorporate only the weight of the rock mass as the resisting force. The chosen methodology, described below and previously applied to the Bluestone DSA project, will be used for the Dover Dam anchors. Stability is analyzed for each monolith individually; therefore, the anchors can be evaluated as a system, on a monolith by monolith basis. A system of anchors can be further broken out into groups when the system of anchors performs more than one function, such as 45 degree anchors to resist sliding and vertical anchors for overturning.




Figure II-2 (an example of anchor embedment calculated for the Bluestone Dam DSA project using EM 1110-1-2908, 30 Nov 94, formula 9-3, the 45 degree anchors have a total length of 535 feet)

Embedment depths can be designed for a group of anchors by totaling the forces within a group, and using formula 9-4 (single anchor in fractured rock) for each group. Using this approach, the Bluestone monolith depicted in figure II-2 would have an embedment length of only 40 feet below the failure plane for the vertical anchors and 66 feet for the 45 degree anchors. The embedment lengths are checked by creating a 3-D Micro Station drawing of the cones and ensuring that the weight of the cones, using the buoyant weight of rock, equals the force the anchors. The tips of the cones start at the midpoint of the bond zones and go out at 45 degree angles, the cones are constrained at monolith boundaries and failure planes. Also, the 45 degree anchor cones, are stopped at the end of the monolith on the downstream side (see Figure II-3). The volumes are calculated by merging the cones in Micro Station. The resisting weight of the cones is calculated by multiplying the volume by the buoyant weight of rock. When looking at multiple groups of anchors, the cones from each group can and will often overlap, the rock in this overlap

area can only be used for one group of anchors and must be subtracted from the other group. The design goal is that the weight of the cones will be at least 1.3 times the force they are opposing. For Dover Dam monolith 7 this methodology gives a resisting weight of 1.8 times the force of the vertical anchors and 2.7 times the force of the 45 degree anchors.




Figure II-3

11.3 Bond Length Calculation

Anchor bond length calculations concentrate on the grout to rock bond and not the grout to tendon bond. According to EM 1110-1-2908, 30 Nov 94: "Experience and numerous pull-out tests have shown that the bond developed between the anchor and the grout is

typically twice that developed between the grout and the rock.” Bond lengths are calculated by using formula 9-6a from EM 1110-1-2908, and vary depending upon hole diameter, grout-to-rock bond strength, and actual loading to be applied. The working bond strength is a weighted average calculated from the material just above and below the embedment depth. At this time no small scale anchor bond pull out tests have been conducted. The grout-to-rock bond strength used for this level of design comes from published strengths in the PTI manual and engineering judgment. The diameter of the hole is dependent on the number of strands and the type of corrosion protection each anchor uses. Bond lengths will be designed as appropriate using formula 9-6a, but the design will ensure that the minimum bond length for anchors is in accordance with the PTI manual recommendations of 15 feet for strand and 10 feet for bars.

12 Future Explorations and Investigations

12.1 Rock

To complete a Detailed Design Report (DDR) additional subsurface exploration and lab testing is needed to adequately characterize the valley bottom, both at the heel and in the apron and apron toe also concrete samples from the dam will be needed, so accurate concrete shear strengths can be assign to the reinforced key and the mass concrete of the dam . Any new features such as anchors, downstream cutoff walls and gate closures that may be a part of the Dover DSA project will also be added to the exploration and testing program.

12.2 Soil

Additional subsurface information is needed to adequately characterize soil stratigraphies and better define the engineering properties of these soils. The designed compositions and placement procedures of in situ project soils and fills are unknown due to limited as-built drawings and no project specifications. The 2004 boring locations were such that they did not provide adequate data for in situ soils and compacted backfill of the downstream left abutment area. All borings performed downstream of the left abutment (C-04-8, 9, and 11) were performed in uncompacted backfill as denoted in as-built drawings. Boring C-04-11 located just downstream of Monolith 20, is in an area labeled as uncompacted backfill on as-built drawings. Both borings C-04-8 and 9 are located in uncompacted backfill behind the left downstream retaining wall. Six (6) borings are proposed in FY-07 to obtain undisturbed soil samples for testing. Following drilling, piezometers will be installed in several holes to monitor groundwater conditions in the downstream abutments.

12.3 Seismic

A site and structure specific seismic evaluation will be completed as part of the DDR.

EXHIBIT II-1

BORING LOCATION PLAN

EXHIBIT II-2

ROCK PROFILES AND SECTIONS



number:
EXH 2
Sheet 1 of

This geological cross-section, titled "MONOLITH #5 (M-5) - SECTION STA. 3+26", illustrates the subsurface geology of a structure. The vertical axis represents elevation in feet, ranging from 780 to 910. The horizontal axis represents stationing, ranging from 110 to 100 on the left and 10 to 100 on the right, with a central "AXIS" line. A "FLOW" arrow points to the right above the structure.

The structure, labeled "MONOLITH #5", is shown with a "ORIGINAL ROCK LINE" and a "LIMESTONE FOUNDATION". The rock layers are identified as follows:

- SHALE**: gray, silty, soft to mod. hard, laminated, slightly effervescent toward bottom.
- LIMESTONE**: dark gray, hard to very hard, fossiliferous.
- SHALE**: dark gray, soft, carbonaceous, highly fissile.
- COAL**: black, boney coal.
- SILTSTONE/SANDY**: gray, mod. hard, sandy in zones, thin bedded.
- SILTSTONE**: gray, mod. hard, laminated, shaly, effervescent.
- SILTSTONE/SANDY**: light gray, hard, crossbedded, med. to coarse grained, micaceous.

Key points and measurements include:

- Point A**: Located at the top of the shale layer on the left side of the axis.
- Point B1**: Located at the top of the limestone layer on the left side of the axis.
- Point B2**: Located at the top of the shale layer on the left side of the axis.
- Point B3**: Located at the top of the coal layer on the left side of the axis.
- Point D1**: Located at the top of the limestone layer on the right side of the axis.
- Point D2**: Located at the top of the shale layer on the right side of the axis.
- Point D3**: Located at the top of the shale layer on the right side of the axis.
- Angles**: 1.61°, 35.50°, and 38.80° are indicated for the rock layers on the right side of the axis.
- Stationing**: The structure is located at station 3+26.
- Elevations**: The structure's elevation is 882.3 feet.
- Coordinates**: The structure's coordinates are N 326657.03, E 2302051.77.
- Other Labels**: "C-04-7", "C-04-6", "ORIGINAL ROCK LINE", "MONOLITH #5", "LIMESTONE FOUNDATION", "FLOW", "AXIS", "D1", "D2", "D3", "B1", "B2", "B3", "A", "SHALE", "LIMESTONE", "COAL", "SILTSTONE/SANDY", "SILTSTONE".

U.S. ARMY CORPS OF ENGINEERS HUNTINGTON DISTRICT HUNTINGTON, WEST VIRGINIA	Designed by:	Date:	Rev.
	Dwn by:	Design file no.	
	Old by:	Drawing code:	
	Reviewed by:		
	Submitted by:	File label (enclos. dgm)	

	Limestone	Shale	Siltstone	Siltstone/Sandy			
WORKING BOND STRENGTH	85 psi	50 psi	90 psi	95 psi			
ALLOWABLE BEARING CAPACITY	2191 psi	300 psi	873 psi	829 psi			
ELASTIC MODULUS (x 10 ⁶)	24.74	1.750	2.750	2.970			
UNIT WEIGHT	168.5 pcf	161.5 pcf	165.8 pcf	159.7 pcf			





EXHIBIT II-3

GEOLOGY AND SOILS LEGEND

Including Identification and Description

Use grain-size curve in identifying the soil

Comparing Soils of Equal Liquid Limit: Toughness and Dry Strength increase with increasing Plasticity Index.

PLASTICITY INDEX

LIQUID LIMIT

PLASTICITY CHART
For laboratory classification of unconsolidated soils

FIELD IDENTIFICATION PROCEDURES FOR FINE-GRAINED SOILS OR FRACTIONS

are to be performed on the minus No. 40 sieve size particles approximately 1/64

After removing particles larger than No. 40 sieve size, prepare a pot of moist soil with a volume of about one-half cubic inch. Add enough water if necessary to make the soil moist. Place the soil in the open part of one hand and shake horizontally, striking vigorously against the other hand several times. A positive reaction consists of a strong adherence of the soil to the palm of the hand. If the soil is very sandy, consistency and becomes glossy. When the sample is squeezed between the fingers, the water and gloss disappear from the surface, the soil stiffens, and finally cracks or crumbles. The rapidity of appearance of water during shaking of it is characteristic during squeezing action in identifying the character of the fines in a soil. Very fine clean sands give the quickest and most distinct reaction whereas silty sands and silts with some inorganic silts, such as a typical rock flour show a moderately quick reaction.

After removing particles larger than No. 40 sieve size, mold a portion of soil to the consistency of putty, adding water, if necessary. Allow the pot to dry completely by oven, sun, or air drying, and then test its strength by breaking or crumbling between the fingers. This strength is a measure of the character and quantity of the colloidal fraction contained in the soil. The dry strength increases with increasing plasticity.



















After removing particles larger than the No. 40 sieve size, a specimen of soil about one-half inch in diameter is rolled into a ball. If the soil is too dry to roll, it is moistened. If it is sticky, the specimen should be spread in a thin layer and allowed to lose some moisture by evaporation. Then the specimen is rolled out by hand on a smooth surface or between the palms of a thick rubber glove. The specimen is rolled until it is smooth and rounded. Repeatedly. During this manipulation the moisture content is gradually reduced and the specimen stiffens, finally loses its plasticity, and crumbles when the plastic limit is reached. The thread in the thread-needle test process should be bumped together and a slight kneading action continued until the lump crumbles.

The tougher the thread near the plastic limit and the stiffer the lump when it finally crumbles, the higher the potential plasticity of the soil. The thread-needle test is a qualitative test. Plastic limit and quick loss of coherence of the lump below the plastic limit indicate either inorganic clay of low plasticity, or materials such as kaolin-type clays and organic clays which can be bent into a thread.

Highly organic clays have a very weak and spongy feel at the plastic limit.

ADDRESS INFORMATION

	mol.	moll'd
	msl.	moist
	mix.	matrix
	n.	near
s)	nod.	nodule(s)
al)	num.	numerous
	o.	open
	od.	odor
	occ.	occasionally
	occu.	occurring
	org.	organic
	pa.	par(ing)s
	pari.	particle(s)
	%	percent(age)
	pi.	piece
	pl.	plastic
	pl	plastic limi
	pbb.	pebbles)
	pk	
	pki.	pocket(s)
	pil.	pill(ed)ing
	pn.	planet(s)
	po.	porous
usions	por.	por(ill)y
ed	pyr.	pyrite(ic)
s	q.	quor(z)(ilic)
	r.	red(dish)
	ro.	rock(s)
	rol.	roll(ed)
	rou.	round(ed)
	ri.	root(s)(iel)
	s.	soil
(ions)	ss	spoil spoon
	so.	sandy
	sol.	saturated
	scol.	scattered
	se.	seams
	sev.	severely
	sevr.	several
	sh.	shaly
	she.	shells
	sil.	siliceous
	sl.	silly
	slik.	slickensided
	sm.	smolt
	so.	some
	sol.	solution
	sio.	ston(ed)
	sif.	stiff
	siks.	streak(s)

E	YEAR	HOLE NO.	DESIGNATION
-	98	52	 Core hole in bedrock
-	98	31	 Disturbed sample boring
-	98	69	 Boring with disturbed sampling in soil and coring in bedrock.
-	98	31	 Undisturbed sample boring
			 Core hole in bedrock, hydraulic pressure tested
			 Indicates angle boring and direction
			 Boring with Piezometer
			 Proposed Exploration
-	98	15	 Test Pit in overburden
-	98	6 - 135	 Test Trench in overburden (TT-98-6), soils classified at stationing as shown (135 feet)
-	98	39	 Undisturbed sample boring with Piezometer
			 Disturbed Sample Boring with Piezometer
			 Washbored
			 Cone Penetrometer Hole
			 Boring with Inclinator
			 Boring with disturbed sampling in soil and coring in bedrock, with a Piezometer.
			 Boring with disturbed sampling in soil and coring in bedrock, and hydraulic pressure tested.
			 Boring with disturbed sampling in soil and coring in bedrock, hydraulic pressure tested, with a Piezometer.

DEGREE OR DEGREE PROGRAM

		BROKEN OR FRACTURED CORE
	Severely Broken	Broken core pieces can not be reconstructed, gravel-sized pieces, core loss common
erife	Moderately Broken	Broken core pieces can be reconstructed with some difficulty
	Slightly Broken	Broken core pieces can be reconstructed easily
		DEGREE OF WEATHERING
	Unweathered	No evidence of any chemical or mechanical alteration
	Slightly Weathered	Slight discoloration on surface, slight alteration along discontinuities, less than 10% of the rock volume altered
ck	Moderately Weathered	Discoloring evident, surface pitted and altered with alteration penetrating well below rock surfaces, weathering "halos" evident, 10% to 50% of the rock altered
	Highly Weathered	Entire mass discolored, alteration pervading nearly all of the rock with some pockets of slightly weathered rock noticeable, some minerals leached away
	Decomposed	Rock reduced to a soil with relict rock texture, generally molded and crumbled by hand
		DISCONTINUITY SURFACE
	Very Rough	Near vertical ridges occur on the discontinuity surface
	Rough	Some ridges are evident; asperities are clearly visible and discontinuity surface feels very abrasive
	Slightly Rough	Asperities on the discontinuity surface are distinguishable and can be felt
duction	Smooth	Surface appears smooth and feels so to the touch
	Slickensided	Visual evidence of polishing exists
on	Planar	Flat shaped discontinuity surface
	Irregular	Undulant or unevenly shaped discontinuity surface

late Precambrian-aged Jacobsville Sandstone Formation. For engineering purposes this formation has three members include: Hard Sandstone, Moderately Hard Sandstone, Weathered Sandstone and these are thinner seams of clay, claystone and shale.

light red or light purple with few light gray reduction spots, hard to very hard, fine to medium to thick bedded.

th numerous light gray reduction spots, moderately hard, fine to medium grained,

dark red with light gray reduction spots, soft to moderately hard, fine grained and thin bedded.

SEDIMENTARY SYMBOLS

- WEATHERED SANDSTONE	SH - SHALE	CON - CONCRETE
- SHALY SANDSTONE	CLS - CLAYSTONE	LS - LIMESTONE

[illegible]

US Army Corps
of Engineers
Huntington District

[illegible]

U.S. ARMY CORPS OF ENGINEERS HUNTINGTON DISTRICT HUNTINGTON, WEST VIRGINIA	Designed by: EC-G	Date:	Rev.:
	Des. by: DOP, DAM	Drawn by: SCL	Design file no.
	Reviewed by: AWK	Drawing code:	
	Submitted by:	File name:	B00LCL.dgn
		Plot date:	
		Plot time:	

**TUSCARAWAS RIVER
DOVER, OH
DOVER DAM
DAM SAFETY ASSURANCE**

Sheet
reference
number:
EXH 3
Sheet 1 of 1

EXHIBIT II-4

GRAPHIC LOGS AND BORINGS

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e.	BOX OR SAMPLE NO. f.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
862.3	20.0	CON	<p>CONCRETE: Natural gravel aggregate.</p> <p>Rounded 2 inch maximum diameter gravel.</p> <p>0.2' Zone of poorly cemented aggregate at 876.2 to 876.0.</p>			<p>100% Drill recovery in concrete Concrete retained for record see G-5 Boxes A&B</p>

HOLE NO. G-4

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 882.3		Hole No. G-4	
PROJECT Dover Dam Gallery			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 2 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
860.5	21.8	CON	CONCRETE: (Continued)			Began Coring
859.5	22.8		Top of Rock	Rec 100%		
		SH	SHALE: Silty, moderately hard dark gray, moderately to highly fissile with numerous fine, light gray sandy lenses. 0.5' unweathered, severely broken high angle fracture from 859.4'-858.9'.	Loss 0.0 Rec 100%	1	Good concrete to rock bond. Porting in Shale 0.05' below Concrete/Rock contact.
849.2	33.1			Loss 0.0 Rec 98%		
		LS	LIMESTONE: Hard, dark gray fossiliferous, thick bedded.	Loss 0.1 Rec 100%	2	
845.2	37.1			Loss 0.0		
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam Gallery

HOLE NO. G-4

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e.	BOX OR SAMPLE NO. f.	REMARKS 10 (drilling time, water loss, depth of weathering, etc., if significant) g
			CONCRETE: Natural, rounded gravel aggregate up to 3 inch maximum diameter.			<p>100% Drill recovery in concrete.</p> <p>Concrete cored and discarded from 882.3' to 851.5'.</p> <p>Concrete appeared to be satisfactory by visual observation with no loss recorded.</p>
862.3	20.0	CON				

HOLE NO. G-5

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 882.3		Hole No. G-5	
PROJECT Dover Dam Gallery			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 2 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			CONCRETE: (Continued)			
		CON				Concrete, see G-5, Box C 25' cold joint @ 854.1
851.5	30.8					Began Coring
				Rec 100%		
849.0	33.3		Top of Rock			Open at concrete to rock contact.
		LS	LIMESTONE: Hard, dark gray fossiliferous, medium to thick bedded. 0.8' unweathered, near vertical fracture 847.3 to 846.5 0.6' open, stained, high angle fracture 846.4 to 845.8 Open bedding plane with same grout coating at 845.8 0.2' open, low angle fracture with grout coating at 845.6 Gradational Contact at 849.0 (open contact with rock) next parting 847.0	Loss 0.0 Rec 96%		
844.5	37.8					
		SH	SHALE: Soft to moderately hard, clayey, very dark gray, highly fissile. Unweathered, low angle joint at 843.8 0.2' Broken zone along fracture with 0.2' loss at 842.4 to 842.0 Gradational contact between Shale and Siltstone.	Loss 0.2		
841.2	41.1					
		SLS	SILTSTONE: Moderately hard, gray, sandy in zones, thin bedded.	Rec 100% Loss 0.0		
840.1	42.2					
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam, Ohio

HOLE NO.
G-5

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam		HUNTINGTON DISTRICT		2 OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. If significant)
a	b	c	d	e	f	g
			CONCRETE: (Continued)			
		CON				
852.7	29.6		CONCRETE: Natural sediment aggregate, some vuggy zones.	Rec 100%		Began Coring
848.5	33.8		Top of Rock	Loss 0.0		Open at Contact (core spun) Next parting 848.4'
		LS	LIMESTONE: Hard, dark gray, fossiliferous, medium bedded.	Rec 96%	1	
843.8	38.5			Loss 0.2		
		SH	SHALE: Moderately hard to hard, dark gray, clayey, thin bedded, highly fissile. Fracture, open, planar, smooth from 843.0' to 842.7'. Vertical fracture, open, rough irregular from 842.2' to 842.1'	Rec 100%		
840.8	41.5					
		SLS	SILTSTONE: Moderately hard to hard, gray, thin bedded, with Shaly zones and zones of fine grained Sandstone. 0.4' Shale, clayey, dark gray at 838.5' to 838.1' 2.5' Sandstone, silty, at 838.1'	Loss 0.0		
838.3	44.0					

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam		HUNTINGTON DISIRICI		3		
OF 3 SHEETS						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
835.6	46.7	SLS	SILTSTONE: (Continued) Thin bedded, moderately broken from 838.5' to 838.1'	Rec N/A		Recovery data not recorded.
			SILTSTONE: Moderately hard, shaley and sandy gray, moderately fissile, with thin sandstone zones. 0.5' Sandstone, fig., at 834.4 to 833.9 Moderately broken and thin bedded from 831.7' to 831.4' Severely broken, crushed to gravel and pebble sized pieces from 830.6' to 830.3'		2	
830.1	52.2	SLS		Loss N/A		
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam, Ohio

HOLE NO.
G-6

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e.	BOX OR SAMPLE NO. f.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
863.5	20.0	CON	CONCRETE: Pea gravel aggregate and some chert fragments.			Concrete was cored and discarded from 882.3' to 850.4'.

HOLE NO. G-7

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.	
PROJECT		INSTALLATION		SHEET	
Dover Dam, Ohio		HUNTINGTON DISTRICT		2	
ELEVATION		DEPTH		LEGEND	
CLASSIFICATION OF MATERIALS (Description)		% CORE RECOVERY		BOX OR SAMPLE NO.	
REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)					
CONCRETE: (Continued)					
CON					
850.4	34.0	Concrete retained from 850.4' to 848.7'	Rec 100%	Began Coring	
848.7	35.8	Top of Rock			
LIMESTONE: Dark gray to black, hard with laminated seams, fossiliferous.					
Severely broken zone from 845.9' to 845.5'					
85° fracture, rough and irregular from 845.9' to 845.4'		Loss D.0			
LS		Rec 96%		1	
844.2	40.5	SHALE: Black, moderately hard.			
Severely broken, crushed, and weathered zone with multiple open bedding planes and incipient fractured zone appears to be pulverized with pieces the size of pebbles and small gravel from 842.0' to 841.4'					
SH		Loss 0.2			
840.9	44.0				

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3 OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
840.9	44.0		SILTSTONE: Sandy, dark gray into gray, moderately hard to hard, sandier with depth. Severely broken and fractured with multiple high angle fractures and open bedding planes 0.02' spacing between from 835.3' to 833.5', 833.2' to 832.6', 832.2' to 830.8', 830.6' to 830.1', 829.6' to 828.9', 828.7' to 827.3', 826.5' to 824.9'	Rec 100%		
				Loss 0.0		
				Rec 96%		
		SLS			2	
				Loss 0.2		
				Rec 98%		
				Loss 0.1		
				Rec 100%		
824.8	61.1		Bottom of Hole	Loss 0.0		

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-7

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 882.3		Hole No. G-8		
PROJECT Dover Dam, Ohio			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 3 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			CONCRETE: (Continued)			
		CON				
849.7	34.7					Began Coring
848.2	36.3		Top of Rock	Rec 100%		
		LS	LIMESTONE: Dark gray to black, hard, thin bedded with laminated seams, fossiliferous.	Loss 0.0		
				Rec 100%	1	
843.9	40.9		SHALE: Block, moderately hard. Badly broken zone from 839.9' to 839.7'			
		SH	0.05' grout seam at 843.7'	Loss 0.0		
				Rec 98%		
841.0	44.0					

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-8

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 882.3		Hole No. C-8		
PROJECT Dover Dam, Ohio			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 3 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
840.1	44.9	SH	SHALE: (Continued)			
			SILTSTONE: Sandy, dark gray into gray moderately hard to hard, sand content increases with depth. Partially weathered and broken zone from 840.3' to 839.5'	Loss 0.1 Rec 96%	1	
				Loss 0.2 Rec 98%		
		SLS		Loss 0.1 Rec 98%	2	
823.9	62.2		Bottom of Hole	Loss 0.1		

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio HOLE NO. C-8

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		882.3		Hole No.		G-9			
PROJECT			Dover Dam, Ohio			INSTALLATION			HUNTINGTON DISTRICT		
SHEET 2			OF 3 SHEETS								
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)					
			CONCRETE: (Continued)								
		CON									
853.5	30.7			Rec 100%		Began Coring					
848.8	35.6		Top of Rock	Loss 0.0							
		LS	LIMESTONE: Dark gray, hard, fossiliferous with laminated seams.	Rec 91%		Started retaining core at elevation 850.1'					
844.9	39.8				1						
		SH	SHALE: Black, moderately hard with some weathered and broken zones. Moderately broken from 844.4' to 843.4' Vertical fracture, open, rough, planar from 843.8' to 843.7' Moderately broken from 843.4' to 842.5' Moderately broken, thin bedded from 842.5' to 840.2'	Loss 0.5 Rec 94%							
841.0	44.0										

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3 OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant)
840.2	44.8	SH	SHALE: (Continued) Evidence of mechanical spin at 841.9' Core diameter loss from 841.1' to 841.0'	Loss 0.3 Rec 96%	1	
			SILTSTONE: Sandy, dark gray into gray, moderately hard to hard, sandier with depth. Vertical fracture, open, planar rough from 835.7' to 835.4'	Loss 0.2 Rec 94%		
		SLS		Loss 0.3 Rec 93%	2	
				Loss 0.1 Rec 100%		
				Loss 0.0 Rec 100%		
825.3	60.7		Bottom of Hole	Loss 0.0		Broke 5' barrel. Used short barrel for the remaining part of the hole.

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio HOLE NO. G-9

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET 3		
DOVER DAM, Ohio		HUNTINGTON DISTRICT		OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
840.7	48.5	SH	SHALE: Block, moderately hard. Bodily weathered zone from 836.3' to 836.0'. Bodily broken zone from 834.8' to 833.8'. Vertical fracture, open, planar, smooth from 844.4' to 844.2'. Severely broken from 843.4' to 842.6'. Thin bedded, moderately broken with multiple high angle fractures from 841.7' to 840.6'.	Loss 0.0 Rec 100%		
			SILTSTONE: Sandy, gray, moderately hard, sandier with depth. 55° fracture, open, planar, smooth from 832.5' to 832.1'. Grout coated bedding plane at 829.3'. Severely broken from 829.0' to 828.2'.	Loss 0.0 Rec 96%	1	
		SLS		Loss 0.2 Rec 98%		
				Loss 0.1 Rec 91%		
825.1	65.1		Bottom of Hole	Loss 0.3		

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-10a

ELEVATION a	DEPTH b	BOX c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e.	BOX OR SAMPLE NO. f.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			CONCRETE: Pea gravel aggregate and some chert			Concrete appeared to be satisfactory by visual observation with no loss recorded.
						Concrete cored and discarded from 886.3' to 852.7'.
867.5	20.0	CON				

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		2		
				OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
			CONCRETE: (Continued)			
		CON				
852.7	35.8					Began Coring
				Rec 100%		
850.3	38.3		Top of Rock			
		LS	LIMESTONE: Dark gray, hard, fossiliferous. 60° fracture, planar rough, grout coated from 846.9' to 846.5.	Loss 0.0 Rec 85%	1	
845.9	43.0					
		SH	SHALE: Black, moderately hard, with some badly weathered zones.			
845.0	44.0					

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-10b

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 882.3		Hole No. G-10b		
PROJECT Dover Dam, Ohio		INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 3 SHEETS		
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
842.3	46.8	SH	SHALE: (Continued) Fractured and badly broken from 846.3' to 844.0' Very soft and clayey from 845.7' to 845.3'	Loss 0.6 Rec 96%	1	
			SILTSTONE: Sandy, dark gray, moderately hard, with some sandier zones and thin sandstone layers.	Loss 0.2 Rec 100%		
		SLS		Loss 0.0 Rec 100%	2	
825.4	64.8			Loss 0.0 Rec 100%	3	
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-10b

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		2		
				OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
			CONCRETE: (Concrete)			
		CON				
853.6	34.8					Began Coring
				Rec 100%		
851.8	36.7		Top of Rock			
		LS	LIMESTONE: Dark gray, hard, fossiliferous, with thin laminations.			
				Loss 0.0		
				Rec 96%		
847.6	41.2					
		SH	SHALE: Black, moderately hard with some slightly weathered zones.			
			Angular fault from 843.7' to 843.4', no grout.			
845.0	44.0					

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		886.3		Hole No. G-11		
PROJECT			Dover Dam, Ohio		INSTALLATION		HUNTINGTON DISTRICT	
SHEET			3		OF 3 SHEETS			
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)		
a	b	c	d	e	f	g		
		SH	SHALE: (Continued)	Loss 0.2 Rec 92%				
843.0	46.1		SILTSTONE: Sandy, gray, moderately hard. 3.7' Sandstone, medium grained from 833.6' to 829.9' 0.8' Sandstone, medium grained from 829.4' to 828.6' Grout coated bedding plane at 833.6 and 829.7'	Loss 0.4 Rec 96%	1			
		SLS		Loss 0.2 Rec 98%	2			
				Loss 0.1 Rec 94%	3			
824.8	65.4		Bottom of Hole	Loss 0.3				

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-11

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 886.3		Hole No. G-12		
PROJECT Dover Dam, Ohio			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 3 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. If significant)
			CONCRETE: (Continued)			
		CON				
854.9	33.4					Began Coring
				Rec 100%		
853.4	35.0		Top of Rock			
			LIMESTONE: Hard, dark gray, fossiliferous, with thin laminations.	Loss 0.0		
			70° fracture, open, planar, rough from 853.3' to 852.6'	Rec 98%		
		LS	55° fracture, open, planar, irregular, rough, moderately broken from 850.4' to 850.0'		1	
848.9	39.8					
			SHALE: Black, moderately hard.	Loss 0.1		
			Broken and partially weathered zone from 847.5' to 846.5'.	Rec 89%		
			Thin grouted closed fractures from 844.3' to 844.1' and 848.1' to 847.5'			
		SH	60° fracture open, planar, smooth from 848.1' to 847.9' and from 847.8' to 847.3'			
845.0	44.0		Moderately broken, thin bedded from 847.5' to 845.2'			

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-12

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		886.3		Hole No. G-12	
PROJECT			Dover Dam, Ohio			INSTALLATION	
			HUNTINGTON DISTRICT			SHEET 3 OF 3 SHEETS	
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)	
842.6	46.5	SH	SHALE: (Continued) Vertical fracture, open, planar smooth from 844.8' to 844.7' Grout coated bedding plane closed and irregular at 844.2', 844.15', and 844.06' Mechanical spin loss at 843.3'	Loss 0.5 Rec 94%	1		
			SILTSTONE: Sandy, dark gray, moderately hard, with some sandier zones.	Loss 0.3 Rec 94%			
		SLS		Loss 0.3 Rec 96%	2		
				Loss 0.2 Rec 80%			
826.2	64.0				3		
		SLS	SILTSTONE: Light gray, sandy, coarse grained.	Loss 1.0			
824.5	65.8		Bottom of Hole				

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-12

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		2		
				OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOV- ERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
			CONCRETE: (Continued)			
		CON				
858.0	30.1			Rec 100%		Began Coring
855.0	33.3		Top of Rock			
		LS	LIMESTONE: Black into dark gray, hard, fossiliferous, with thin laminations. Fault zones from 854.8 to 854.1 and 851.3 to 850.6	Loss 0.0 Rec 95%	1	
850.3	38.3		SHALE: Black, moderately hard. Weathered and broken from 847.5 to 846.5 Thin grouted veins from 846.5 to 846.3	Loss 0.2 Rec 95%		
		SH		Loss 0.1 Rec 88%		
845.0	44.0				2	

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-13a

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		886.3		Hole No. G-13a	
PROJECT			Dover Dam, Ohio			INSTALLATION	
			HUNTINGTON DISTRICT			SHEET 3 OF 3 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g	
842.8	46.3	SH	SHALE: (Continued)	Loss 0.6 Rec 94%			
			SILTSTONE: Sandy, gray, moderately hard, interlayered with some sandier zones. 55° fracture, open, rough, planar from 833.5' to 833.2'	Loss 0.3 Rec 96%	2		
		SLS		Loss 0.2 Rec 90%			
				Loss 0.5 Rec 100%	3		
825.5	64.7		SILTSTONE: Light gray, sandy, coarse grained.	Loss 0.0			
825.1	65.1	SLS	Bottom of Hole				

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			CONCRETE: With pea gravel and some chert.			
						Concrete appeared to be satisfactory by visual observation with no loss recorded.
						Concrete cored and discarded from 886.3' to 857.3'.
		CON				
867.5	20.0					

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		2		
				OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
			CONCRETE: (Continued)			
		CON				
857.3	30.9					Began Coring
				Rec 100%		
855.3	33.0		Top of Rock			
		LS	LIMESTONE: Dark gray to black, hard, fossiliferous. Multiple high angled, grout coated, rough, nonplanar fractured zone from 852.4' to 851.4'. 70° High angle, planar, rough grout coated fracture from 855.2' to 854.4'	Loss 0.0 Rec 100% Loss 0.0 Rec 100%	1	
850.7	37.9					
		SH	SHALE: Black, moderately hard. Broken zone with multiple 40°-60° fractures, rough and nonplanar. Badly broken and weathered zones from 847.3' to 846.1'.	Loss 0.0 Rec 81%		
846.1	42.8					
		SLS	SILTSTONE: Sandy, gray moderately hard, with some sandier zones.			
845.0	44.0				2	

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam, Ohio

HOLE NO.
G-13b

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3 OF 3 SHEETS		
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SHALE: (Continued)			
		SH		Loss 0.8 Rec 91%		
840.5	48.7					
		SS	SANDSTONE: Gray, medium grained, moderately hard.	Loss 0.4 Rec 86%		
838.8	50.5					
			SILTSTONE: Sandy, gray into dark gray, moderately hard, gradually becoming shaley (more fissile) with depth.		2	
		SLS		Loss 0.7 Rec 80%		
				Loss 0.8 Rec 75%		
829.4	60.5					
		SLS	SILTSTONE: Gray, sandy, medium to coarse grained, moderately hard.	Loss 0.8 Rec 20%	3	
825.8	64.4			Loss 1.6		
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-13b

ELEVATION e	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e.	BOX OR SAMPLE NO. f.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
867.5	20.0	CON	CONCRETE: Pea gravel aggregate and Chert.			Concrete appeared to be satisfactory by visual observation with no loss recorded. Concrete cored and discarded from 886.3' to 839.4'.

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3		
OF 3 SHEETS						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant)
a	b	c	d	e	f	g
			CONCRETE: (Continued)			
		CON				
839.4	49.9					Began Coring
837.8	51.6		Top of Rock	Rec 78%		
		LS	LIMESTONE: Dark gray to black, hard, fossiliferous.			Loss accumulative. Majority of loss probably in Concrete Rock bond area.
836.9	52.6					
		SH	SHALE: Sandy, dark gray into gray, moderately hard, with some sandier zones. Grouted fracture from 836.2' to 835.9', possible fault. More Shaly from 832.3' to 830.2'.	Loss 1.1 Rec 96%		
					1	
830.2	59.7			Loss 0.2 Rec 98%		
		SLS	SILTSTONE: Gray, moderately hard, sandy, medium to coarse grained. Medium bedded with grout coated planes from 827.9' to 827.3'.			
825.1	65.1			Loss 0.1	2	
			Bottom of Hole			

[illegible]

HOLE NO.	G-14b
----------	-------

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE		Hole No.		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3 OF 3 SHEETS		
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant) g
			CONCRETE: (Continued)			
839.7	49.6	CON				Began Coring
836.7	51.8		Top of Rock	Rec 96%		
			SILTSTONE: Sandy, dark gray into gray, moderately hard, with some sandier zones. Broken zone from 837.2' to 836.9'.	Loss 0.2 Rec 94%	1	
830.9	59.0	SLS				
			SILTSTONE: Gray, moderately hard, sandy, medium to coarse grained. Dark gray Shale layer from 830.5' to 829.9' and from 829.4' to 829.3'.	Loss 0.3 Rec 96%		
		SLS				
825.0	65.2			Loss 0.2 Rec 100% Loss 0.0	2	
			Bottom of Hole			

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-14b

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 886.3		Hole No. G-15		
PROJECT		INSTALLATION		SHEET		
Dover Dam, Ohio		HUNTINGTON DISTRICT		3		
				OF 3 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
843.8	45.2		CONCRETE: (Continued)			Began Coring
		CON		Rec 98%		
839.7	49.6		Top of Rock			
		SLS	SILTSTONE: Sandy, dark gray, moderately hard, with some sandier zones. Moderately broken bedding planes with breaks 0.03' to 0.1' average spacing between 839.1' to 836.3' Moderately broken with bedding planes spaced at 0.02' to 0.2' from 834.3' to 833.4' Severely broken from 833.4' to 831.8'	Loss 0.1 Rec 100%	1	
				Loss 0.0 Rec 91%		
831.8	58.0		SILTSTONE: Gray, moderately hard, sandy, medium to coarse grained. SHALE, silty, dark gray, thin bedded, with thin light gray sandstone stringers throughout from 829.4' to 829.1'	Loss 0.4 Rec 96%		
		SLS			2	
825.4	64.8		Bottom of Hole	Loss 0.2		

LRH FORM 1836-A
MAY 04

PROJECT Dover Dam, Ohio

HOLE NO. G-15

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 4 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326733.86 E 2301857.81				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-1				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 3 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 21						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 919.5						
7. THICKNESS OF OVERBURDEN 4.2 Feet				16. DATE HOLE STARTED 6/24/04 COMPLETED 6/24/04						
8. DEPTH DRILLED INTO ROCK 69.1 Feet				17. ELEVATION TOP OF HOLE 932.21 Feet						
9. TOTAL DEPTH OF HOLE 73.3 Feet				18. TOTAL CORE RECOVERY FOR BORING 98.8%						
				19. NAME OF INSPECTOR STEWART						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -2DD	BLOWS
931.8	0.4	OL	ORGANIC CLAY WITH SAND (OL), br. and gr., low pl., ve. mst., m. to f. sand w/tr. rt. and wood frags.	52.1						WH
		GC	CLAYEY GRAVEL WITH SAND (GC), gr. and br., low pl., mst., ong. to rau. gravel, c. to f. sand	8.2	32	22				3
929.2	3.0			6.3						4
		CL	LEAN CLAY (CL), gr., low pl., dry, w/wd. silty SH	% CORE RECOV- ERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant)				25
928.0	4.2									52
		SH	SHALE: Soft to mod. hard, gray, silty to sandy. Slight weathering from 928.0 to 926.0. Bedding plane breaks every 0.2' from 928.0 to 924.1. Increasingly silty with depth from 925.6 to 921.5.	REC 79%	1					50/0.2
				RQD 0%						
				L 0.8						
				REC 100%	2					
921.5	10.7			RQD 93%						
		SS	SANDSTONE: Med. to coarse grained, light gray, micaceous, hard, occasional shale stringers, crossbedded. Gray shale zone from 920.9 to 920.1. 45° Fracture, iron stained from 920.9 to 920.7. Moderate weathering from 920.9 to 918.8. Broken zone with severe weathering and soft from 920.4 to 920.1. Iron staining from 910.9 to 898.4. 55° Iron stained fracture from 910.4 to 910.0. Horizontal, iron stained fracture at 902.1, 902.0 Near vertical fracture, iron stained from 902.0 to 901.6. Vertical fracture from 885.3 to 884.3. Coal stringers from 884.2 to 883.2.	L 0.0	3					
				REC 100%						
				RQD 100%	4					
				L 0.0						
				REC 100%	5					

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-1

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 932.21		Hole No. C-04-1	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 2 OF 4 SHEETS
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				RQD 92%	5	
				L 0.0		
				REC 100%	6	
				RQD 100%		
				L 0.0	7	
				REC 100%		
				RQD 90%	8	
				L 0.0		
				REC 100%	9	
				RQD 100%		
				L 0.0	10	
				REC 100%		
				RQD 100%	11	
				L 0.0		
				REC 100%	12	
				L 0.0		
				REC 100%		

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE	Hole No. C-04-1		
PROJECT			INSTALLATION	SHEET		
Dover Dam			HUNTINGTON DISTRICT	3		
			OF 4 SHEETS			
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)
a	b	c	d	e	f	g
				RQD 80%	12	
					13	
				L 0.0		
		SS		REC 100%		
				RQD 91%	14	
				L 0.0		
878.0	54.2			REC 100%	15	
			SHALE: Dark gray, soft, occasional slickensides, carbonaceous, occasional siderite nodules.			
			Clay seam, plastic, damp, dark gray and slight sulfur smell from 878.0 to 877.9.	RQD 18%		
			Broken every 0.1'-0.05' from 878.0 to 874.0.		16	
			Calcite stringers from 874.6 to 874.5.	L 0.0		
		SH	Siderite nodules from 873.3 to 873.0.	REC 100%		
			Calcareous from 872.8 to 870.0.			
				RQD 70%	17	
870.0	62.2					
			LIMESTONE: Dark gray, hard, crystalline grained, fossiliferous.	L 0.0		
		LS		REC 100%		
867.9	64.3				18	
			COAL: Block, soft, blocky, vitreous.			
			Bone coal, black, hard from 866.8 to 865.5.	RQD 54%		
865.5	66.7					
		C				
			SHALE: Gray, silty to sandy, mod. hard, occasional sandstone stringers.	L 0.0	19	
	68	SH				

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-1

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 4 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326760.03 E 2301884.66				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-2				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN :DISTURBED 4 :UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 20						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 922.2						
7. THICKNESS OF OVERBURDEN 4.9 Feet				16. DATE HOLE :STARTED 6/28/04 :COMPLETED 6/29/04						
8. DEPTH DRILLED INTO ROCK 68.7 Feet				17. ELEVATION TOP OF HOLE 933.81 Feet						
9. TOTAL DEPTH OF HOLE 73.6 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR STEWART						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
933.0	0.8	SC-SM	SILTY CLAYEY SAND (SC-SM), gr., low pl., mst., f. sand w/tr. org. and animal discard odor							1
		GC	CLAYEY GRAVEL WITH SAND (GC), gr., m. pl., mst., subong. to rou. gravel, f. sand	7.3	32	21				2
										3
										5
										3
929.7	4.1		low pl. @ El. 930.8 - El. 929.7	8.8						3
928.9	4.9	CL	LEAN CLAY (CL), gr., low pl., dry w/wd. silty SH	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)				25
										50/0.4
		SH	SHALE: Gray, soft, laminated. Vertical fracture from 928.8 to 927.4.	REC 100%						
927.4	6.4			RQD 17%	1					
926.6	7.2	SS	SANDSTONE: Gray, mod. hard, med. grained, micaceous.							
			60° Fracture from 927.4 to 926.8.	L 0.0						
		SH	SHALE: Gray, soft to mod. hard, laminated, silty to sandy. 45° Fracture at 925.1. Vertical fracture from 922.2 to 922.0. Vertical fracture from 921.7 to 921.1.	REC 100%						
				RQD 61%	2					
921.1	12.7									
		SS	SANDSTONE: Light gray, hard, med. grained, crossbedded, thick beds, micaceous iron stained. Vertical fracture from 904.3 to 902.7. 70° Fracture from 890.2 to 888.9.	L 0.0						
				REC 100%	3					
				RQD 100%						
					4					
				L 0.0						
				REC 100%	5					

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-2

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 933.81		Hole No. C-04-2	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 2 OF 4 SHEETS
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				RQD 100%	5	
				L 0.0		
				REC 100%	6	
				RQD 100%	7	
				L 0.0		
				REC 100%		
		SS		RQD 68%	8	
				L 0.0		
				REC 100%	9	
				RQD 98%		
				L 0.0	10	
				REC 100%		
				RQD 100%	11	
				L 0.0		
	44					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-2

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 933.81		Hole No. C-04-2	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				REC 100%		
				RQD 74%	12	
				L 0.0		
		SS		REC 100%	13	
				RQD 100%		
				L 0.0	14	
				REC 100%		
878.9	54.9					
			SHALE: Dark gray, mod. hord, laminated, scattered siderite nodules, numerous slickensided fractures, efferevescent in last 0.2'. 45° Fracture at 875.7.	RQD 26%	15	
				L 0.0		
		SH		REC 100%	16	
				RQD 24%		
871.6	62.2					
			LIMESTONE: Gray, very hard, fine to med. crystalline grained, fossiliferous.	L 0.0	17	
		LS		REC 100%		
867.7	66.1					
			COAL: Black, mod. hord, vitreous luster.	RQD 60%	18	
865.9	67.9	C				
		SH				

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.81		Hole No. C-04-2		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant) g
860.1	73.7	SH	SHALE Cont. Dark gray to black, mod. hard, carbonaceous, laminated, silty. Silty from 865.9 to 865.3. Coalstringers from 865.0 to 864.0.	L 0.0 REC 100% ROD 97%	19 20	
			BOTTOM OF HOLE @ 860.1			

LRH FORM 1836-A
 MAY 04

PROJECT
 Dover Dam

HOLE NO.
 C-04-2

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 4 SHEETS
1. PROJECT Dover Dam			10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW	
2. LOCATION (Coordinates or Station) N 326644.53 E 2301866.04			11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29	
3. DRILLING AGENCY HC NUTTING			12. MANUFACTURER'S DESIGNATION OF DRILL CME 45	
4. HOLE NO. (As shown on drawing title and file number) C-04-3			13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN : DISTURBED 8 : UNDISTURBED 0	
5. NAME OF DRILLER BRAGG			14. TOTAL NUMBER CORE BOXES 22	
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEC. FROM VERT.			15. ELEVATION GROUND WATER 891.4	
7. THICKNESS OF OVERBURDEN 17.5 Feet			16. DATE HOLE : STARTED 5/17/04 : COMPLETED 5/19/04	
8. DEPTH DRILLED INTO ROCK 74.5 Feet			17. ELEVATION TOP OF HOLE 933.65 Feet	
9. TOTAL DEPTH OF HOLE 92.0 Feet			18. TOTAL CORE RECOVERY FOR BORING 100%	
			19. NAME OF INSPECTOR STEWART	

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
933.2	0.5	SW	WELL GRADED SAND WITH GRAVEL (SW), br. and bk., dry, ang. to rou. gravel, c. to f. sand w/asphalt							29
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand	6.4						11
										5
										9
										3
930.7	3.0									8
		SW-SM	WELL GRADED SAND WITH SILT AND GRAVEL (SW-SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand	5.0			40	48	12	12
										9
										5
										6
927.7	6.0									5
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand	5.9						6
										13
										6
										6
										9
										15
										8
										10
				5.6						10
										8
										8
921.7	12.0									6
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr. and br., m. pl., mst., subang. gravel, f. sand w/SS and SH frags.	15.8	34	20	20	19	61	5
										3
										4
										2
										3
										3
			SANDY LEAN CLAY (CL), gr. br., low pl., mst., f. sand w/tr. SH and SS frags.	13.8						5
				4.6						4
917.2	16.5									3
		SM	SILTY SAND (SM), lt. br., non pl., dry, f. sand w/wd. SS	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant)				23
916.2	17.5									50
		SS	SANDSTONE: Light brown/gray, hard, med. grained, micaceous, crossbedded, numerous fractures with number of fractures decreasing with depth. Vertical fracture from 906.8 to 906.5.	REC 100% RQD 0% REC 100% RQD 0%	1					

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-3

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.65		Hole No. C-04-3		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SANDSTONE Cont.	ROD 0%	1	
			Several 45° fractures from 906.5 to 905.8.			
			30° Fracture at 905.2 and 898.2.		2	
			60° Fracture from 904.2 to 903.8.			
			35° Fracture at 901.4 and 901.2.			
			Open vertical fracture from 879.9 to 877.5.	L 0.0 REC 100%		
				ROD 0%	3	
				L 0.0 REC 100%		
				ROD 47%	4	
				L 0.0 REC 100%		
		SS		ROD 88%	5	
				L 0.0 REC 100%		
				ROD 90%	6	
				L 0.0 REC 100%		
				ROD 90%	7	
				L 0.0 REC 100%		
				ROD 90%	8	
				L 0.0 REC 100%		
	44					5/19/04

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-3

DRILLING LOG (Cont Sheet)			ELEVATION "TOP OF HOLE" 933.65		Hole No. C-04-3	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
		SS		REC 100%	9	
				RQD 90%		
				L 0.0	10	
				REC 100%		
				RQD 92%	11	
				L 0.0		
				REC 100%		
877.5	56.2	SH	SHALE: Dark gray to black, mod. hard, numerous siderite nodules throughout, laminated.	RQD 0%	12	
				L 0.0		
				REC 100%	13	
872.7	61.0	LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded, fossiliferous. Open vertical fracture from 872.7 to 870.4. Vertical fracture from 870.4 to 868.7.	RQD 28%		14
				L 0.0		
869.0	64.7			REC 100%		
867.4	66.3	C	COAL: Black, pyritic, vitreous.			
		SH	SHALE: Gray, silty, mod. hard, laminated 1/3" thick with some being carbonaceous, sandy in zones. 45° Fracture at 858.3.	RQD 50%	15	
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-3

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.65		Hole No. C-04-3		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SHALE Cont.	L 0.0	15	
			30° Fracture at 856.5 and 856.3.	REC 100%		
			70° Fracture at 855.2.		16	
			Several coal stringers and one coal lamination 1/3' thick from 863.3 to 863.0.	RQD 88%		
			Zone of fractures from 856.6 to 853.3.			
				L 0.0		
				REC 100%	17	
				RQD 30%		
					18	
				L 0.0		
				REC 100%		
852.2	81.5	SH		RQD 66%	19	
			LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded, fossiliferous.			
				L 0.0		
				REC 100%	20	
848.3	85.4	LS		RQD 85%		
			SHALE: Dark gray to black, mod. hard, silty, fossiliferous in upper part, laminated, carbonaceous.			
			40° Fracture with slickensided surface at 845.5 and 845.2.	L 0.0		
				REC 100%	21	
844.1	89.6	SH		RQD 88%		
			SANDSTONE: Gray, mod. hard, very fine grained, shaley.			
					22	
841.7	92	SS		L 0.0		
			BOTTOM OF HOLE @ 841.7			

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 5 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326713.76 E 2301955.00				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-4				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 12 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 22						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 899.9						
7. THICKNESS OF OVERBURDEN 28.4 Feet				16. DATE HOLE STARTED 5/10/04 COMPLETED 5/11/04						
8. DEPTH DRILLED INTO ROCK 72.7 Feet				17. ELEVATION TOP OF HOLE 933.79 Feet						
9. TOTAL DEPTH OF HOLE 101.1 Feet				18. TOTAL CORE RECOVERY FOR BORING 98.5%						
				19. NAME OF INSPECTOR STEWART						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
930.8	3.0	GP	POORLY GRADED GRAVEL WITH SAND (GP), br., dry, subang. to ang. gravel, c. to f. sand w/asphalt frags. mst., ang. to rou. gravel w/alluvium, flint, and SS frags. @ El. 933.2-El. 930.7	5.9						100
										28
										47
										15
										21
										18
										6
										18
										21
										8
		SP-SM	POORLY GRADED SAND WITH SILT AND GRAVEL (SP-SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand w/alluvium, flint and SS frags.	4.4			40	50	10	12
										14
										9
										18
										14
										6
										11
										9
										7
										7
		SP-SM		5.4						15
										12
										9
										9
										8
										11
										9
										4
										15
										9
915.8	18.0	SP-SM		4.9						5
										5
										7
										4
										4
										4
										4
										4
										4
										4
913.8	20.0	SP	POORLY GRADED SAND WITH GRAVEL (SP), br., mst., ang. to rou. gravel, c. to f. sand w/alluvium, flint and SS frags.	4.5						5
										5
										4
										4
										3
										3
										3
										3
										3
										3

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-4

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE	Hole No. C-04-4							
PROJECT		INSTALLATION						SHEET		
Dover Dam		HUNTINGTON DISTRICT						2 OF 5 SHEETS		
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
912.8	21.0	SP	POORLY GRADED SAND WITH GRAVEL (SP), br., mst., ong. to rou. gravel, c. to f. sand w/ alluvium, flint and SS frags.	4.5						3
										2
		GP	POORLY GRADED GRAVEL WITH SAND (GP), br. and whi., ve. mst. to mst., ong. to rou. gravel, c. to f. sand w/ alluvium and SS frags. br. @ El. 909.7-EI. 906.7	6.1						3
										4
										5
										4
										3
										3
				7.3						3
										6
906.8	27.0		POORLY GRADED GRAVEL WITH SAND AND SILTY CLAY (GP-GC), br., low pl., mst., ong. to rou. gravel, c. to f. sand w/SS and conglomerate frags. and alluvium	9.1						4
										4
		GP-GC	SILTY SAND WITH GRAVEL (SM), gr., non pl., dry, ong. to rou. gravel, c. to f. sand w/SS frags. and alluvium	6.5						7
905.8	28.0			% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)				11
905.4	28.4	SM								52/0.4
			SANDSTONE: Light gray and light brown, med. to coarse, mod. hard, micaceous, weathered, somewhat friable, iron stained throughout.	REC 100% ROD 0% L 0.0						
			Numerous fractures from 905.4 to 901.5.	REC 47%	1					
			50° Fracture at 900.6 and from 885.0 to 884.4.	ROD 0%						
			Shaley and fractured from 896.8 to 896.5.	L 1.1						
			Vertical open fracture along carbonaceous lamination from 892.5 to 890.6.	REC 100%						
			Vertical surface crack from 889.5 to 888.9.	ROD 0%	2					
			45° Fracture from 886.1 to 885.7.							
			Vertical fracture from 885.0 to 883.5 and 905.1 to 904.7.	L 0.0						
		SS	Numerous soft shale lenses and clayey stringers from 882.8 to 882.2.	REC 100%						
					3					
				ROD 56%						
				L 0.0						
				REC 100%	4					
				ROD 62%						
					5					

LRH FORM 1836-A MAY 04

PROJECT Dover Dam

HOLE NO. C-04-4

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.79		Hole No. C-04-4		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
		SS		L 0.0	5	
				REC 100%		
				RQD 36%	6	
				L 0.0		
				REC 100%	7	
880.8	53.0			RQD 38%		
		SH	SHALE: Dark gray, mod. hard, laminated, weathered, few slickensided fractures, few siderite nodules throughout. 20° Slickensided fracture at 879.9. Vertical fracture from 879.0 to 878.6 and 876.6 to 876.1. Slightly effervescent from 876.8 to 874.7.	L 0.0	8	
				REC 100%		
				RQD 0%	9	
874.7	59.1					
		LS	LIMESTONE: Gray, hard, fossiliferous. Vertical healed fracture from 874.7 to 873.3.	L 0.0		
				REC 100%	10	
872.3	61.5					
		C	COAL: Black, vitreous, pyritic.	RQD 20%		
871.0	62.8					
		SH	SHALE: Light gray, mod. hard, carbonaceous zones, thin bedded. 50° Fracture at 870.3. 45° Fracture 868.8. Dark gray, silty to sandy from 866.7 to 848.6. Vertical fracture from 868.3 to 868.0 and 864.8 to 863.9. 60° Fracture from 861.0 to 860.5. Effervescent from 864.4 to 848.7.	L 0.0	11	
				REC 100%		
					12	
				RQD 76%		
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-4

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.79		Hole No. C-04-4		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant) g
			SHALE Cont. 80° Fracture from 858.8 to 853.8.		12	
				L 0.0		
				REC 100%	13	
				RQD 72%		
					14	
				L 0.0		
				REC 100%		
				RQD 78%	15	
				L 0.0		
				REC 100%		
				RQD 88%	16	
				L 0.0		
848.6	85.2				17	
			LIMESTONE: Dark gray, hard, thick bedded, fossiliferous. Vertical fracture zone from 845.0 to 843.9.	REC 100%		
				RQD 72%		
					18	
843.6	90.2			L 0.0		
			SHALE: Dark gray to black, mod. hard, carbonaceous and calcareous and fossiliferous near top, laminated. 45° Fracture 838.3.	REC 100%	19	
	92					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-4

DRILLING LOG (Cont Sheet)

ELEVATION TOP OF HOLE 933.79

Hole No. C-04-4

PROJECT
Dover Dam

INSTALLATION
HUNTINGTON DISTRICT

SHEET 5
OF 5 SHEETS

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SHALE Cont. Near vertical fracture from 842.5 to 841.3.	RQD 31%	19	
		SH		L 0.0		
838.1	95.7			REC 100%	20	
			SILTSTONE: Gray, mod. hard, thin bedded, shaley. Sandy zone from 834.6 to 833.6.	RQD 87%		
		SLS			21	
				L 0.0		
832.7	101.1			REC 100%		
				RQD 100%		
				L 0.0	22	
			BOTTOM OF HOLE @ 832.7.			
	116					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-4

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 2 SHEETS
1. PROJECT Dover Dam		10. SIZE AND TYPE OF BIT 3" HOLLOW		
2. LOCATION (Coordinates or Station) N 326540.28 E 2301875.50		11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29		
3. DRILLING AGENCY HC NUTTING		12. MANUFACTURER'S DESIGNATION OF DRILL CME 45		
4. HOLE NO. (As shown on drawing title and file number) C-04-5		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 15 UNDISTURBED 0		
5. NAME OF DRILLER BRAGG		14. TOTAL NUMBER CORE BOXES 0		
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.		15. ELEVATION GROUND WATER 878.0		
7. THICKNESS OF OVERBURDEN 35.5 Feet		16. DATE HOLE STARTED 4/28/04 COMPLETED 4/28/04		
8. DEPTH DRILLED INTO ROCK 0 Feet		17. ELEVATION TOP OF HOLE 901.69 Feet		
9. TOTAL DEPTH OF HOLE 35.5 Feet		18. TOTAL CORE RECOVERY FOR BORING N/A %		
		19. NAME OF INSPECTOR STEWART		

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
901.3	0.3	GM	SILTY GRAVEL WITH SAND (GM), bk., non pl., ms., w/orgs. and animal discard odor	30.9						2
			POORLY GRADED GRAVEL WITH SAND AND SILT (GP-GM), br., non pl., mst., subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	9.8						3
										5
										4
										5
		GP-GM	ang. to rou. gravel @ El. 898.6- El. 895.6	5.3						4
										1
										7
							49	42	9	9
										4
										8
895.6	6.0									15
		GP	POORLY GRADED GRAVEL WITH SAND (GP), br., mst., ang. to rou. gravel, c. to f. sand w/SS and alluvium	7.3						8
										14
										16
										6
										14
892.6	9.0									13
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., ve. mst., subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	12.2						6
										8
										8
							31	50	19	5
										5
										7
889.6	12.0									
		GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), br., low pl., ve. mst., subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	9.4						2
										1
										2
										5
										6
										5
886.6	15.0									
		SM	SILTY SAND WITH GRAVEL (SM), br., low to non pl., ve. mst., subang. to rou. gravel, c. to f. sand w/SS frags, alluvium, and flint	11.1						7
										12
										6
										2
			ang. to rou. gravel @ El. 884.8- El. 881.9	13.1						4
										8
							18	53	29	4
										2
										3
881.9	19.7									
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. pl., ve. mst., subang. to rou. gravel, f. sand w/ tr. wood frags. and natural gas odor	20.5			29	20	51	1
881.6	20.0									

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-5

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE	Hole No. C-04-5							
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT						SHEET 2 OF 2 SHEETS		
ELEVATION <i>a</i>	DEPTH <i>b</i>	LEGEND <i>c</i>	CLASSIFICATION OF MATERIALS (Description) <i>d</i>	MC	LL	PL	% +4	% SAND	% -200	BLOWS	
879.1	22.5	CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. pl., ve. mst., subang. to rou. gravel, f. sand w/tr. wood frags. and natural gas odor	20.5			29	20	51	2 3 3 6 4	
876.1	25.5		GRAVELLY LEAN CLAY (CL), gr., m. pl., ve. mst., subang. to ang. gravel w/tr. wood frags. and natural gas odor	31.1	41	23	▽ 4/28/04			1 5 3 2 4 4	
873.1	28.5		LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel	20.2						1 3 7 4 8 11	
870.6	31.0		SANDY LEAN CLAY (CL), br., m. pl., ve. mst., f. sand	18.4	27	15				2 5 8 3 4 5	
868.9	32.7	SC-SM	SILTY CLAYEY SAND (SC-SM), gr. and br., low pl., ve. mst., f. sand	20.0			4	53	43	10 9 10	
867.1	34.5	CL	LEAN CLAY WITH SAND (CL), gr., low pl., mst., f. sand w/tr. SS frags. and mottled	13.3						5 11 45	
866.1	35.5		LEAN CLAY (CL), m. to low pl., mst. w/wd. shale and mottled	11.3						11 50	
			BOTTOM OF HOLE								

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 5 SHEETS
1. PROJECT Dover Dam		10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW		
2. LOCATION (Coordinates or Station) N 326575.10 E 2301911.35		11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29		
3. DRILLING AGENCY HC NUTTING		12. MANUFACTURER'S DESIGNATION OF DRILL CME 45		
4. HOLE NO. (As shown on drawing title and file number) C-04-5A		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 15 UNDISTURBED 0		
5. NAME OF DRILLER BRAGG		14. TOTAL NUMBER CORE BOXES 20		
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.		15. ELEVATION GROUND WATER 871.5		
7. THICKNESS OF OVERBURDEN 35.2 Feet		16. DATE HOLE STARTED 5/7/04 COMPLETED 5/9/04		
8. DEPTH DRILLED INTO ROCK 70.0 Feet		17. ELEVATION TOP OF HOLE 902.03 Feet		
9. TOTAL DEPTH OF HOLE 105.2 Feet		18. TOTAL CORE RECOVERY FOR BORING 100%		
		19. NAME OF INSPECTOR STEWART		

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% -4	% SAND	% -200	BLOWS
901.7	0.3	ML	GRAVELLY SILT WITH SAND (ML), dk. br., non pl., mst., subang. gravel, f. sand w/org. and animal discord	28.1						3
		GP	POORLY GRADED GRAVEL WITH SAND (GP), br., mst., ang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	7.6						5
										8
										6
899.0	3.0									14
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., mst., subang. to ang. gravel, c. to f. sand w/SS and LS frags and alluvium	6.7			38	46	16	11
										4
										15
										17
896.0	6.0									14
		SP-SM	POORLY GRADED SAND WITH GRAVEL AND SILT (SP-SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand w/SS and LS frags. and alluvium	5.6			43	46	11	17
										12
										16
										15
893.0	9.0									10
		GP	POORLY GRADED GRAVEL WITH SAND (GP), br., ve. mst., ang. to rou. gravel, c. to f. sand w/SS and LS frags. and alluvium	7.2						23
										19
										11
										10
										7
890.0	12.0									4
		GP-GM	POORLY GRADED GRAVEL WITH SAND AND SILT (GP-GM), br., non pl., wet to ve. mst., subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	12.4						2
										1
										3
										5
										5
887.0	15.0									9
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., wet, subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	11.9			21	65	14	9
										12
										7
										10
										8
			low pl. @ El. 884.0-El. 882.7	13.0						5
882.7	19.3									3
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. pl., ve. mst., subang. to rou. gravel, c. to f. sand	20.4						4
882.0	20.0									4

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-5A

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 902.03		Hole No. C-04-5A					
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 2 OF 5 SHEETS				
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
a	b	c	d							
878.0	24.0		GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. pl., ve. mst., subang. to rou. gravel, c. to f. sand mst., subang. gravel w/f. sand @ El. 881.0-El. 878.0	20.4						4
									14	
									3	
									3	
									5	
872.0	30.0	CL	LEAN CLAY WITH SAND (CL), gr., m. pl., mst., f. sand	20.7	35	23				4
									9	
									5	
									5	
									5	
869.3	32.7		SANDY LEAN CLAY WITH GRAVEL (CL), br., m. pl., mst., subang. gravel, f. sand	18.1	37	22				WH
									3	
									4	
									6	
									9	
866.8	35.2	CL-ML	SILTY CLAY (CL-ML), gr. and br., low pl., mst. w/wd. silty SH and SH frags. gr., dry @ El. 867.5-El. 866.8	16.2						5
									8	
									12	
									9	
									8	
		SH	SHALE: Gray, silty, mod. hard, laminated to very thin bedded, weathered to 862.2, effervescent starting at 862.2. 45° Fracture at 862.2, and from 856.1 to 855.6. Vertical fracture from 860.3 to 860.2. 20° Fracture at 859.5.	16.2	38	23				5
									8	
									12	
									9	
									8	
			SANDY LEAN CLAY WITH GRAVEL (CL), br., m. pl., mst., subang. gravel, f. sand	12.7						5
				6.4						8
				% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)		17		
								14		
								50/2		
			SHALE: Gray, silty, mod. hard, laminated to very thin bedded, weathered to 862.2, effervescent starting at 862.2. 45° Fracture at 862.2, and from 856.1 to 855.6. Vertical fracture from 860.3 to 860.2. 20° Fracture at 859.5.	REC 100%						
				RQD 0%	1					
				L 0.0						
				REC 100%						
				RQD 24%	2					
			SHALE: Gray, silty, mod. hard, laminated to very thin bedded, weathered to 862.2, effervescent starting at 862.2. 45° Fracture at 862.2, and from 856.1 to 855.6. Vertical fracture from 860.3 to 860.2. 20° Fracture at 859.5.	L 0.0						
				REC 100%						
				RQD 24%	2					
				L 0.0						
					3					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-5A

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 902.03		Hole No. C-04-5A	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				REC 100%	3	
		SH		RQD 38%	4	
				L 0.0		
851.6	50.4			REC 100%		
		LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded, fossiliferous.	RQD 90%	5	
				L 0.0		
847.6	54.4			REC 100%		
		SH	SHALE: Dark gray, mod. hard, carbonaceous, fossiliferous, calcareous in upper part, laminated.	RQD 45%	6	
					7	
843.3	58.7			L 0.0		
		SS	SANDSTONE: Gray, mod. hard, very fine grained, shaley, laminated. Light gray with brown and maroon crossbeds, hard from 837.3 to 835.8. 20° Fracture at 834.5.	REC 100%		
				RQD 93%	8	
				L 0.0		
				REC 100%		
					9	
				RQD 94%		
	68				10	

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 902.03		Hole No. C-04-5A		
PROJECT Dover Dam		INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 5 SHEETS		
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				L 0.0		
				REC 100%	10	
				RQD 98%		
		SS		L 0.0	11	
				REC 100%		
				RQD 98%	13	
823.3	78.7			L 0.0		
			SILTSTONE: Gray, mod. hard, shaley, laminated.	REC 100%	13	
			Sandy zone from 822.2 to 821.7, 821.0 to 820.9, 819.8 to 819.3 and 817.9 to 817.7.	RQD 90%		
		SLS		L 0.0	14	
817.5	84.5			REC 100%		
			SANDSTONE: Light gray, hard, med. grained, occasional silty shale, carbonaceous laminations, crossbedded, micaceous.	RQD 92%	15	
			Near vertical fracture from 811.1 to 810.7.			
			25° Fracture at 807.5.			
			Siltstone zone, dark gray from 807.1 to 804.8.			
			45° Fracture at 805.0.			
		SS	Occasional coal stringers in last 3.0'.	L 0.0		
				REC 100%	16	
				RQD 88%		
	92				17	

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 5 SHEETS
1. PROJECT Dover Dam			10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW	
2. LOCATION (Coordinates or Station) N 326580.98 E 2301918.29			11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29	
3. DRILLING AGENCY HC NUTTING			12. MANUFACTURER'S DESIGNATION OF DRILL CME 45	
4. HOLE NO. (As shown on drawing title and file number) C-04-6			13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 16 UNDISTURBED 0	
5. NAME OF DRILLER BRAGG			14. TOTAL NUMBER CORE BOXES 21	
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.			15. ELEVATION GROUND WATER 871.8	
7. THICKNESS OF OVERBURDEN 35.0 Feet			16. DATE HOLE STARTED 4/28/04 COMPLETED 5/5/04	
8. DEPTH DRILLED INTO ROCK 70.5 Feet			17. ELEVATION TOP OF HOLE 902.09 Feet	
9. TOTAL DEPTH OF HOLE 105.5 Feet			18. TOTAL CORE RECOVERY FOR BORING 99.3%	
			19. NAME OF INSPECTOR STEWART	

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% -4	% SAND	% -200	BLOWS
901.8	0.3	CL-ML	GRAVELLY SILTY CLAY WITH SAND (CL-ML). dk. br., low pl., mst., ang. gravel, f. sand w/tr. org.	28.6						3
		GP-GM	POORLY GRADED GRAVEL WITH SAND AND SILT (GP-GM), br., non pl., mst., subang. gravel, c. to f. sand w/SS frags.	8.5						5
										11
										7
										11
899.1	3.0									16
		SM	SILTY SAND WITH GRAVEL (SM), br., non pl., mst., ang. to rou. gravel, c. to f. sand	7.2			36	50	14	5
										11
										11
										10
										21
896.1	6.0									19
		GM	SILTY GRAVEL WITH SAND (GM), br., non pl., mst., ang. to rou. gravel, c. to f. sand	8.0						7
										13
										16
										10
										15
										11
										8
										8
										3
										2
										4
										7
890.1	12.0									
		SM	SILTY SAND WITH GRAVEL (SM), br., low to non pl., mst., subang. gravel, c. to f. sand	10.4			21	62	17	4
										5
										11
										5
										9
										10
			ve. mst. @ El. 887.0-El. 879.7							7
										13
										12
										9
										8
										8
										8
										13
										14
										7
882.1	20.0									
							19	65	16	

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-6

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 902.09		Hole No. C-04-6						
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT				SHEET 2 OF 5 SHEETS				
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS	
879.8	22.3	SM	SILTY SAND WITH GRAVEL (SM), br., low to non pl., mst., subang. gravel, c. to f. sand	10.0			19	65	16	7	
				12.0						6	
878.1	24.0	CL	GRAVELLY LEAN CLAY (CL), gr., m. pl., mst., subang. gravel w/tr. org. and chert	23.4						4	
									6		
876.6	25.5	SP-SM	POORLY GRADED SAND WITH GRAVEL AND SILT (SP-SM), lt. br., non pl., mst., subang. gravel, f. sand w/wd. SS	8.9						2	
									3		
873.6	28.5	CL	SANDY LEAN CLAY (CL), gr., m. pl., f. sand w/tr. SS frags.	17.3	36	21				16	
									22		
									8		
									6		
870.6	31.5	CL	SANDY LEAN CLAY (CL), gr., m. pl., mst., f. sand	15.9	35	21				5	
									8		
869.9	32.2	CL	SANDY LEAN CLAY WITH GRAVEL (CL), gr., m. to low pl., mst., subang. gravel, f. sand	14.9						9	
									4		
867.6	34.5	CL-ML	LEAN CLAY (CL), gr. & br., low pl., mst. to dry w/wd. silty SH	12.5						7	
				5.5					10		
				% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)	5				
867.1	35.0	CL-ML	SILTY CLAY (CL-ML), gr., low pl., dry w/wd. silty SH							9	
44		SH	SHALE: Gray, silty, soft to mod. hard, laminated, slightly effervescent starting at 860.6 and continues to 852.0.	REC 86%						35	
			Near vertical fracture from 865.5 to 863.6.	RQD 0%	1				50		
			Vertical fracture 859.8 to 859.5.								
			20° Fracture at 857.8.	L 0.5							
			45° Fracture at 856.3.	REC 100%							
		SH			2						
				RQD 46%							
					3						
		SH									

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-6

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 902.09		Hole No. C-04-6		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
852.0	50.1	SH		REC 100%	3	
				RQD 38%	4	
				L 0.0		
				REC 100%		
		LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded, fossiliferous.	RQD 82%	5	
				L 0.0		
				REC 100%	6	
847.4	54.7	SH	SHALE: Dark gray, mod. hard, calcareous in upper 0.6', fossiliferous, laminated. 45° Fracture at 846.9.	RQD 86%	7	
				L 0.0		
843.5	58.6	SS	SANDSTONE: Gray, hard, very fine grained, shaley, thick bedded. Light gray, med. grained and crossbedded from 836.4 to 835.3. 30° Fracture at 829.5. 50° Fracture from 821.2 to 820.8.	REC 100%	8	
				RQD 98%		
				L 0.0		
				REC 100%	9	
				RQD 96%	10	
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-6

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 902.09		Hole No. C-04-6	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 4 OF 5 SHEETS
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOV- ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				L 0.0	10	
				REC 100%		
				RQD 98%	11	
		SS		L 0.0	12	
				REC 100%		
				RQD 94%	13	
823.5	78.6			L 0.0		
			SILTSTONE: Gray, mod. hard, shaley, laminated.	REC 100%		
		SLS		RQD 90%	14	
				L 0.0		
818.1	84.0			REC 100%	15	
			SANDSTONE: Light gray, hard, med. grained, crossbedded in thick beds, micaceous, occasional silty-shale laminations and wavy stringers.	RQD 88%		
			Shaley, dark gray zone from 807.3 to 806.8 and 806.4 to 805.6.			
			Coal laminations from 797.8 to 797.4.			
			Zone with numerous fractures from 808.4 to 806.7.		16	
		SS		L 0.0		
				REC 100%		
				RQD 78%	17	
	92					

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 5 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326657.03 E 2302051.77				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-7				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 12 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 21						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 872.4						
7. THICKNESS OF OVERBURDEN 28.1 Feet				16. DATE HOLE STARTED 5/19/04 COMPLETED 5/21/04						
8. DEPTH DRILLED INTO ROCK 68.1 Feet				17. ELEVATION TOP OF HOLE 886.95 Feet						
9. TOTAL DEPTH OF HOLE 96.2 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR STEWART						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% -4	% SAND	% -200	BLOWS
883.7	3.3	GP	POORLY GRADED GRAVEL WITH SAND (GP), dk. gr., mst., subang. to ang. gravel, c. to f. sand w/LS frags.	6.5						3
			lt. br., subang. gravel w/SS frags. @ El. 885.4-El. 883.9	8.8						10
			gr., dry, ang. gravel w/wd. LS @ El. 883.9-El. 883.6	0.9						5
									23	
880.4	6.6			% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)				
879.5	7.5	NS	NO SAMPLE							AUGER
876.5	10.5	GP	POORLY GRADED GRAVEL WITH SAND (GP), gr. br., wet, subang. to ang. gravel w/SS & LS frags.	10.9						6
									6	
									4	
									5	
873.5	13.5	GP	POORLY GRADED GRAVEL (GP), gr. br., wet, subang. to ang. gravel w/SS frags.	8.9						9
									6	
									54	
									60	
870.5	16.5	GC	CLAYEY GRAVEL (GC), gr. br., m. pl., wet, subang. to rou. gravel w/SS frags. & alluvium	26.9						51
									45	
									56	
									51	
867.5	19.5	SW	WELL GRADED SAND WITH GRAVEL (SW), wet, subang. to ang. gravel, c. to f. sand w/SS frags., alluvium and sewer odor	17.9						57
									67	
									21	
									1	
867.0	20.0	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), br., low pl., wet, subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	14.0						20
									1	
									1	
									1	
										1
										WH
										WH

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-7

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 886.95		Hole No. C-04-7						
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT				SHEET 2 OF 5 SHEETS				
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% -4	% SAND	% -200	BLOWS	
864.5	22.5	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), br., low pl., wet, subang. to rou. gravel, c. to f. sand w/SS frags. and alluvium	14.0			29	50	21	WH 23 10 15 10	
863.0	24.0	GP	POORLY GRADED GRAVEL (GP), br., wet, ang. to rou. gravel w/SS frags. and alluvium	8.0						2 9 8	
860.0	27.0	CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. pl., ve. mst. to mst., subang. to rou. gravel, f. sand w/tr. wood frags.	23.1	41	23				3 6 7 4 8 7	
859.2	27.8	GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., m. pl., mst., ang. to rou. gravel, c. to f. sand w/SS and flint frags. and alluvium	14.3						12 46	
858.9	28.1	GP	POORLY GRADED GRAVEL WITH SAND (GP), gr. br., mst., subang. to ang. gravel, c. to f. sand w/ calcareous or concrete	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)					50/1
			CONCRETE: Drilled without sampling.	REC 100%							
				RQD	2						
				L 0.0							
				REC 100%							
		CON			3						
				RQD							
				L 0.0							
				REC 100%	4						
848.6	38.4										
			LIMESTONE: Dark gray, hard to very hard, fossiliferous.	RQD 100%							
					5						
				L 0.0							
		LS		REC 100%							
					6						
843.2	43.8			RQD 46%							
		SH									

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-7

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 886.95		Hole No. C-04-7	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
		SH	SHALE: Dark gray, carbonaceous, mod. hard. Fossiliferous from 843.2 to 842.9. Silty from 843.2 to 842.1.		6	
				L 0.0		
				REC 100%	7	
839.5	47.5		COAL: Black, Boney coal from 839.5 to 839.0. Vitreous from 839.0 to 838.2.			
		C	Vertical fracture from 839.5 to 839.0.	RQD 39%		
838.8	48.2					
		SS	SANDSTONE: Gray, mod. hard, fine grained laminated and shaley with shale stringers and occasional interbeds. Silty from 817.7 to 817.2. Wavy laminations from 815.8 to 815.6.		8	
				L 0.0		
				REC 100%		
				RQD 100%	9	
				L 0.0		
				REC 100%		10
				RQD 100%		
				L 0.0		11
				REC 100%		
				RQD 100%		12
			L 0.0			
			REC 100%		13	

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-7

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 886.95		Hole No. C-04-7	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant) g
		SS		RQD 92%	13	
815.6	71.4			L 0.0	14	
		SLS	SILTSTONE: Gray, mod. hard, laminated, shaley, effervescent. Vertical fracture from 813.3 to 813.0.	REC 100%		
				RQD 76%	15	
				L 0.0		
809.1	77.9			REC 100%	16	
			SANDSTONE: Light gray, hard, crossbedded, med. to coarse grained, micaceous. Several very thin lenses of dark gray, very soft clay from 807.9 to 807.8. Vertical surface crack from 804.0 to 803.8. Coal stringers from 798.5 to 798.2. Coal laminations averaging 0.01' thick from 792.6 to 791.5. Vertical fracture from 791.9 to 791.5.	RQD 90%		
				L 0.0	17	
				REC 100%		
		SS		RQD 90%	18	
				L 0.0		
				REC 100%		
				RQD 84%	19	
				L 0.0	20	
	92			REC 100%		

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-7

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 4 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326222.98 E 2302153.36				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-8				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 18 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 17						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.				15. ELEVATION GROUND WATER 869.3						
7. THICKNESS OF OVERBURDEN 27.3 Feet				16. DATE HOLE STARTED 6/4/04 COMPLETED 6/5/04						
8. DEPTH DRILLED INTO ROCK 56.0 Feet				17. ELEVATION TOP OF HOLE 885.38 Feet						
9. TOTAL DEPTH OF HOLE 83.3 Feet				18. TOTAL CORE RECOVERY FOR BORING 99.3%						
				19. NAME OF INSPECTOR KISER						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
885.1	0.3	NS	NO SAMPLE - TOPSOIL							3
		CL	SANDY LEAN CLAY (CL), br. gr., low pl., mst., f. sand w/tr. org. and SH frags.	13.5						4
										4
										3
										4
882.4	3.0									4
		GC	CLAYEY GRAVEL WITH SAND (GC), br. gr., low pl., mst., subang. gravel, f. sand w/SH and SS frags.	11.1			30	21	49	3
			br. and gr. w/SLS frags. @ El. 880.8-El. 879.3							4
				10.6	28	19	30	29	41	3
879.4	6.0									4
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), br. gr., low pl., mst., subang. to rou. gravel, f. sand w/SS frags. and alluvium	14.8			25	24	51	3
877.9	7.5									4
		CL	SANDY LEAN CLAY WITH GRAVEL (CL), br. gr., low pl., mst., subang. to rou. gravel, f. sand w/tr. SH frags., flint, and alluvium	14.3	30	20	20	29	51	6
876.4	9.0									9
		SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), br. gr., low pl., mst., ang. to rou. gravel, f. sand w/tr. org., SS frags., and alluvium	11.6			23.4	14.6	35	4
874.9	10.5									6
		GM	SILTY GRAVEL WITH SAND (GM), br. & gr., low to non pl., mst., ang. to rou. gravel, c. to f. sand w/flint and SS frags.	7.2						18
			br. gr., low pl. w/alluvium @ El. 873.3-El. 871.8							32
				12.1	29	23				18
871.8	13.5									7
		SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), br. gr., low pl., mst., ang. to rou. gravel, c. to f. sand w/flint, alluvium, and SS frags.	9.0			35	37	28	4
			br. and gr. subang. to rou. gravel @ El. 870.3-El. 868.8							11
				9.0						9
868.9	16.5									7
		GC	CLAYEY GRAVEL WITH SAND (GC), gr., low pl., wet to ve. mst., subang. gravel, c. to f. sand w/SS and SLS frags.	13.8			36	35	29	4
867.3	18.0									4
		GW-GC	WELL GRADED GRAVEL WITH SAND AND SILTY CLAY (GW-GC), br., low pl., wet, subang. to ang. gravel, c. to f. sand w/SS and SLS frags.	12.7						8
865.9	19.5									7
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), dk. gr., m. to low pl., ve. mst. to mst., subang. gravel, f. sand w/SS and SH frags.	13.9						11
865.4	20.0									10
										2

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-8

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 885.38		Hole No. C-04-8					
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 2 OF 4 SHEETS				
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
862.9	22.5	CL	GRAVELLY LEAN CLAY WITH SAND (CL), dk. gr., m. to low pl., ve. mst. to mst., subang. gravel, f. sand w/SS and SH frags. gr. br., low pl., ve. mst. @ El. 864.3-El. 862.8	13.9						11
				16.4	27	18			3	
									5	
								6		
861.4	24.0		SANDY LEAN CLAY WITH GRAVEL (CL), gr., m. pl., ve. mst., f. sand	17.9					2	
									2	
									3	
859.9	25.5		GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. pl., ve. mst. to mst., subang. gravel, f. sand w/SS and SH frags. and alluvium	11.4			34	15	51	5
										5
										32
858.2	27.3	GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), gr. & br., low pl., mst. to dry, subang. to ang. gravel, c. to f. sand w/wd. sandy SH frags.	9.6						26
				8.6					9	
								9		
									50/3	
854.2	31.2	SLS	Siltstone boulders and cobbles overlying about 0.8' of sandy lean clay with gravel.	% CORE RECOVERY REC 95%	BOX OR SAMPLE NO. 1	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) 9				
				RQD N/A						
				L 0.2						
849.4	36.0	LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded grading into underlying shale at 849.4, fossiliferous.	REC 96%	2					
				RQD 96%						
				L 0.2						
844.5	40.9	SH	SHALE: Dark gray to black, mod. hard, laminated, carbonaceous, fossiliferous in upper portion. 30° Fracture at 848.8.	REC 100%	3					
				RQD 34%						
				L 0.0						
844.3	41.1	C	COAL: Black, vitreous.		4					
841.9	43.5	SH	SHALE: Gray, mod. hard, silty, laminated, gradational into underlying sandstone at 842.8.	RQD 44%	5					
	44	SS		L 0.0						

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-8

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 885.38		Hole No. C-04-8	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 3 OF 4 SHEETS
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SANDSTONE: Light gray to gray, mod. hard, very fine grained, very silty, thin to thick bedded.	REC 100%		
		SS		RQD 96%	6	
				L 0.0		
				REC 100%	7	
				RQD 90%		
833.0	52.2					
			SANDSTONE: Light gray to gray, mod. hard to hard, fine to medium grained, zones silty, thin to thick bedded, occasional shale stringers and laminations throughout, cross-bedded zones below 825.6, micaceous.	L 0.0	8	
			Sholey from 830.4 to 829.2.	REC 100%		
			Shale layer, dark gray from 820.4 to 820.2.			
		SS		RQD 94%	9	
				L 0.0	10	
				REC 100%		
				RQD 88%	11	
				L 0.0		
				REC 100%	12	
820.2	65.2					
			SANDSTONE: Light gray to gray, mod. hard to hard, medium to coarse grained, thin to thick bedded, occasional shale stringers and laminations and zones throughout, zones cross-bedded, micaceous.	RQD 96%		
		SS			13	
	68			L 0.0		

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-8

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 885.38		Hole No. C-04-8		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			Sandstone continued: Occasional cool stringers and laminations from 812.8 to 803.6, especially at 804.9.	REC 100%		
				RQD 87%	14	
				L 0.0		
				REC 100%	15	
		SS		RQD 86%	16	
				L 0.0		
				REC 100%	17	
				RQD 65%		
802.1	83.3			L 0.0		
			BOTTOM OF HOLE @ 802.1			
	92					

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 4 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326266.66 E 2302196.73				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-9				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 16 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 16						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 870.0						
7. THICKNESS OF OVERBURDEN 30.1 Feet				16. DATE HOLE STARTED 6/3/04 COMPLETED 6/4/04						
8. DEPTH DRILLED INTO ROCK 52.0 Feet				17. ELEVATION TOP OF HOLE 884.82 Feet						
9. TOTAL DEPTH OF HOLE 82.1 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR KISER						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% -4	% SAND	% -200	BLOWS
883.3	1.5	CL	SANDY LEAN CLAY WITH GRAVEL (CL), br., low pl., mst., subang. gravel, f. sand w/SH frags.	14.9						3
881.8	3.0	CL	SANDY LEAN CLAY (CL), br., m. pl., mst., f. sand w/tr. SH frags.	16.3	33	21				3
880.3	4.5	GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), br., low pl., mst., subang. gravel, f. sand	10.1						4
877.3	7.5	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), gr., low pl., mst., subang. to rou. gravel, f. sand	13.8			16	44	40	6
875.8	9.0	GM	SILTY GRAVEL WITH SAND (GM), dk. gr., low to non pl., mst., subang. to ang. gravel, f. sand w/ SLS frags.	11.3						20
874.3	10.5	CL-ML	GRAVELLY SILTY CLAY WITH SAND (CL-ML), gr. br., low pl., mst., subang. gravel, f. sand w/ tr. SH frags.	14.2			25	24	51	1
872.8	12.0	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), gr. br., low pl., mst., subang. gravel, f. sand w/ SS frags.	11.4			35	41	24	2
868.3	16.5	GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), gr. br., low pl., ve. mst., subang. to rou. gravel, f. sand w/SS frags. and alluvium wet @ El. 871.3-El. 868.3	15.5						2
				15.5			40	39	21	4
865.3	19.5	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), gr. br., low pl., wet, ang. gravel, c. to f. sand w/SS frags. and alluvium	16.1			39	41	20	2
864.8	20.0	CL	GRAVELLY LEAN CLAY WITH SAND (CL), m. pl., wet to ve. mst., subang. to rou. gravel, c. to f. sand	20.5			29	20	51	0

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-9

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 884.82		Hole No. C-04-9						
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT							SHEET 2 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% -4	% SAND	% -200	BLOWS	
862.3	22.5	CL	GRAVELLY LEAN CLAY WITH SAND (CL), m. pl., wet to ve. mst., subang. to rou. gravel, c. to f. sand	20.5			29	20	51	0 1 0 1 1	
854.8	30.0	GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., low pl., wet, subang. gravel, f. sand w/SH and SS frags. m. pl. @ El. 859.3-El. 854.8	22.7	32	22	31	20	49	WH WH WH 0 0 1 0 1 2	
854.7	30.1	NS	gr., subang. to ang. gravel w/SS and flint frags. @ El. 856.3-El. 854.8	23.4	36	22	31	20	49	0 0 1 2	
854.7	30.1	NS	NO RECOVERY	25.4			31	20	49	0 0 1 1 2 3	
850.3	34.5	LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, medium to thick bedded, grades into underlying shale at 850.3, fossiliferous. Near vertical fracture from 854.7 to 854.0. Weathered bedding plane at 850.3.	REC 100% RQD 68% L 0.0	1					REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) 9	
845.9	38.9	SH	SHALE: Dark gray to black, mod. hard, laminated, carbonaceous, fossiliferous in upper part. Near vertical fracture from 846.2 to 845.7.	REC 100% RQD 86% L 0.0	2						
845.7	39.1	C	COAL: Black, v. tereous	REC 100% RQD 49% L 0.0	3						
843.8	41.0	SH	SHALE: Gray, mod. hard, laminated, silty to sandy, grades into very fine grained sandstone below 843.8.	REC 100% RQD 92% L 0.0	4						
	44	SS	SANDSTONE: Gray, mod. hard, very fine grained, silty, thin to thick bedded, grades to siltstone below 836.9.								

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-9

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 884.82		Hole No. C-04-9		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
836.9	47.9	SS		REC 100%	5	
				RQD 98%		
834.2	50.6	SLS	SILTSTONE: Gray, mod. hard, shaley, sandy, laminated to thin bedded.	L 0.0	6	
				REC 100%		
			SANDSTONE: Gray, mod. hard to hard, fine to medium grained, cross-bedded, micaceous, scattered shaley stringers and laminations. Silty to shaley from 831.3 to 830.7 and from 829.0 to 828.6. Shaley from 828.2 to 828.1, 826.9 to 826.8, and from 822.7 to 822.6.	RQD 100%	7	
				L 0.0		
				REC 100%	8	
		SS		RQD 80%		
				L 0.0	9	
				REC 100%		
				RQD 98%	10	
820.7	64.1			L 0.0		
		SS	SANDSTONE: Light gray to gray, mod. hard to hard, medium to coarse grained, zones cross-bedded, medium to thick bedded, occasional shale stringers and laminations throughout, micaceous. Shaley from 818.5 to 818.3. Shale layer at 20° angle from 812.8 to 812.0. (continued on following page)	REC 100%	11	
				RQD 94%		
	68			L 0.0		

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-9

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 4 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326328.49 E 2302312.07				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-10				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 20 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 16						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 863.1						
7. THICKNESS OF OVERBURDEN 29.7 Feet				16. DATE HOLE STARTED 6/7/04 COMPLETED 6/8/04						
8. DEPTH DRILLED INTO ROCK 52.3 Feet				17. ELEVATION TOP OF HOLE 886.15 FEET						
9. TOTAL DEPTH OF HOLE 82.0 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR KISER						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% -4	% SAND	% -200	BLOWS
885.9	0.3	NS	NO SAMPLE-TOPSOIL							1
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	16.4						2
884.7	1.5	CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/SH and SS frags.	14.3						4
										3
883.2	3.0									4
										5
		GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., m. pl., mst., subang. to rou. gravel, c. to f. sand w/ alluvium	13.1						2
			gr., low pl. w/SS frags. @ El. 881.6-El. 880.1							3
				12.9	27	19				7
880.2	6.0									4
										4
		GP-GM	POORLY GRADED GRAVEL WITH SAND AND SILT (GP-GM), gr., non pl., mst., subang. to ang. gravel, c. to f. sand w/wd. SS	6.2			61	28	11	26
879.0	7.2									40
878.7	7.5	NS	NO SAMPLE							50/2
										AUGER
		GM	SILTY GRAVEL WITH SAND (GM), gr., non pl., dry, subang. to ang. gravel, c. to f. sand w/SS and SLS frags	8.3						7
										7
877.2	9.0									12
		GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., low pl., mst., subang. to ang. gravel, f. sand	11.7	29	19				4
										5
875.7	10.5									4
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/SS frags.	17.4						2
										3
874.2	12.0									3
		GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., low pl., mst., subang. to ang. gravel, c. to f. sand w/SS frags. and alluvium	17.0			30	21	49	3
										16
872.7	13.5									9
		SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), gr. & br., low pl., mst., subang. to rou. gravel, f. sand	13.2						1
										5
871.2	15.0									5
										3
		CL	GRAVELLY LEAN CLAY WITH SAND (CL), lt. br., m. to low pl., mst., subang. gravel, f. sand w/SS frags.	15.7						3
869.7	16.5									6
										3
		CL	LEAN CLAY WITH SAND (CL), m. pl., mst., f. sand	17.5	37	22				4
868.2	18.0									6
										4
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/SH frags.	16.2						5
866.7	19.5									8
			GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. to low pl., mst., subang. gravel w/wd. sandy SH and SH frags.	15.7						4
866.2	20.0									4

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-10

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 886.15		Hole No. C-04-10					
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT			SHEET 2 OF 4 SHEETS				
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
865.2	21.0	CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. to low pl., mst., subang. gravel w/wd. sandy SH frags.	15.7						4
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/SH frags.	16.4	35	21				7
863.7	22.5									3
										5
862.2	24.0	GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., m. to low pl., mst., subang. gravel, c. to f. sand w/SS frags.	14.0						6
										3
860.7	25.5	GP-GM	POORLY GRADED GRAVEL WITH SAND AND SILT (GP-GM), gr. br., non pl., wet to ve. mst., subang. gravel, c. to f. sand w/SS frags.	12.4						5
										6
859.2	27.0	SM	SILTY SAND WITH GRAVEL (SM), gr. br., non pl., wet, subang. gravel, c. to f. sand w/SS frags.	15.2			25	54	21	11
										24
857.7	28.5	CL	LEAN CLAY WITH SAND (CL), gr., low pl., mst., f. sand w/wd. SH frags.	12.6						6
										10
856.5	29.7	CL-ML	SILTY CLAY (CL-ML), gr., low pl., mst. w/wd. silty SH	11.5						6
										18
										19
										39
										50/2
		LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, thin to thick bedded, grades into underlying shale at 851.8, fossiliferous.	REC 100% RQD 49% L 0.0	BOX OR SAMPLE NO. 1					
			Vertical fracture from 856.4 to 855.6.	REC 100%						
851.9	34.3			RQD 82%						
		SH	SHALE: Dark gray to black, mod. hard, laminated, carbonaceous, fossiliferous in upper part.	L 0.0 REC 100%	2					
848.0	38.2				3					
847.9	38.3	C	COAL: Black, low quality (shaley)	RQD 67%						
		SH	SHALE: Gray to dark gray, soft to mod. hard, laminated, silty.							
845.2	41.0			L 0.0	4					
		SLS	SILTSTONE: Gray, mod. hard, silty to sandy, zones very sandy, thin to thick bedded.	REC 100%						
			Sandy zone from 842.1 to 840.0.	RQD 98%						
	44			L 0.0	5					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-10

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 886.15		Hole No. C-04-10		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 4 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
		SLS			5	
				REC 100%	6	
838.0	48.2			RQD 100%	7	
			SANDSTONE WITH INTERBEDDED SHALE: Sandstone is gray, mod. hard to hard, fine to medium grained, thin to thick bedded, micaceous, occasional shale stringers. Shale is gray, mod. hard, silty to sandy, laminated, thin bedded. Siltstone zone from 835.1 to 834.1.	L 0.0 REC 100%		
		SS		RQD 90%	8	
				L 0.0 REC 100%	9	
827.4	58.8			RQD 76%		
			SANDSTONE: Gray, hard, fine to medium grained, thin to thick bedded, micaceous, shaley zones. Shaley zone from 821.0 to 820.8 and from 817.9 to 817.5.	L 0.0 REC 100%	10	
		SS		RQD 93%	11	
				L 0.0 REC 100%	12	
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-10

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 2 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326188.34 E 2302264.46				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-11				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 12 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 3						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 888.4						
7. THICKNESS OF OVERBURDEN 19.0 Feet				16. DATE HOLE STARTED 6/6/04 COMPLETED 6/6/04						
8. DEPTH DRILLED INTO ROCK 10.3 Feet				17. ELEVATION TOP OF HOLE 901.80 FEET						
9. TOTAL DEPTH OF HOLE 29.3 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR KISER						
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
901.4	0.4	NS	NO SAMPLE-TOPSOIL							1
			SANDY LEAN CLAY WITH GRAVEL (CL), br., low pl., mst. to dry, subang. gravel, f. sand	12.6						4
900.3	1.5									4
		CL	SANDY LEAN CLAY (CL), br., m. pl., mst., f. sand	15.6						4
898.8	3.0									6
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/tr. wood frags.	15.7			19	21	60	4
897.3	4.5									6
		GC	CLAYEY GRAVEL WITH SAND (GC), br., m. pl., mst., subang. to rou. gravel, c. to f. sand	14.3	32	20				3
895.8	6.0									3
			GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. to low pl., mst., subang. gravel, f. sand w/ SH frags.	16.4			25	24	51	3
894.3	7.5									3
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. to low pl., mst., subang. to rou. gravel, f. sand	17.9						3
892.8	9.0									4
		CL	SANDY LEAN CLAY (CL), gr., m. pl., mst., f. sand	19.7			11	36	53	3
891.3	10.5									3
			GRAVELLY LEAN CLAY WITH SAND (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/SS and SH frags.	13.7	30	21				2
889.8	12.0									5
			SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	14.5						3
888.3	13.5									3
		SC	CLAYEY SAND WITH GRAVEL (SC), gr. br., m. pl., mst., subang. gravel, f. sand	9.8	29	18				5
886.8	15.0									2
		SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), low pl., mst., subang. gravel, c. to f. sand w/ SS frags.	12.4			40	40	20	3
885.3	16.5									3
		GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), low pl., mst., subang. gravel, c. to f. sand w/ SS and SLS frags.	11.0						3
882.9	18.9									15
882.8	19.0	NS	NO RECOVERY							3
		LS	LIMESTONE: Gray, hard, fine to med. crystalline grained, fossiliferous.	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant)				
LRH FORM 1836 MAY 04				PROJECT Dover Dam		HOLE NO. C-04-11				

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 901.80		Hole No. C-04-11	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 2 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. If significant) g
881.3	20.5	LS	60° Fracture from 882.8 to 882.3.	REC 100%		
880.6	21.2	C	COAL: Black, vitreous, shaley zone from 881.0 to 880.8	RQD 22%	1	
		SH	SHALE: Gray, soft to mod. hard, silty to clayey, laminated, grades into silty to sandy shale below 877.1. Vertical fracture from 876.8 to 876.3.	L 0.0 REC 100%	2	
877.1	24.7			RQD 0%		
		SH	SHALE: Gray, mod. hard, silty to sandy, zones very sandy, occasional siderite nodules below 874.8. Near vertical fracture from 875.2 to 874.8. Iron stained zone from 874.8 to 873.3. Weathered and water stained near vertical fracture from 874.6 to 873.3. Vertical fracture from 873.2 to 872.9.	L 0.0 REC 100% RQD 19%	3	
872.5	29.3			L 0.0		
			BOTTOM OF HOLE @ 872.5			

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-11

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 2 SHEETS
1. PROJECT Dover Dam		10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW		
2. LOCATION (Coordinates or Station) N 326271.34 E 2302355.30		11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29		
3. DRILLING AGENCY HC NUTTING		12. MANUFACTURER'S DESIGNATION OF DRILL CME 45		
4. HOLE NO. (As shown on drawing title and file number) C-04-12		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 11 UNDISTURBED 0		
5. NAME OF DRILLER		14. TOTAL NUMBER CORE BOXES 3		
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.		15. ELEVATION GROUND WATER 877.2		
7. THICKNESS OF OVERBURDEN 23.7 Feet		16. DATE HOLE STARTED 6/14/04 COMPLETED 6/14/04		
8. DEPTH DRILLED INTO ROCK 10.6 Feet		17. ELEVATION TOP OF HOLE 901.71 FEET		
9. TOTAL DEPTH OF HOLE 34.3 Feet		18. TOTAL CORE RECOVERY FOR BORING 100%		
		19. NAME OF INSPECTOR		

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% -4	% SAND	% -200	BLOWS
901.1	0.6	CL-ML	GRAVELLY SILTY CLAY WITH SAND (CL-ML), gr. br., low pl., ve. mst., subang. to rou. gravel, f. sand w/tr. rts., SH frags. and org. odor	14.5			30	19	51	2
										4
										4
										11
898.7	3.0	CL	SANDY SILTY CLAY WITH GRAVEL (CL-ML), gr. br., low pl., mst., subang. gravel, f. sand	15.3	33	21				7
										5
										3
										3
895.7	6.0	CL	SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand w/chemical odor	10.7						8
										2
										3
										56
892.7	9.0	GC-GM	SILTY CLAYEY GRAVEL WITH SAND (GC-GM), low pl., mst., subang. to ang. gravel, f. sand w/SLS frags.	15.8						73
										8
										57
										7
886.7	15.0	CL	SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	16.9	30	21	20	29	51	6
										3
										2
										2
884.2	17.5	SC-SM	SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	12.9						2
										2
										3
										7
882.2	19.5	CH	SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	23.4	51	27				3
										2
										9
										4
881.7	20.0	CH	SANDY LEAN CLAY WITH GRAVEL (CL), gr. br., m. pl., mst., subang. gravel, f. sand	31.1						2
										2

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-12

DRILLING LOG		DIVISION Great Lakes and Ohio River		INSTALLATION CELRH-EC-G		SHEET 1 OF 5 SHEETS				
1. PROJECT Dover Dam				10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW						
2. LOCATION (Coordinates or Station) N 326143.71 E 2302370.21				11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29						
3. DRILLING AGENCY HC NUTTING				12. MANUFACTURER'S DESIGNATION OF DRILL CME 45						
4. HOLE NO. (As shown on drawing title and file number) C-04-13				13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 7 UNDISTURBED 0						
5. NAME OF DRILLER BRAGG				14. TOTAL NUMBER CORE BOXES 24						
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED 0 DEG. FROM VERT.				15. ELEVATION GROUND WATER 920.4						
7. THICKNESS OF OVERBURDEN 16.9 Feet				16. DATE HOLE STARTED 5/25/04 COMPLETED 6/2/04						
8. DEPTH DRILLED INTO ROCK 82.0 Feet				17. ELEVATION TOP OF HOLE 934.03 Feet						
9. TOTAL DEPTH OF HOLE 98.9 Feet				18. TOTAL CORE RECOVERY FOR BORING 100%						
				19. NAME OF INSPECTOR STEWART						
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	MC	LL	PL	% +4	% SAND	% -200	BLOWS
931.0	3.0	SC	CLAYEY SAND WITH GRAVEL (SC), gr., m. pl., mst., subang. gravel, c. to f. sand w/wood frags.	33.5	39	28				3 3 5 3 4 7
928.0	6.0	SC-SM	SILTY CLAYEY SAND WITH GRAVEL (SC-SM), gr. br., low pl., mst., subang. to rou. gravel, c. to f. sand	9.5			35	39	26	4 7 8 6 6 5
920.0	14.0	CL-ML	GRAVELLY SILTY CLAY WITH SAND (CL-ML), gr. br., low pl., mst., subang. gravel, f. sand w/tr. wood frags. no wood frags. @ El. 925.0-El. 920.0 ve. mst. @ El. 922.0-El. 920.0	12.9 17.3 20.8		35 22				4 7 8 2 3 4 2 2 2 1 2 3 1 2 3 4 17 25 18 50 27 50/.4
917.1	16.9		GRAVELLY SILTY CLAY (CL-ML), gr., low pl., dry, ang. gravel w/wd. silty SH	4.6						
916.4	17.6	SH	SHALE: Dark gray to black, soft to mod. hard, silty, laminated.	4.2						
916.1	17.9	C	BONE COAL: Black							
		SS	SANDSTONE: Gray, hard, med. to coarse grained, micaceous, cross-bedded in thin to thick beds. Iron stained zone from 902.3 to 900.9.	REC 100% ROD 99% L 0.0 REC 100%	BOX OR SAMPLE NO. 1					REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-13

DRILLING LOG (Cont Sheet)

ELEVATION TOP OF HOLE

934.03

Hole No. C-04-13

PROJECT

Dover Dam

INSTALLATION

HUNTINGTON DISTRICT

SHEET 2

OF 5 SHEETS

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	% CORE RECOVER- ERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if signif/cant)
a	b	c	d	e	f	g
			SANDSTONE continued:	RQD 92%	2	
			Vertical fracture from 892.0 to 890.7.			
			Iron stained zone from 893.0 to 889.7.			
			Vertical fracture from 890.5 to 889.7.			
				L 0.0		
				REC 100%	3	
				RQD 93%		
				L 0.0	4	
				REC 100%		
		SS		RQD 100%	5	
				L 0.0		
				REC 100%	6	
				RQD 100%		
				L 0.0	7	
				REC 100%		
				RQD 62%	8	
				L 0.0		
	44					

LRH FORM 1836-A

PROJECT

Dover Dam

HOLE NO.

C-04-13

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 934.03		Hole No. C-04-13		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. if significant) g
889.7	44.3	SS	SHALE: Dark gray, mod. hard, laminated, scattered siderite nodules.	REC 100%		
		SH		RQD 52%	9	
885.0	49.0			L 0.0		
		LS	LIMESTONE: Gray, hard, fine to medium crystalline grained, fossiliferous, thin bedded.	REC 100%	10	
883.0	51.0					
882.2	51.8	C	COAL: Black, vitreous, interbedded with very few shale laminations.	RQD 78%		
		SS	Healed vertical fracture from 883.9 to 883.0			
880.8	53.2		SANDSTONE: Light gray, mod. hard to hard, very fine grained, fossiliferous, silty.		11	
		SH	Black in color from 882.2 to 884.2.	L 0.0		
879.4	54.6		30° Fracture at 880.6.	REC 100%		
		SH/SS	SHALE: Gray, mod. hard, silty, thin to thick bedded, occasional carbonaceous shale stringers.		12	
			30° Fracture at 878.2.	RQD 100%		
876.1	57.9		INTERBEDDED SANDSTONE AND SHALE: Light gray (SS), dark gray (SH), mod. hard to hard.			
			SHALE: Dark gray, mod. hard	L 0.0	13	
				REC 100%		
				RQD 100%		
		SH			14	
				L 0.0		
				REC 100%		
					15	
				RQD 100%		
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-13

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 904.03		Hole No. C-04-13		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 4 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
				L 0.0 REC 100%		
				RQD 100%	16	
		SH		L 0.0 REC 100%	17	
				RQD 100%	18	
855.0	79.0			L 0.0		
			LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded grading into underlying shale at 849.5, fossiliferous.	REC 100%		
		LS		RQD 90%	19	
849.5	84.5			L 0.0 REC 100%	20	
			SHALE: Dark gray to black, mod. hard, silty, laminated, carbonaceous, fossiliferous in upper part.	RQD 96%		
		SH		L 0.0	21	
844.7	89.3			REC 100%		
844.4	89.6	C	COAL: Black, vitreous.			
			SHALE: Gray, mod. hard, silty, thin to thick bedded.	RQD 80%	22	
	92	SH				

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-13

[illegible]

DRILLING LOG		DIVISION Great Lakes and Ohio River	INSTALLATION CELRH-EC-G	SHEET 1 OF 5 SHEETS
1. PROJECT Dover Dam		10. SIZE AND TYPE OF BIT 4" CORE AND 3" HOLLOW		
2. LOCATION (Coordinates or Station) N 326162.96 E 2302396.76		11. DATUM FOR ELEVATION SHOWN (TBM or MSL) NGVD 29		
3. DRILLING AGENCY HC NUTTING		12. MANUFACTURER'S DESIGNATION OF DRILL CME 45		
4. HOLE NO. (As shown on drawing title and file number) C-04-14		13. TOTAL NO. OF OVER-BURDEN SAMPLES TAKEN DISTURBED 8 UNDISTURBED 0		
5. NAME OF DRILLER BRAGG		14. TOTAL NUMBER CORE BOXES 25		
6. DIRECTION OF HOLE <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED _____ DEG. FROM VERT.		15. ELEVATION GROUND WATER 918.1		
7. THICKNESS OF OVERBURDEN 18.3 Feet		16. DATE HOLE STARTED 5/23/04 COMPLETED 5/24/04		
8. DEPTH DRILLED INTO ROCK 82.8 Feet		17. ELEVATION TOP OF HOLE 933.94 Feet		
9. TOTAL DEPTH OF HOLE 101.1 Feet		18. TOTAL CORE RECOVERY FOR BORING 100%		
		19. NAME OF INSPECTOR STEWART		

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	MC	LL	PL	% +4	% SAND	% -200	BLOWS
930.9	3.0	CL	GRAVELLY LEAN CLAY WITH SAND (CL), gr., m. to low pl., mst., subang. to ang. gravel, c. to f. sand w/ flint and coal frags.				30	19	51	2 2 2 3 5 12
927.9	6.0	GC	CLAYEY GRAVEL WITH SAND (GC), gr. br., m. pl., mst., subang. gravel, c. to f. sand	9.3	32	21				5 10 10 4 4 5
924.9	9.0	SC	CLAYEY SAND WITH GRAVEL (SC), gr. and br., m. pl., mst., subang. to rou. gravel, c. to f. sand	17.2			19	33	48	2 4 4 2 3 4
920.9	13.0	CL	LEAN CLAY WITH GRAVEL (CL), gr., m. pl., mst., subang. gravel	19.5	35	23				1 3 4 2 2 3
918.9	15.0	CL-ML	SILTY CLAY (CL-ML), gr., low pl., dry w/wd. silty SH	6.9						2 2 18 6 15 16
915.9	18.0	CL	SILTY CLAY WITH GRAVEL (CL-ML), gr., low pl., dry, subang. gravel w/wd. SH	5.1						19 25 44 15 26 42
915.6	18.3	CL	LEAN CLAY (CL), low pl., mst. to dry w/wd. silty SH	9.6						50/3
915.0	18.9	SH	SHALE: Dark gray to black, soft to mod. hard, silty, laminated.	% CORE RECOVERY	BOX OR SAMPLE NO.	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant)				
914.7	19.2	C	BONE COAL: Black	REC 100%	1					
		SS	SANDSTONE: (description on following page)							

LRH FORM 1836
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-14

DRILLING LOG (Cont Sheet)			ELEVATION TOP OF HOLE 933.94		Hole No. C-04-14	
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 2 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
			SANDSTONE: Ligth gray and gray, hard, med. to coarse grained, micaceous, cross-bedded in thin to thick beds. Vertical fracture from 913.9 to 912.9. 45° Fracture at 912.0. 45° Fracture at 910.9. Occasional coal stringers from 909.9 to 907.2. 30° Fracture at 907.1.	RQD 30%	1	
				L 0.0		
				REC 100%		
				RQD 85%	2	
				L 0.0		
				REC 100%	3	
				RQD 98%		
				L 0.0		
		SS	REC 100%			
			RQD 100%	5		
			L 0.0			
			REC 100%		6	
			RQD 100%			
			L 0.0			
			REC 100%		7	
			RQD 94%		8	

DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE 933.94		Hole No. C-04-14		
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET 3 OF 5 SHEETS	
ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVER- ERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) g
889.7	44.2	SS	SHALE: Dark gray, mod. hard, laminated, silty. 45° Fracture at 889.3. 45° Fracture at 887.0. Slickensided at 885.6.	L 0.0 REC 100%	8	
		SH	Vertical fracture and siderite from 884.6 to 884.3. Carbonaceous and fossiliferous zone from 884.3 to 883.2.	RQD 82%	9	
883.2	50.7					
882.1	51.8	LS	LIMESTONE: Gray to dark gray, hard, fine to med. crystalline grained, fossiliferous, thin bedded.	L 0.0 REC 100%	10	
881.1	52.8	C	COAL: Black, vitreous, pyritic.			
879.8	54.1	SS	SANDSTONE: Light gray, mod. hard to hard, very fine grained, silty.	RQD 72%		
		SH	SHALE: Gray, mod. hard, laminated. 45° Fracture at 879.1.		11	
877.8	56.1			L 0.0		
		SH/SS	INTERBEDDED SANDSTONE AND SHALE: Light gray (SS), dark gray (SH), mod. hard to hard. 60° Fracture from 859.6 to 859.0.	REC 100%	12	
874.0	59.9			RQD 100%		
		SH	SHALE: Dark gray, mod. hard. Effervescent from 874.9 to 854.0.	L 0.0 REC 100%	13	
				RQD 100%	14	
				L 0.0 REC 100%	15	
	68					

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam

HOLE NO.
C-04-14

DRILLING LOG (Cont Sheet)

ELEVATION TOP OF HOLE

933.94

Hole No. C-04-14

PROJECT

Dover Dam

INSTALLATION

HUNTINGTON DISTRICT

SHEET 4

OF 5 SHEETS

ELEVATION a	DEPTH b	LEGEND c	CLASSIFICATION OF MATERIALS (Description) d	% CORE RECOVERY e	BOX OR SAMPLE NO. f	REMARKS (Drilling time, water loss, depth of weathering, etc. If significant) g
				RQD 100%	15	
				L 0.0 REC 100%	16	
		SH		RQD 88%		
				L 0.0 REC 100%	17	
				RQD 92%	18	
854.0	79.9					
			LIMESTONE: Gray, hard, fine to med. crystalline grained, thick bedded, fossiliferous.	L 0.0 REC 100%	19	
		LS		RQD 86%		
848.5	85.4				20	
			SHALE: Dark gray to black, mod. hard, laminated, carbonaceous, fossiliferous in upper part.	L 0.0 REC 100%		
		SH	35° Fracture with slight slickensides at 848.4. Slickensided at 845.6. 45° Fracture at 845.5.	RQD 68%	21	
844.2	89.7					
843.9	90.0	C	COAL: Black, vitreous.			
			SHALE: Gray, mod. hard, silty, laminated.	L 0.0 REC 100%	22	
		SH	45° Fracture with slickensides at 843.8. (Continued on following page)			
	92					

LRH FORM 1836-A
MAY 04

PROJECT

Dover Dam

HOLE NO.

C-04-14



DRILLING LOG (Cont Sheet)		ELEVATION TOP OF HOLE	933.94		Hole No.	C-04-14
PROJECT Dover Dam			INSTALLATION HUNTINGTON DISTRICT		SHEET OF 5 SHEETS	5
ELEVATION <i>a</i>	DEPTH <i>b</i>	LEGEND <i>c</i>	CLASSIFICATION OF MATERIALS (Description) <i>d</i>	% CORE RECOVERY <i>e</i>	BOX OR SAMPLE NO. <i>f</i>	REMARKS (Drilling time, water loss, depth of weathering, etc., if significant) <i>g</i>
838.3	95.6	SH	SHALE continued: 60° Fracture with slickensides from 842.9 to 842.4. 45° Fracture with slight slickensides at 841.9. 45° Fracture at 840.3.	ROD 74%	22	
				L 0.0 REC 100%	23	
		SS	SANDSTONE: Gray, hard, fine grained, micaceous, shaley. Silty zone from 838.3 to 836.7. Silty zone from 834.0 to 833.0	ROD 100%	24	
833.0	100.9			L 0.0	25	
			BOTTOM OF HOLE @ 833.0			

LRH FORM 1836-A
MAY 04

PROJECT
Dover Dam
HOLE NO.
C-04-14

EXHIBIT II-5

OVERBURDEN SECTIONS



- ## NOTES
1. Soil stratigraphies, as shown, and corresponding strength parameters were provided to CELRH-EC-DS (Structural Design Section) for use in stability analyses.
 2. Assumed some as upstream in Situ Soils (~50-60% fines) due to no available data from 2004 borings in downstream left abutment (C-04-8, 9, & 11). Borings C-04-8 and C-04-9 are located in uncompacted backfill behind retaining wall and C-04-11 is located in uncompacted backfill adjacent to downstream side of dam.
 3. Labeled as rolled embankment. However, this zone is not labeled so on as-built drawing. Assumed materials uncompacted backfill due to its soil classification (50% fines) and location (placed over in Situ Soils), as well as average blow count value (N=8), which is similar to uncompacted backfill elsewhere at the site. However, due to its limited use on site, it was not included in the table of soil strength parameters (Table II-4). (See Tab II, Sec. 6.2.6)

[illegible]

Designed by: EC-QS		Date: 11/14/2005	Rev.
Drawn by: SCL	Chk by:	Design file no.	
Reviewed by:		Drawing code:	
Submitted by: SCL		File name: B3025G.dgn Plot date: Plot number: 1' = 1'	

U.S. ARMY CORPS OF ENGINEERS
HUNTINGTON DISTRICT
HUNTINGTON, WEST VIRGINIA

TUSCAWARAS RIVER
DOVER, OH
DOVER DAM
DAM SAFETY ASSURANCE

GEOTECHNICAL
LEFT ABUTMENT OVERBURDEN
SECTION AT MONOLITH #17

Sheet
reference
number:
B1302
Sheet 1 of 1

EXHIBIT II-6

ROCK LABORATORY TEST DATA

	Cross Bed Shear Intact Peak (ϕ) (c) psi	Shear Parallel to Bedding Natural Fracture Peak (ϕ) (c) psi	Basic phi angle Smooth Sawn Surface (ϕ) (c) psi	Bedrock Dam Interface Grout on Rock Peak (ϕ) (c) psi	Allowable Bearing psi	E ₁₅₀ Elastic Modulus (x10 ⁶)	Unit Weight
Limestone	65 150 psi***	39 7 psi	29 0 psi	50 33 psi*****	2191	24.740	168.5 pcf
Upper Sandstone	64 88 psi***	28 3 psi	26 0 psi	50 70 psi*****	522	2.050	148 pcf
Sandy Siltstone	46 20 psi***	26 2 psi	21 0 psi	50 60 psi*****	829	2.970	159.7 pcf
Siltstone	31 15 psi***	25 1.5 psi	14 0 psi	31 60 psi*****	873	2.750	165.8 pcf
Shale	29 5 psi***	19 .5 psi	12.5 0 psi	30 50 psi*****	300	1.750	161.5 pcf
Fault/Slickensided Joint**	19* 0 psi						
Concrete Key Lift Joint**		38 Controlled by Rebar**					

Shear Parallel to Bedding when used with the key should be reduced by 50% due to strain incompatibility with the rebar

*The cross bed shear strength assigned to the (Fault / Slickensided Joint) is the average of the basic phi angle for all of the materials except the Upper Sandstone.


The Upper Sandstone was excluded because it is not a component in the passive wedge of the 3 monoliths analyzed.

**The cohesion value used in the concrete key is assigned by structural section and is not published here.

***The cross bed shear cohesion was taken directly from the intact peak lower bound plot except cohesion was then reduced by 50 percent to account for scaling effects.


****The cohesion was taken directly from the lower bound plot of the grout on rock peak except cohesion was reduced by 66 percent to represent portions in the monolith where the contact is not bonded.

DOVER DAM LIMESTONE-INTACT PEAK




x Shear Tests - - - - - Linear Regression ——— Lower Bound


DOVER DAM UPPER SANDSTONE-INTACT PEAK



DOVER DAM SANDY SILTSTONE-INTACT PEAK



DOVER DAM SHALE-INTACT PEAK



**Summary of Rock Testing Results
Direct Shear of Intact Rock Specimens**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Limestone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DS-103	1	C-04-03	82.7	40.0 80.0 120.0	1,224.4	32.2 ⁽¹⁾ 74.5 109.9
DS-104	2	C-04-03	85.1	80.0 40.0 120.0	1,120.2	99.5 41.8 128.5
DS-105	3	C-04-06	51.7	120.0 40.0 80.0	1,991.0	58.4 ⁽¹⁾ 15.4 29.7
DS-106	4	C-04-06	52.3	40.0 80.0 120.0	1,513.2	22.0 ⁽¹⁾ 55.4 83.5
DS-107	5	C-04-06	53.0	80.0 40.0 120.0	1,860.6	81.8 ⁽¹⁾ 39.1 113.9
DS-108	6	C-04-05A	54.2	120.0 40.0 80.0	1,351.1	122.1 41.1 82.8
DS-109	7	C-04-13	50.3	40.0 80.0 120.0	186.0	54.3 77.6 100.2
DS-110	8	C-04-09	31.2	80.0 40.0 120.0	1,298.8	30.0 ⁽¹⁾ 18.0 50.3
DS-111	9	C-04-09	34.3	120.0 40.0 80.0	546.8	140.1 50.3 84.9

Note(s): (1). Shear plane extended in Hydro-stone encasement and additional preparation was performed prior to additional shearing.

**Summary of Rock Testing Results
Direct Shear of Intact Rock Specimens**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Upper Sandstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DS-76	1	C-04-01	13.5	40.0 80.0 120.0	272.1	15.2 ⁽¹⁾ 30.9 47.9
DS-77	2	C-04-01	14.2	80.0 40.0 120.0	354.3	79.4 35.5 112.7
DS-78	3	C-04-01	16.1	120.0 40.0 80.0	574.1	99.5 40.0 64.0
DS-79	4	C-04-01	43.1	40.0 80.0 120.0	365.2	42.5 67.5 91.0
DS-80	5	C-04-01	45.3	80.0 40.0 120.0	372.7	78.5 28.6 93.2
DS-81	6	C-04-14	32.1	120.0 40.0 80.0	461.9	130.6 42.3 76.8
DS-82	7	C-04-14	35.9	40.0 80.0 120.0	271.0	55.1 63.5 ⁽²⁾ 85.5
DS-83	8	C-04-14	38.5	80.0 40.0 120.0	325.2	117.0 47.0 129.8
DS-84	9	C-04-13	41.2	120.0 40.0 80.0	429.7	109.2 35.9 70.4

Note(s): (1). Shear plane extended in Hydro-stone encasement and additional preparation was performed prior to additional shearing.

(2). Equipment malfunction caused premature termination of second test.

**Summary of Rock Testing Results
Direct Shear of Intact Rock Specimens**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone / Sandy

<u>FMSM ID No.</u>	<u>USACE Test No.</u>	<u>Boring</u>	<u>Depth (feet)</u>	<u>Normal Stress (psi)</u>	<u>Peak Shear Stress (psi)</u>	<u>Post Peak Shear Stress (psi)</u>
DS-85	1	C-04-06	59.2	40.0	96.4	38.5
				80.0		71.9
				120.0		92.5
DS-86	2	C-04-06	63.1	80.0	189.2	47.0
				40.0		26.8
				120.0		67.3
DS-87	3	C-04-06	70.7	120.0	100.4	67.0
				40.0		25.3
				80.0		44.0
DS-88	4	C-04-06	90.5	40.0	287.5	38.0
				80.0		67.5
				120.0		90.0
DS-89	5	C-04-06	98.3	80.0	506.2	139.9
				40.0		N/A ⁽¹⁾
				120.0		N/A ⁽¹⁾
DS-90	6	C-04-09	52.8	120.0	243.1	77.6
				40.0		24.7
				80.0		45.5
DS-91	7	C-04-09	53.75	40.0	291.4	23.8
				80.0		41.6
				120.0		66.5
DS-92	8	C-04-09	57.7	80.0	492.1	49.5 ⁽²⁾
				40.0		20.4
				120.0		63.5
DS-93	9	C-04-09	67.6	120.0	143.6	63.2
				40.0		17.0
				80.0		30.8

Note(s): (1). Specimen deteriorated during initial test, prohibiting additional tests.

(2). Shear plane extended in Hydro-stone encasement and additional preparation was performed prior to additional shearing.

**Summary of Rock Testing Results
Direct Shear of Intact Rock Specimens**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DS-112	1	C-04-04	96.1	40.0 80.0 120.0	74.6	30.7 53.6 71.1
DS-113	2	C-04-04	96.6	80.0 40.0 120.0	262.2	81.4 44.3 116.3
DS-114	3	C-04-04	97.0	120.0 40.0 80.0	89.6	N/A ⁽¹⁾ 24.9 46.9
DS-115	4	C-04-06	79.1	40.0 80.0 120.0	67.1	30.2 50.9 70.2
DS-116	5	C-04-06	82.5	80.0 40.0 120.0	235.5	52.1 21.3 N/A ⁽²⁾
DS-117	6	C-04-05A	80.5	120.0 40.0 80.0	84.1	70.1 22.0 40.5
DS-118	7	C-04-05A	82.0	40.0 80.0 120.0	111.4	32.4 50.1 62.8
DS-119	8	C-04-09	49.7	80.0 40.0 120.0	36.7	24.6 11.6 29.6
DS-120	9	C-04-10	43.3	120.0 40.0 80.0	198.2	90.6 19.3 44.0

Note(s): (1). Stable sliding resistance not achieved in 0.5-inch deflection.
(2). Specimen deteriorated during second test, prohibiting additional tests.

**Summary of Rock Testing Results
Direct Shear of Intact Rock Specimens**


**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Shale


FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DS-94	1	C-04-01	62.0	40.0 80.0 120.0	40.6	21.8 34.1 52.2
DS-95	2	C-04-01	68.7	80.0 40.0 120.0	77.8	50.1 21.4 72.8
DS-96	3	C-04-01	71.0	120.0 40.0 80.0	173.4	69.7 23.6 40.6
DS-97	4	C-04-13	46.0	40.0 80.0 120.0	61.1	36.8 ⁽¹⁾ 42.4 ⁽¹⁾ 25.4 ⁽¹⁾
DS-98	5	C-04-13	47.5	80.0 40.0 120.0	50.8	30.7 15.7 39.3
DS-99	6	C-04-13	48.2	120.0 40.0 80.0	1,916.5	N/A ⁽²⁾ N/A ⁽²⁾ N/A ⁽²⁾
DS-100	7	C-04-13	48.4	40.0 80.0 120.0	19.1	16.8 ⁽¹⁾ 34.1 ⁽¹⁾ N/A ⁽³⁾
DS-101	8	C-04-13	91.0	80.0 40.0 120.0	90.2	71.7 34.4 80.6
DS-102	9	C-04-13	92.9	120.0 40.0 80.0	134.1	58.1 16.5 30.3

Note(s): (1). Specimen shear surfaces deteriorated with each test.
(2). Specimen deteriorated during initial test, prohibiting additional tests.
(3). Stable sliding resistance not achieved in 0.5-inch deflection.


DOVER DAM LIMESTONE-NATURAL FRACTURE PEAK




DOVER DAM UPPER SANDSTONE-NATURAL FRACTURE PEAK




DOVER DAM SANDY SILTSTONE-NATURAL FRACTURE PEAK



DOVER DAM SILTSTONE-NATURAL FRACTURE PEAK



DOVER DAM SHALE-NATURAL FRACTURE PEAK



x Shear Tests - - - - - Linear Regression — Lower Bound

**Summary of Rock Testing Results
Direct Shear of Natural Rock Fractures**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Limestone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSNF-28	1	C-04-03	84.2	40.0	40.7	30.1
				80.0		56.7
				120.0		82.0
DSNF-29	2	C-04-06	50.3	80.0	82.0	50.9
				40.0		29.3
				120.0		84.7
DSNF-30	3	C-04-06	53.4	120.0	114.3	80.4
				40.0		30.3
				80.0		61.1
DSNF-31	4	C-04-11	20.2	40.0	30.6	26.2
				80.0		47.5
				120.0		71.2
DSNF-32	5	C-04-02	64.6	80.0	69.6	62.6
				40.0		33.0
				120.0		93.4
DSNF-33	6	C-04-14	83.7	120.0	136.7	91.8
				40.0		33.8
				80.0		60.7

**Summary of Rock Testing Results
Direct Shear of Natural Rock Fractures**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Upper Sandstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSNF-1	1	C-04-01	17.2	40.0	29.8	24.1
				80.0		42.0
				120.0		60.1
DSNF-2	2	C-04-01	17.8	80.0	43.0	34.5
				40.0		16.0
				120.0		48.3
DSNF-3	3	C-04-01	19.0	120.0	72.9	62.5
				40.0		22.9
				80.0		44.6
DSNF-4	4	C-04-01	22.5	40.0	26.0	24.2
				80.0		45.2
				120.0		64.8
DSNF-5	5	C-04-01	40.9	80.0	N/A ⁽¹⁾	52.5
				40.0		25.8
				120.0		N/A ⁽²⁾
DSNF-6	6	C-04-14	34.6	120.0	81.9	70.7
				40.0		26.3
				80.0		48.5
DSNF-7	7	C-04-14	37.1	40.0	28.5	24.2
				80.0		45.6
				120.0		65.3
DSNF-8	8	C-04-14	39.0	80.0	41.8	38.0
				40.0		21.7
				120.0		58.1
DSNF-9	9	C-04-14	40.5	120.0	N/A ⁽¹⁾	58.3
				40.0		20.6
				80.0		38.2

Note(s): (1). No apparent peak shear stress was observed for initial test.

(2). Stable sliding resistance not achieved in 0.5-inch deflection.

**Summary of Rock Testing Results
Direct Shear of Natural Rock Fractures**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone / Sandy

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSNF-10	1	C-04-06	60.8	40.0	28.2	18.9
				80.0		31.1
				120.0		37.5
DSNF-11	2	C-04-06	64.5	80.0	48.7	31.9
				40.0		N/A ⁽¹⁾
				120.0		N/A ⁽¹⁾
DSNF-12	3	C-04-06	65.2	120.0	57.5	51.3
				40.0		14.2
				80.0		24.5
DSNF-13	4	C-04-06	67.9	40.0	14.1	13.6
				80.0		N/A ⁽²⁾
				120.0		N/A ⁽²⁾
DSNF-14	5	C-04-06	67.3	80.0	33.7	27.6
				40.0		12.4
				120.0		36.5
DSNF-15	6	C-04-06	91.0	120.0	51.4	49.8
				40.0		16.8
				80.0		31.4
DSNF-16	7	C-04-09	52.0	40.0	23.8	20.1
				80.0		33.5
				120.0		47.3
DSNF-17	8	C-04-09	62.6	80.0	29.7	26.7
				40.0		11.0
				120.0		N/A ⁽²⁾
DSNF-18	9	C-04-09	65.1	120.0	90.6	76.4
				40.0		27.9
				80.0		48.5

Note(s): (1). Specimen deteriorated during initial test, prohibiting additional tests.

(2). Stable sliding resistance not achieved in 0.5-inch deflection.

**Summary of Rock Testing Results
Direct Shear of Natural Rock Fractures**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone

<u>FMSM ID No.</u>	<u>USACE Test No.</u>	<u>Boring</u>	<u>Depth (feet)</u>	<u>Normal Stress (psi)</u>	<u>Peak Shear Stress (psi)</u>	<u>Post Peak Shear Stress (psi)</u>
DSNF-37	1	C-04-04	98.2	40.0 80.0 120.0	11.8	10.9 15.5 22.5
DSNF-38	2	C-04-06	81.7	80.0 40.0 120.0	N/A ⁽¹⁾	37.1 19.4 54.0
DSNF-39	3	C-04-05A	81.3	120.0 40.0 80.0	68.8	43.5 19.6 32.6
DSNF-40	4	C-04-10	42.9	40.0 80.0 120.0	15.9	14.1 26.4 31.7
DSNF-41	5	C-04-10	45.4	80.0 40.0 120.0	47.2	30.1 16.2 39.2
DSNF-42	6	C-04-07	71.8	120.0 40.0 80.0	66.0	50.4 17.6 32.0
DSNF-43	7	C-04-07	73.1	40.0 80.0 120.0	N/A ⁽¹⁾	14.0 26.3 37.0
DSNF-44	8	C-04-07	73.5	80.0 40.0 120.0	N/A ⁽¹⁾	26.0 15.4 36.7
DSNF-45	9	C-04-07	74.9	120.0 40.0 80.0	60.3	47.7 17.1 30.6

Note(s): (1). No apparent peak shear stress was observed for initial test.

**Summary of Rock Testing Results
Direct Shear of Natural Rock Fractures**


**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Shale


FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSNF-19	1	C-04-01	59.6	40.0 80.0 120.0	17.7	16.5 N/A ⁽¹⁾ N/A ⁽¹⁾
DSNF-20	2	C-04-01	68.0	80.0 40.0 120.0	50.1	30.1 19.0 36.7
DSNF-21	3	C-04-01	69.5	120.0 40.0 80.0	57.1	49.0 15.4 24.3
DSNF-22	4	C-04-13	46.9	40.0 80.0 120.0	13.4	12.9 19.6 28.3
DSNF-23	5	C-04-13	47.8	80.0 40.0 120.0	22.7	17.5 11.2 27.6
DSNF-24	6	C-04-13	86.5	120.0 40.0 80.0	34.1	32.1 9.7 18.1
DSNF-25	7	C-04-13	88.5	40.0 80.0 120.0	14.4	12.3 17.6 29.3
DSNF-26	8	C-04-06	43.1	80.0 40.0 120.0	38.5	30.1 15.0 44.3
DSNF-27	9	C-04-06	43.8	120.0 40.0 80.0	N/A ⁽²⁾	N/A ⁽³⁾ 14.4 21.6

Note(s): (1). Specimen deteriorated during initial test, prohibiting additional tests.
(2). No apparent peak shear stress was observed for initial test.
(3). Stable sliding resistance not achieved in 0.5-inch deflection.


DOVER DAM LIMESTONE-SAWN SURFACES POST PEAK




DOVER DAM UPPER SANDSTONE-SAWN SURFACES POST PEAK




DOVER DAM SANDY SILTSTONE-SAWN SURFACES POST PEAK



DOVER DAM SILTSTONE-SAWN SURFACES POST PEAK



DOVER DAM SHALE-SAWN SURFACES POST PEAK



**Summary of Rock Testing Results
Direct Shear of Rock-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Limestone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSSS-64	1	C-04-05A	50.8	40.0	N/A ⁽¹⁾	22.5
				80.0		46.3
				120.0		71.7
DSSS-65	2	C-04-05A	51.4	80.0	N/A ⁽¹⁾	39.2
				40.0		19.2
				120.0		58.7
DSSS-66	3	C-04-05A	53.7	120.0	N/A ⁽¹⁾	68.8
				40.0		10.2
				80.0		20.1
DSSS-67	4	C-04-09	31.7	40.0	N/A ⁽¹⁾	21.8
				80.0		40.1
				120.0		71.2
DSSS-68	5	C-04-09	33.6	80.0	N/A ⁽¹⁾	44.2
				40.0		23.5
				120.0		73.0
DSSS-69	6	C-04-13	80.2	120.0	N/A ⁽¹⁾	63.0
				40.0		17.8
				80.0		37.7

Note(s): (1). No apparent peak shear stress was observed for initial test.

**Summary of Rock Testing Results
Direct Shear of Rock-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Upper Sandstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSSS-46	1	C-04-01	19.8	40.0	N/A ⁽¹⁾	20.8
				80.0		42.0
				120.0		61.4
DSSS-47	2	C-04-01	21.7	80.0	N/A ⁽¹⁾	41.1
				40.0		19.6
				120.0		61.2
DSSS-48	3	C-04-01	41.6	120.0	N/A ⁽¹⁾	59.4
				40.0		18.7
				80.0		38.0
DSSS-49	4	C-04-14	22.4	40.0	N/A ⁽¹⁾	16.2
				80.0		35.8
				120.0		52.0
DSSS-50	5	C-04-13	37.9	80.0	N/A ⁽¹⁾	40.5
				40.0		20.3
				120.0		62.6
DSSS-51	6	C-04-13	39.2	120.0	N/A ⁽¹⁾	65.2
				40.0		19.1
				80.0		39.4

Note(s): (1). No apparent peak shear stress was observed for initial test.

**Summary of Rock Testing Results
Direct Shear of Rock-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone / Sandy

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSSS-52	1	C-04-06	62.2	40.0 80.0 120.0	17.0	14.1 26.2 36.7
DSSS-53	2	C-04-06	69.7	80.0 40.0 120.0	38.3	35.9 18.6 50.0
DSSS-54	3	C-04-06	92.0	120.0 40.0 80.0	N/A ⁽¹⁾	65.9 19.9 39.9
DSSS-55	4	C-04-09	50.9	40.0 80.0 120.0	17.2	15.6 31.5 46.6
DSSS-56	5	C-04-09	68.9	80.0 40.0 120.0	N/A ⁽¹⁾	39.4 18.9 58.7
DSSS-57	6	C-04-09	71.5	120.0 40.0 80.0	61.2	60.3 20.4 39.6

Note(s): (1). No apparent peak shear stress was observed for initial test.

Summary of Rock Testing Results
Direct Shear of Rock-on-Rock Sawn Surfaces

Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio

Siltstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSSS-70	1	C-04-04	97.4	40.0	18.6	13.5
				80.0		25.6
				120.0		30.9
DSSS-71	2	C-04-04	98.8	80.0	26.1	16.5
				40.0		9.9
				120.0		27.3
DSSS-72	3	C-04-06	80.3	120.0	41.2	30.3
				40.0		10.0
				80.0		16.6
DSSS-73	4	C-04-06	83.3	40.0	N/A ⁽¹⁾	13.1
				80.0		21.9
				120.0		35.0
DSSS-74	5	C-04-05A	80.9	80.0	24.9	17.1
				40.0		9.2
				120.0		21.1
DSSS-75	6	C-04-10	47.9	120.0	39.7	27.6
				40.0		8.7
				80.0		15.2

Note(s): (1). No apparent peak shear stress was observed for initial test.


Summary of Rock Testing Results
Direct Shear of Rock-on-Rock Sawn Surfaces

Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio


Shale

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSSS-58	1	C-04-06	44.6	40.0 80.0 120.0	13.8	10.5 17.3 26.9
DSSS-59	2	C-04-05A	43.0	80.0 40.0 120.0	28.9	20.0 10.4 29.2
DSSS-60	3	C-04-05A	43.8	120.0 40.0 80.0	39.4	28.2 8.4 16.2
DSSS-61	4	C-04-05A	44.2	40.0 80.0 120.0	13.5	8.5 16.0 24.1
DSSS-62	5	C-04-05A	45.3	80.0 40.0 120.0	26.1	18.2 7.5 22.2
DSSS-63	6	C-04-05A	45.7	120.0 40.0 80.0	47.7	35.1 11.2 20.1

DOVER DAM LIMESTONE-GROUT-ON-ROCK SAWN SURFACES PEAK




DOVER DAM LIMESTONE-GROUT-ON-ROCK SAWN SURFACES POST PEAK




x Shear Tests - - - - - Linear Regression - - - - - Lower Bound


DOVER DAM UPPER SANDSTONE-GROUT-ON-ROCK SAWN SURFACES PEAK




DOVER DAM UPPER SANDSTONE-GROUT-ON-ROCK SAWN SURFACES POST PEAK




DOVER DAM SANDY SILTSTONE-GROUT-ON-ROCK SAWN SURFACES PEAK




DOVER DAM SANDY SILTSTONE-GROUT-ON-ROCK SAWN SURFACES POST PEAK




DOVER DAM SILTSTONE-GROUT-ON-ROCK SAWN SURFACES PEAK




DOVER DAM SILTSTONE-GROUT-ON-ROCK SAWN SURFACES POST PEAK



DOVER DAM SHALE-GROUT-ON-ROCK SAWN SURFACES PEAK



DOVER DAM SHALE-GROUT-ON-ROCK SAWN SURFACES POST PEAK



Summary of Rock Testing Results
Direct Shear of Grout-on-Rock Sawn Surfaces

Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio

Limestone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSGR-148	1	C-04-06	53.8	40.0 80.0 120.0	43.6	24.3 38.0 53.0
DSGR-149	2	C-04-06	54.2	80.0 40.0 120.0	359.2	33.6 21.4 66.9
DSGR-150	3	C-04-05A	53.3	120.0 40.0 80.0	233.7	56.1 19.5 37.7
DSGR-151	4	C-04-09	32.1	40.0 80.0 120.0	183.0	29.3 51.1 74.3
DSGR-152	5	C-04-09	34.0	80.0 40.0 120.0	60.8	40.7 18.1 56.6
DSGR-153	6	C-04-09	33.1	120.0 40.0 80.0	251.8	59.5 16.6 37.0
DSGR-154	7	C-04-11	20.0	40.0 80.0 120.0	26.2	24.5 45.2 66.1
DSGR-155	8	C-04-13	79.6	80.0 40.0 120.0	432.7	53.1 27.0 83.6
DSGR-156	9	C-04-13	83.1	120.0 40.0 80.0	502.6	64.2 19.6 42.4

**Summary of Rock Testing Results
Direct Shear of Grout-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Upper Sandstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSGR-121	1	C-04-01	20.4	40.0 80.0 120.0	328.5	24.8 49.9 72.9
DSGR-122	2	C-04-01	38.5	80.0 40.0 120.0	297.6	56.3 23.7 76.7
DSGR-123	3	C-04-01	39.2	120.0 40.0 80.0	316.1	84.1 24.6 52.6
DSGR-124	4	C-04-01	45.7	40.0 80.0 120.0	451.3	31.8 60.7 76.1
DSGR-125	5	C-04-01	46.7	80.0 40.0 120.0	448.2	61.2 31.0 85.7
DSGR-126	6	C-04-14	32.9	120.0 40.0 80.0	490.3	79.1 24.5 48.7
DSGR-127	7	C-04-14	39.8	40.0 80.0 120.0	318.6	26.7 52.8 80.8
DSGR-128	8	C-04-13	38.7	80.0 40.0 120.0	461.1	56.8 27.4 75.3
DSGR-129	9	C-04-13	40.8	120.0 40.0 80.0	428.3	84.0 24.0 49.1

Summary of Rock Testing Results
Direct Shear of Grout-on-Rock Sawn Surfaces

Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio

Siltstone / Sandy

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSGR-130	1	C-04-06	62.6	40.0	267.8	17.9
				80.0		35.0
				120.0		49.4
DSGR-131	2	C-04-06	63.9	80.0	178.2	47.1
				40.0		24.4
				120.0		62.1
DSGR-132	3	C-04-06	89.4	120.0	437.8	91.5
				40.0		26.8
				80.0		55.1
DSGR-133	4	C-04-06	101.3	40.0	316.8	26.0
				80.0		52.9
				120.0		82.5
DSGR-134	5	C-04-09	53.2	80.0	420.7	51.2
				40.0		22.9
				120.0		77.5
DSGR-135	6	C-04-09	56.9	120.0	266.6	81.7 ⁽¹⁾
				40.0		32.5
				80.0		52.1
DSGR-136	7	C-04-09	66.5	40.0	280.3	27.8
				80.0		49.8
				120.0		74.1
DSGR-137	8	C-04-09	66.8	80.0	426.7	48.7
				40.0		24.4
				120.0		73.0
DSGR-138	9	C-04-09	70.7	120.0	456.5	80.7
				40.0		24.1
				80.0		52.9

Note(s): (1). Shear plane extended in Hydro-stone encasement and additional preparation was performed prior to additional shearing.

**Summary of Rock Testing Results
Direct Shear of Grout-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Siltstone

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSGR-157	1	C-04-06	79.6	40.0 80.0 120.0	446.4	21.1 56.6 88.7
DSGR-158	2	C-04-06	83.0	80.0 40.0 120.0	353.7	32.6 15.7 48.1
DSGR-159	3	C-04-06	83.75	120.0 40.0 80.0	291.9	62.4 ⁽¹⁾ 18.6 30.8
DSGR-160	4	C-04-05A	83.8	40.0 80.0 120.0	88.6	29.9 51.6 70.4
DSGR-161	5	C-04-10	46.6	80.0 40.0 120.0	238.0	41.5 15.6 55.8
DSGR-162	6	C-04-10	47.3	120.0 40.0 80.0	253.8	65.6 16.5 39.2
DSGR-163	7	C-04-07	72.3	40.0 80.0 120.0	294.5	24.5 45.5 65.4
DSGR-164	8	C-04-07	72.6	80.0 40.0 120.0	257.3	38.1 17.4 47.9
DSGR-165	9	C-04-07	75.6	120.0 40.0 80.0	366.3	67.4 16.5 33.7

Note(s): (1). Shear plane extended in Hydro-stone encasement and additional preparation was performed prior to additional shearing.

**Summary of Rock Testing Results
Direct Shear of Grout-on-Rock Sawn Surfaces**

**Dover Dam Rock Testing
Dover, Tuscarawas County, Ohio**

Shale

FMSM ID No.	USACE Test No.	Boring	Depth (feet)	Normal Stress (psi)	Peak Shear Stress (psi)	Post Peak Shear Stress (psi)
DSGR-139	1	C-04-13	92.4	40.0 80.0 120.0	206.9	20.0 31.9 46.0
DSGR-140	2	C-04-13	93.6	80.0 40.0 120.0	321.6	42.5 15.6 54.9
DSGR-141	3	C-04-06	42.1	120.0 40.0 80.0	250.9	59.4 17.4 32.7
DSGR-142	4	C-04-05A	40.4	40.0 80.0 120.0	161.7	20.3 36.5 48.6
DSGR-143	5	C-04-05A	41.1	80.0 40.0 120.0	187.2	36.5 17.3 47.9
DSGR-144	6	C-04-05A	41.8	120.0 40.0 80.0	254.4	56.3 18.8 33.6
DSGR-145	7	C-04-05A	43.5	40.0 80.0 120.0	189.2	19.1 32.6 47.3
DSGR-146	8	C-04-05A	44.4	80.0 40.0 120.0	233.7	39.8 20.5 54.9
DSGR-147	9	C-04-05A	44.8	120.0 40.0 80.0	209.9	52.8 17.4 29.6

DOVER - LIMESTONE ALLOWABLE BEARING CAPACITY

INPUT PARAMETERS

c = cohesion:	150 psi	Required input for equations 6-1, 6-4, 6-5, 6-6	21600.0 psf
ϕ = phi angle:	65 degree	Required input for all equations	
D=depth of foundation below ground surface:	3 ft	Required input for equations 6-1, 6-3	
γ = effective unit weight of the rock mass:	98 pcf	Required input for equations 6-1, 6-3, 6-4	
B = width of the foundation:	35 ft	Required input for equations 6-1, 6-3, 6-4, 6-6, Goodman	
J = correction factor (see figure 6-2 of EM 1110-1-2908):	1.0	Required input for equation 6-6	
L = length of foundation:	65.0 ft	Required input for equation 6-6 (strip foundation shape) and L/B ratio	
S = Joint spacing:	20.0 ft	Required input for equations 6-6 and Goodman	
(q_u) = unconfined compressive strength:	19353 psi	Required input for equations 6-7 (cohesion equation) and Goodman	
(RMR) Rock Mass Rating:	37	Required input for equations 6-7 (cohesion equation)	
FS = factor of safety (min. 3, see eq. 6-11 EM 1110-1-2908):	3	Required input for all equations, separate Goodman FS input.	

COHESION EQUATION (equation 6-7)

$$s = 0.001$$


$$(c) \text{ cohesion} = 2 \text{ psi}$$

MISCELLANEOUS STEPS

$N_q = \tan^2(45 + \phi/2)$	20.33				
$N_\gamma = N_q^{1/2}(N_q^2 - 1)$	1858.44	1765.52	1672.59	1579.67	1300.91
$N_c = N_q^2$	413.20				
$N_c = 2N_q^{1/2}(N_q + 1)$	192.31	201.93	215.39	240.39	230.77
$N_{\alpha} = 2N_q^{1/2} + N_q (\cot \phi) (S/B) (1 - 1/N_q) - N_q (\cot \phi) + 2N_q^{1/2}$	9.4				

COMPRESSIVE FAILURE (equation 6-5, EM 1110-1-2908)

MODE: open, near vertical joint set(s) $S < B$: compressive failure of individual rock columns.




$$q_{ult} = 2c \tan(45 + \phi/2)$$

q_{ult} = ultimate bearing capacity	1353 psi
q_a = allowable bearing capacity	451 psi

GENERAL SHEAR FAILURE WITHOUT COHESION (equation 6-3, EM 1110-1-2908)

MODE 1: moderately dipping joint set(s) $S < B$ or $S > B$: general shear failure with potential for failure along joints.

MODE 2: two or more closely spaced joint sets. $S < B$: general shear failure with irregular failure surface through rock mass.



$$q_{ult} = 0.5\gamma B N_\gamma + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

q_{ult} = ultimate bearing capacity


q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
3308701 psf	3149340 psf	2989979 psf	2830618 psf	2352535 psf
22977 psi	21870 psi	20764 psi	19657 psi	16337 psi
7659 psi	7290 psi	6921 psi	6552 psi	5446 psi

GENERAL SHEAR FAILURE WITH COHESION (equation 6-1, EM 1110-1-2908)

MODE 1: ductile, intact rock or with few joints $S > B$: general shear failure along well defined failure surfaces.

MODE 2: Closed, near vertical joint set(s) $S < B$: general shear failure along well defined failure surfaces.



$$q_{ult} = cN_c + 0.5\gamma B N_\gamma + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
7462639 psf	7510975 psf	7642389 psf	8023040 psf	7337261 psf
51824 psi	52160 psi	53072 psi	55716 psi	50953 psi
17275 psi	17387 psi	17691 psi	18572 psi	16984 psi

LOCAL SHEAR FAILURE (equation 6-4, EM 1110-1-2908)

MODE: brittle intact rock or with few joints $S > B$: local shear failure caused by localized brittle fracture



$$q_{ult} = cN_c + 0.5\gamma B N_\gamma$$

$$L/B \text{ ratio: } 1.8571$$


q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
7341158 psf	7389494 psf	7520909 psf	7901560 psf	7215780 psf
50980 psi	51316 psi	52229 psi	54872 psi	50110 psi
16993 psi	17105 psi	17410 psi	18291 psi	16703 psi

SPLITTING FAILURE (equation 6-6, EM 1110-1-2908)

MODE: open or closed, widely spaced and vertical joints $S > B$: Failure initiated by splitting leading to general shear failure.



q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=<32	square	circular
554 psi	1193 psi	1403 psi
185 psi	398 psi	468 psi

GOODMAN EQUATION (Introduction to Rock Mechanics, 1980, P311, EQ 9.8)

F.S. = factor of safety: 5 (Additional input value)

Nsubphi =	20.262024
NPhi-1 =	19.262024
S/B =	0.5714286
Intermediate	10.902537
Intermediate	0.566012
Capacity =	10954
q_a = allowable bearing capacity	2191 psi

DOVER - UPPER SANDSTONE ALLOWABLE BEARING CAPACITY

INPUT PARAMETERS

c = cohesion:	88 psi	Required input for equations 6-1, 6-4, 8-5, 6-6	12672.0 psf
ϕ = phi angle:	64 degree	Required input for all equations	
D=depth of foundation below ground surface:	3 ft	Required input for equations 6-1, 6-3	
γ = effective unit weight of the rock mass:	98 pcf	Required input for equations 6-1, 6-3, 6-4	
B= width of the foundation:	35 ft	Required input for equations 6-1, 6-3, 8-4, 6-8, Goodman	
J = correction factor (see figure 6-2 of EM 1110-1-2908):	1.0	Required input for equation 6-8	
L = length of foundation:	65.0 ft	Required input for equation 6-8 (strip foundation shape) and L/B ratio	
S = Joint spacing:	20.0 ft	Required input for equations 6-6 and Goodman	
(q_u) = unconfined compressive strength:	4614 psi	Required input for equations 8-7 (cohesion equation) and Goodman	
(RMR) Rock Mass Rating:	66	Required input for equations 6-7 (cohesion equation)	
FS = factor of safety (min. 3, see eq. 6-11 EM 1110-1-2908):	3	Required input for all equations, separate Goodman FS input.	

COHESION EQUATION (equation 6-7)

$$s = 0.023$$


$$(c) \text{ cohesion} = 12 \text{ psi}$$

MISCELLANEOUS STEPS

$N_q = \tan^2(45 + \phi/2)$	18.74				
$N_q = N_q^{1/2} (N_q^{1/2} - 1)$	1516.92	1441.07	1365.22	1289.38	1081.84
$N_q = N_q^2$	351.37				
$N_c = 2N_q^{1/2} (N_q + 1)$	170.97	179.52	191.49	213.71	205.16
$N_{cr} = 2N_q^{1/2} + N_q (\cot \phi) (S/B) (1 - 1/N_q) - N_q (\cot \phi) + 2N_q^{1/2}$	8.9				

COMPRESSIVE FAILURE (equation 6-5, EM 1110-1-2908)

MODE: open, near vertical joint set(s) S<B: compressive failure of individual rock columns.




$$q_{ult} = 2c \tan(45 + \phi/2)$$

q_{ult} = ultimate bearing capacity	762 psi
q_a = allowable bearing capacity	254 psi

GENERAL SHEAR FAILURE WITHOUT COHESION (equation 6-3, EM 1110-1-2908)

MODE 1: moderately dipping joint set(s) S<B or S>B: general shear failure with potential for failure along joints.

MODE 2: two or more closely spaced joint sets. S<B: general shear failure with irregular failure surface through rock mass.



$$q_{ult} = 0.5\gamma B N_{\gamma} + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

q_{ult} = ultimate bearing capacity


q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
2704811 psf	2574735 psf	2444660 psf	2314584 psf	1924358 psf
18783 psi	17880 psi	16977 psi	16074 psi	13364 psi
6261 psi	5960 psi	5659 psi	5358 psi	4455 psi

GENERAL SHEAR FAILURE WITH COHESION (equation 6-1, EM 1110-1-2908)

MODE 1: ductile, intact rock or with few joints S>>B: general shear failure along well defined failure surfaces.

MODE 2: Closed, near vertical joint set(s) S<B: general shear failure along well defined failure surfaces.



$$q_{ult} = cN_c + 0.5\gamma B N_{\gamma} + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$


q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
4871350 psf	4849602 psf	4871184 psf	5022759 psf	4524205 psf
33829 psi	33678 psi	33828 psi	34880 psi	31418 psi
11276 psi	11228 psi	11276 psi	11627 psi	10473 psi

LOCAL SHEAR FAILURE (equation 6-4, EM 1110-1-2908)

MODE: brittle intact rock or with few joints S>>B: local shear failure caused by localized brittle fracture



$$q_{ult} = cN_c + 0.5\gamma B N_{\gamma}$$

$$L/B \text{ ratio: } 1.8571$$


q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
4768049 psf	4746300 psf	4767882 psf	4919457 psf	4420904 psf
33111 psi	32960 psi	33110 psi	34163 psi	30701 psi
11037 psi	10987 psi	11037 psi	11388 psi	10234 psi

SPLITTING FAILURE (equation 6-6, EM 1110-1-2908)

MODE: open or closed, widely spaced and vertical joints S>B: Failure initiated by splitting leading to general shear failure.



q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=<32	square	circular
309 psi	666 psi	784 psi
103 psi	222 psi	261 psi

GOODMAN EQUATION (Introduction to Rock Mechanics, 1980, P311, EQ 9.8)

F.S. = factor of safety:	5 (Additional input value)
Nsubphi =	18.886695
NPhi-1 =	17.686695
S/B =	0.5714286
Intermediate	10.002728
Intermediate	0.565551
Capacity =	2609
q_a = allowable bearing capacity	522 psi

DOVER - SILTSTONE / SANDY ALLOWABLE BEARING CAPACITY

INPUT PARAMETERS

c = cohesion:	20 psi	Required input for equations 6-1, 6-4, 6-5, 6-6	2880.0 psf
ϕ = phi angle:	46 degree	Required input for all equations	
D=depth of foundation below ground surface:	3 ft	Required input for equations 6-1, 6-3	
γ = effective unit weight of the rock mass:	98 pcf	Required input for equations 6-1, 6-3, 6-4	
B = width of the foundation:	35 ft	Required input for equations 6-1, 6-3, 6-4, 6-6, Goodman	
J = correction factor (see figure 6-2 of EM 1110-1-2908):	1.0	Required input for equation 6-6	
L = length of foundation:	65.0 ft	Required input for equation 6-6 (strip foundation shape) and L/B ratio	
S = Joint spacing:	20.0 ft	Required input for equations 6-6 and Goodman	
(q_u) = unconfined compressive strength:	7494 psi	Required input for equations 6-7 (cohesion equation) and Goodman	
(RMR) Rock Mass Rating:	51	Required input for equations 6-7 (cohesion equation)	
FS = factor of safety (min. 3, see eq. 6-11 EM 1110-1-2908):	3	Required input for all equations, separate Goodman FS input.	

COHESION EQUATION (equation 6-7)

$$s = 0.004$$


$$(c) \text{ cohesion} = 7 \text{ psi}$$

MISCELLANEOUS STEPS

$N_q = \tan^2(45 + \phi/2)$	6.12				
$N_c = N_q^{1/2} (N_q^2 - 1)$	90.30	85.78	81.27	76.75	63.21
$N_q = N_q^2$	37.49				
$N_c = 2N_q^{1/2} (N_q + 1)$	35.25	37.01	39.48	44.06	42.30
$N_q = 2N_q^{1/2} / (1 + N_q (\cot \phi) (S/B) (1 - 1/N_q) - N_q (\cot \phi) + 2N_q^{1/2})$	3.9				

COMPRESSIVE FAILURE (equation 6-5, EM 1110-1-2908)

MODE: open, near vertical joint set(s) $S < B$: compressive failure of individual rock columns.




$$q_{ult} = 2c \tan(45 + \phi/2)$$

q_{ult} = ultimate bearing capacity	99 psi
q_a = allowable bearing capacity	33 psi

GENERAL SHEAR FAILURE WITHOUT COHESION (equation 6-3, EM 1110-1-2908)

MODE 1: moderately dipping joint set(s) $S < B$ or $S > B$: general shear failure with potential for failure along joints.

MODE 2: two or more closely spaced joint sets. $S < B$: general shear failure with irregular failure surface through rock mass.



$$q_{ult} = 0.5\gamma B N_q + \gamma D N_q$$


$$L/B \text{ ratio: } 1.8571$$

	strip L/B >= 10	strip L/B = 5	strip L/B = 2	square	circular
q_{ult} = ultimate bearing capacity	165878 psf	158136 psf	150393 psf	142650 psf	119422 psf
	1152 psi	1098 psi	1044 psi	991 psi	829 psi
q_a = allowable bearing capacity	384 psi	366 psi	348 psi	330 psi	276 psi

GENERAL SHEAR FAILURE WITH COHESION (equation 6-1, EM 1110-1-2908)

MODE 1: ductile, intact rock or with few joints. $S > B$: general shear failure along well defined failure surfaces.

MODE 2: Closed, near vertical joint set(s) $S < B$: general shear failure along well defined failure surfaces.



$$q_{ult} = cN_c + 0.5\gamma B N_q + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

	strip L/B >= 10	strip L/B = 5	strip L/B = 2	square	circular
q_{ult} = ultimate bearing capacity	267402 psf	264735 psf	264099 psf	269554 psf	241249 psf
	1857 psi	1838 psi	1834 psi	1872 psi	1675 psi
q_a = allowable bearing capacity	619 psi	613 psi	611 psi	624 psi	558 psi

LOCAL SHEAR FAILURE (equation 6-4, EM 1110-1-2908)

MODE: brittle intact rock or with few joints $S > B$: local shear failure caused by localized brittle fracture




$$q_{ult} = cN_c + 0.5\gamma B N_q$$

$$L/B \text{ ratio: } 1.8571$$

	strip L/B >= 10	strip L/B = 5	strip L/B = 2	square	circular
q_{ult} = ultimate bearing capacity	256379 psf	253713 psf	253076 psf	258532 psf	230227 psf
	1780 psi	1762 psi	1757 psi	1795 psi	1599 psi
q_a = allowable bearing capacity	593 psi	587 psi	586 psi	598 psi	533 psi

SPLITTING FAILURE (equation 6-6, EM 1110-1-2908)

MODE: open or closed, widely spaced and vertical joints $S > B$: Failure initiated by splitting leading to general shear failure.



	strip L/B <= 32	square	circular
q_{ult} = ultimate bearing capacity	31 psi	66 psi	78 psi
q_a = allowable bearing capacity	10 psi	22 psi	26 psi

GOODMAN EQUATION (Introduction to Rock Mechanics, 1980, P311, EQ 9.8)

F.S. = factor of safety:	5 (Additional input value)
Nsubphi =	6.1109919
NPhi-1 =	5.1109919
S/B =	0.5714286
Intermediate	2.8268752
Intermediate	0.5530972
Capacity =	4145
q_a = allowable bearing capacity	829 psi

DOVER - SILTSTONE ALLOWABLE BEARING CAPACITY

INPUT PARAMETERS

c = cohesion:	15 psi	Required input for equations 6-1, 6-4, 6-5, 6-6	2160.0 psf
ϕ = phi angle:	31 degree	Required input for all equations	
D=depth of foundation below ground surface:	3 ft	Required input for equations 6-1, 6-3	
γ = effective unit weight of the rock mass:	98 pcf	Required input for equations 6-1, 6-3, 6-4	
B = width of the foundation:	35 ft	Required input for equations 6-1, 6-3, 6-4, 6-6, Goodman	
J = correction factor (see figure 6-2 of EM 1110-1-2908):	1.0	Required input for equation 6-6	
L = length of foundation:	65.0 ft	Required input for equation 6-6 (strip foundation shape) and L/B ratio	
S = Joint spacing:	20.0 ft	Required input for equations 6-6 and Goodman	
(q_u) = unconfined compressive strength:	8170 psi	Required input for equations 6-7 (cohesion equation) and Goodman	
(RMR) Rock Mass Rating:	52	Required input for equations 6-7 (cohesion equation)	
FS = factor of safety (min. 3, see eq. 6-11 EM 1110-1-2908):	3	Required input for all equations, separate Goodman FS input.	

COHESION EQUATION (equation 6-7)

$$s = 0.005$$


$$(c) \text{ cohesion} = 11 \text{ psi}$$

MISCELLANEOUS STEPS

$N_q = \tan^2(45 + \phi/2)$	3.12				
$N_q = N_q^{1/2} (N_q^{1/2} - 1)$	15.47	14.69	13.92	13.15	10.83
$N_q = N_q^2$	9.75				
$N_q = 2N_q^{1/2} (N_q + 1)$	14.57	15.30	16.32	18.21	17.49
$N_q = 2N_q^{1/2} / (1 + N_q (\cot \phi) (S/B) (1 - 1/N_q) - N_q (\cot \phi) + 2N_q^{1/2})$	1.4				

COMPRESSIVE FAILURE (equation 6-5, EM 1110-1-2908)

MODE: open, near vertical joint set(s) S<B: compressive failure of individual rock columns.




$$q_{ult} = 2c \tan(45 + \phi/2)$$

q_{ult} = ultimate bearing capacity	31 psi
q_a = allowable bearing capacity	10 psi

GENERAL SHEAR FAILURE WITHOUT COHESION (equation 6-3, EM 1110-1-2908)

MODE 1: moderately dipping joint set(s) S<B or S>B: general shear failure with potential for failure along joints.

MODE 2: two or more closely spaced joint sets. S<<B: general shear failure with irregular failure surface through rock mass.



$$q_{ult} = 0.5 \gamma B N_{\gamma} + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

q_{ult} = ultimate bearing capacity


q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
29394 psf	28067 psf	26741 psf	25415 psf	21436 psf
204 psi	195 psi	186 psi	176 psi	149 psi
68 psi	65 psi	62 psi	59 psi	50 psi

GENERAL SHEAR FAILURE WITH COHESION (equation 6-1, EM 1110-1-2908)

MODE 1: ductile, intact rock or with few joints S>>B: general shear failure along well defined failure surfaces.

MODE 2: Closed, near vertical joint set(s) S<B: general shear failure along well defined failure surfaces.



$$q_{ult} = cN_c + 0.5 \gamma B N_{\gamma} + \gamma D N_q$$

$$L/B \text{ ratio: } 1.8571$$

q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
60869 psf	61116 psf	61993 psf	64758 psf	59206 psf
423 psi	424 psi	431 psi	450 psi	411 psi
141 psi	141 psi	144 psi	150 psi	137 psi

LOCAL SHEAR FAILURE (equation 6-4, EM 1110-1-2908)

MODE: brittle intact rock or with few joints S>>B: local shear failure caused by localized brittle fracture



$$q_{ult} = cN_c + 0.5 \gamma B N_{\gamma}$$

$$L/B \text{ ratio: } 1.8571$$


q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=>10	strip L/B=5	strip L/B=2	square	circular
58001 psf	58249 psf	59128 psf	61891 psf	56338 psf
403 psi	405 psi	411 psi	430 psi	391 psi
134 psi	135 psi	137 psi	143 psi	130 psi

SPLITTING FAILURE (equation 6-6, EM 1110-1-2908)

MODE: open or closed, widely spaced and vertical joints S>B: Failure initiated by splitting leading to general shear failure.



q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B=<32	square	circular
8 psi	18 psi	21 psi
3 psi	6 psi	7 psi

GOODMAN EQUATION (Introduction to Rock Mechanics, 1980, P311, EQ 9.8)

F.S. = factor of safety: 5 (Additional input value)

Nsubphi =	3.1179475
NPhi-1 =	2.1179475
S/B =	0.5714286
Intermediate	1.1319589
Intermediate	0.5344803
Capacity =	4367

q_a = allowable bearing capacity 873 psi

DOVER - SHALE ALLOWABLE BEARING CAPACITY

INPUT PARAMETERS

c = cohesion:	5 psi	Required input for equations 6-1, 6-4, 6-5, 6-6	720.0 psf
ϕ = phi angle:	29 degree	Required input for all equations	
D=depth of foundation below ground surface:	3 ft	Required input for equations 6-1, 6-3	
γ = effective unit weight of the rock mass:	98 pcf	Required input for equations 6-1, 6-3, 6-4	
B= width of the foundation:	35 ft	Required input for equations 6-1, 6-3, 6-4, 6-6, Goodman	
J = correction factor (see figure 6-2 of EM 1110-1-2908):	1.0	Required input for equation 6-6	
L = length of foundation:	65.0 ft	Required input for equation 6-6 (strip foundation shape) and L/B ratio	
S = Joint spacing:	20.0 ft	Required input for equations 6-6 and Goodman	
(q_u) = unconfined compressive strength:	2822 psi	Required input for equations 6-7 (cohesion equation) and Goodman	
(RMR) Rock Mass Rating:	25	Required input for equations 6-7 (cohesion equation)	
FS = factor of safety (min. 3, see eq. 6-11 EM 1110-1-2908):	3	Required input for all equations, separate Goodman FS input.	

COHESION EQUATION (equation 6-7)


$$s = \frac{0.000}{(c) \text{ cohesion} = 0 \text{ psi}}$$

MISCELLANEOUS STEPS

$N_q = \tan^2(45 + \phi/2)$	2.88				
$N_c = N_q^{1/2} (N_q^2 - 1)$	12.39	11.77	11.15	10.53	8.87
$N_q = N_q^2$	8.30				
$N_c = 2N_q^{1/2} (N_q + 1)$	13.18	13.83	14.76	16.47	15.81
$N_{cs} = 2N_q^{3/2} + N_q (\cot \phi) (S/B) (1 - 1/N_q) - N_q (\cot \phi) + 2N_q^{1/2}$	1.1				

COMPRESSIVE FAILURE (equation 6-5, EM 1110-1-2908)

MODE: open, near vertical joint set(s) S<B: compressive failure of individual rock columns.




$$q_{ult} = 2 c \tan(45 + \phi/2)$$

q_{ult} = ultimate bearing capacity	17 psi
q_a = allowable bearing capacity	6 psi

GENERAL SHEAR FAILURE WITHOUT COHESION (equation 6-3, EM 1110-1-2908)

MODE 1: moderately dipping joint set(s) S<B or S>B: general shear failure with potential for failure along joints.

MODE 2: two or more closely spaced joint sets. S<<B: general shear failure with irregular failure surface through rock mass.



$$q_{ult} = 0.5 \gamma B N_{\gamma} + \gamma D N_q$$

L/B ratio: 1.8571

q_{ult} = ultimate bearing capacity


q_a = allowable bearing capacity

strip L/B>10	strip L/B=5	strip L/B=2	square	circular
23692 psf	22629 psf	21567 psf	20504 psf	17316 psf
165 psi	157 psi	150 psi	142 psi	120 psi
55 psi	52 psi	50 psi	47 psi	40 psi

GENERAL SHEAR FAILURE WITH COHESION (equation 6-1, EM 1110-1-2908)

MODE 1: ductile, intact rock or with few joints S>>B: general shear failure along well defined failure surfaces.

MODE 2: Closed, near vertical joint set(s) S<B: general shear failure along well defined failure surfaces.



$$q_{ult} = c N_c + 0.5 \gamma B N_{\gamma} + \gamma D N_q$$

L/B ratio: 1.8571

q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B>10	strip L/B=5	strip L/B=2	square	circular
33178 psf	32590 psf	32191 psf	32362 psf	28700 psf
230 psi	226 psi	224 psi	225 psi	199 psi
77 psi	75 psi	75 psi	75 psi	66 psi

LOCAL SHEAR FAILURE (equation 6-4, EM 1110-1-2908)

MODE: brittle intact rock or with few joints S>>B: local shear failure caused by localized brittle fracture



$$q_{ult} = c N_c + 0.5 \gamma B N_{\gamma}$$

L/B ratio: 1.8571


q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B>10	strip L/B=5	strip L/B=2	square	circular
30738 psf	30149 psf	29751 psf	29921 psf	26259 psf
213 psi	209 psi	207 psi	208 psi	182 psi
71 psi	70 psi	69 psi	69 psi	61 psi

SPLITTING FAILURE (equation 6-6, EM 1110-1-2908)

MODE: open or closed, widely spaced and vertical joints S>B: Failure initiated by splitting leading to general shear failure.



q_{ult} = ultimate bearing capacity

q_a = allowable bearing capacity

strip L/B<32	square	circular
2 psi	5 psi	5 psi
1 psi	2 psi	2 psi

GOODMAN EQUATION (Introduction to Rock Mechanics, 1980, P311, EQ 9.8)

F.S. = factor of safety:	5 (Additional input value)
Nsubphi =	2.8765727
NPhi-1 =	1.8765727
S/B =	0.5714286
Intermediate	0.9967809
Intermediate	0.5311803
Capacity =	1499

q_a = allowable bearing capacity 300 psi

DOVER DSA

Lithology: LIMESTONE

Boring	Tested depth	Compressive Strength (PSI)	E_{t50} Elastic Modulus (x10^{^6})
C-04-03	81.7 - 82.5	20,810	32.95
C-04-03	83.0 - 83.7	18,910	19.48
C-04-06	50.6 - 51.3	19,790	45.22*
C-04-05A	52.1 - 52.8	20,190	31.31
C-04-13	49.0 - 49.7	20,200	15.22

Average Compressive Strength=	19,980	Average Elastic Modulus=	24.74
STDEVP=	626.48	STDEVP=	7.56
Average minus one STDEVP =	19,353.52		

*Note test results accompanied by * were not used in the statistical equations

DOVER DSA

Lithology: Upper Sandstone

Boring	Tested depth	Compressive Strength (PSI)	E _{t50} Elastic Modulus (x10 ^{^6})
C-04-01	12.3 - 13.1	5,210	1.49
C-04-02	14.9 - 15.7	6,800	1.53
C-04-03	43.4 - 44.1	5,550	2.22
C-04-14	23.3 - 24.0	8,710	3.77
C-04-14	41.4 - 42.2	4,360	1.23
Average Compressive Strength=		6,126	Average Elastic Modulus= 2.05
STDEVP=		1,511.35	STDEVP= 0.92
Average minus one STDEVP =		4,614.65	

*Note test results accompanied by * were not used in the statistical equations

DOVER DSA

Lithology: Lower Sandstone

Boring	Tested depth	Compressive Strength (PSI)	E_{t50} Elastic Modulus ($\times 10^6$)
C-04-06	61.3 - 62.0	8,270	2.81
C-04-06	65.6 - 66.4	14,900	3.80
C-04-06	97.0 - 97.8	3070*	2.06*
C-04-09	54.3 - 55.0	8,530	2.50
C-04-09	60.3 - 61.1	9,170	2.75
Average Compressive Strength=		10,218	Average Elastic Modulus= 2.97
Average minus one STDEVP =		STDEVP= 2,723.21	STDEVP= 0.50
			7,494.29

*Note test results accompanied by * were not used in the statistical equations

DOVER DSA

Lithology: Siltstone

Boring	Tested depth	Compressive Strength (PSI)	E ₅₀ Elastic Modulus (x10 ⁶)
C-04-04	100.3 - 101.0	8,240	3.03
C-04-05A	79.0 - 79.7	8,270	3.03
C-04-10	44.3 - 45.0	13,040	2.60
C-04-09	48.6 - 49.3	10,170	4.26*
C-04-10	41.4 - 42.1	9,890	2.33

Average Compressive Strength=	9,922	Average Elastic Modulus=	2.75
STDEVP=	1,751.72	STDEVP=	0.30
Average minus one STDEVP =	8,170.28		

*Note test results accompanied by * were not used in the statistical equations

DOVER DSA

Lithology: Shale

Boring	Tested depth	Compressive Strength (PSI)	E ₁₅₀ Elastic Modulus (x10 ^{^6})
C-04-01	60.2 - 61.5*	410*	0.03*
C-04-01	67.1 - 67.8	2,750	1.67
C-04-01	72.0 - 72.8	2,940	1.81
C-04-13	87.2 - 87.9	4,320	1.76
C-04-13	90.0 - 90.8*	3,880	7.23*

Average Compressive Strength=	3,473	Average Elastic Modulus=	1.75
Average minus one STDEVP =	STDEVP=	STDEVP=	0.06
	649.98		
	2,822.52		

*Note test results accompanied by * were not used in the statistical equations

CLASSIFICATION PARAMETERS AND THEIR RATINGS

PARAMETER			RANGES OF VALUES							
1	Strength of intact rock material	Point-load strength index	>10 MPa	4-10 MPa	2-4 MPa	1-2 MPa	For this low range- Uniaxial compressive test is preferred			
		Uniaxial compressive strength	> 250 MPa	100 - 250 MPa	50 - 100 MPa	25 - 50 MPa	5-25 MPa	1-5 MPa	<1 MPa	
2	Rating	Rating	15	12	7	4	2	1	0	
		Drill core quality RQD	90%-100%	75%-90%	50%-75%	25%-50%	<25%			
3	Rating	Rating	20	17	13	6	3			
		Spacing Discontinuities	>2m	0.6-2m	200-600mm	60-200mm	<60mm			
4	Rating	Rating	20	15	10	8	5			
		Condition of Discontinuities	Very rough surfaces. Not continuous No separation Unweathered wall rock	Slightly rough surfaces. Separation <1mm. Slightly weathered walls	Slightly rough surfaces. Separation <1mm. Highly weathered walls	Slickensided surfaces OR Gouge <5mm thick OR Separation 1-5mm. Continuous.	Soft gouge >5mm thick OR Separation >5mm. Continuous.			
5	Rating	Rating	30	25	20	10	0			
		Inflow per 10m tunnel length	None	<10 L/mm	10-25 L/mm	25-125 L/mm	>125 L/mm			
5	Groundwater	Ratio	0	0.0-0.1	0.1-0.2	0.2-0.5	>0.5			
		General Conditions	Completely dry	Damp	Wet	Dripping	Flowing			
5	Rating	Rating	15	10	7	4	0			

Lithology	PARAMETER					Joint Orientation Adjustment	Rating Total
	1	2	3	4	5		
Limestone	12	13	10	10	7	-15	37
Upper Sandstone	4	17	15	25	7	-2	66
Siltstone / Sandy	7	17	10	25	7	-15	51
Siltstone	7	20	10	25	7	-15	54
Shale	2	13	8	10	7	-15	25




Boring	ABUTMENT RQD									ABUTMENT RQD											
	Limestone			Upper Sandstone			Sandy Siltstone			Siltstone			Shale			Coal			SS interbedded w/ SH		
	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT
C-04-1	70	1.1	77	93	2.5	232.5							18	4	72	2.4	54	129.6			0
				100	5.0	500							0	3.7	0						
				92	5.0	460							93	2.8	260.4						
				100	5.0	500							54	2.4	129.6						
				90	5.1	459							54	1.7	91.8						
				100	5.0	500							100	4.9	490						
				100	5.0	500							70	4.0	280						
				80	4.9	392															
				91	5.1	464.1															
			18	0.9	16.2																
C-04-2	67	1.0	67	0	2.6	0	100	1	100	91	1.1	100.1	36	3.3	118.8						
	91	1.1	100.1	36	1.1	39.6	71	3.8	269.8	100	5.7	570									
	100	4.2	420	36	0.8	28.8	100	2.0	200												
	100	1.1	110	0	10.1	0	66	5.0	330												
	98	5.0	490	40	4.3	172	100	2.9	290												
	72	5.0	360	71	1.2	85.2	100	3.1	310												
	100	3.8	380	78	5.0	390	100	7.7	770												
				98	5.0	480															
C-04-3	28	2.8	78.4	96	5.0	430	0	1.2	0	88	2.4	211.2	0	2.6	0	50	1.6	80			
	50	0.9	45	100	8.0	800	0	5.0	0				28	2.2	61.6						
	86	2.3	151.8	67	4.0	268	0	4.8	0				50	2.5	125						
	86	1.6	136	91	3.0	273	47	5.2	244.4				88	5.0	440						
			0	100	2.1	210	88	5.0	440				30	5.0	150						
			0	100	4.4	440	90	5.0	450				66	2.7	178.2						
				100	2.4	240	90	5.0	450				85	1.2	102						
				88	5.0	440	92	5.1	469.2				88	3.0	264						
				92	5.0	460	0	2.4	0												
				94	2.8	263.2															
				100	0.6	60															
				100	5.7	570															
			100	6.4	640																
C-04-4	0	1.4	0	0	0.7	0	100	0.8	80				38	2.4	91.2	20	1.3	26			
	20	1.0	20	0	2.8	0	87	4.6	400.2				0	3.7	0						
	72	4.9	352.8	0	3.5	0			0				20	2.7	54						
	31	0.1	3.1	66	5.0	280			0				76	5.1							
			0	62	5.0	310			0				72	4.9							
			0	36	5.1	183.6			0				78	5.0							
			0	38	2.5	95			0				88	4.7							
			0			0			0				31	4.8							
			0			0			0				87	0.7							
			0			0			0												
C-04-5a	90	3.1	279	0		0	93	4.9	455.7	90	4.8	432	0	3.3	0			0			0
	46	0.9	40.5	0		0	94	5.1	479.4	92	1.0	92	24	5.1	122.4						
			0	0		0	98	4.9	480.2				38	4.9	186.2						
			0	0		0	96	5.1	499.8				90	1.9	171						
			0	0		0	92	4.2	386.4				46	4.3	193.5						
			0	0		0	88	4.9	431.2												
			0	0		0	80	5.0	400												
			0	0		0	78	5.1	397.8												
			0	0		0	67	1.5	100.5												
C-04-6	82	3.5	287	0		0	96	5.0	490	90	5	450	88	3.9	335.4			0			0
	86	1.1	94.6	0		0	96	5.0	480	88	0.4	35.2	0	3.5	0						
			0	0		0	98	5.0	490			0	46	5.0	230						
			0	0		0	94	5.0	470				38	5.1	193.8						
			0	0		0	88	4.6	404.8				62	1.5	123						
			0	0		0	78	4.9	382.2												
			0	0		0	50	5.0	250												
			0	0		0	84	5.0	420												
			0	0		0	75	2.2	165												
C-04-7	100	2.8	280	0		0	39	1.8	70.2	76	4.8	364.8	46	2.4	110.4						
	46	2.6	119.6	0		0	100	5.0	500	90	1.7	153	39	3.2	124.8						
				0		0	100	5.0	500												
				0		0	100	4.9	490												
				0		0	92	5.1	469.2												
				0		0	76	0.2	15.2												
				0		0	90	3.3	297												
				0		0	90	5.0	450												
				0		0	84	5.0	420												

ABUTMENT RQD												ABUTMENT RQD											
	Limestone			Upper Sandstone			Sandy Siltstone			Siltstone			Shale			Coal			SS interbedded w/ SH				
Boring	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT	RQD	THICK	PRODUCT		
C-04-8	96	4.8	460.8			0	44	0.4	17.6			0	34	2.9	98.6	44	0.2	8.8					
			0			0	86	6	576			0	44	2.0	88								
			0			0	90	2.3	207				44	2.4									
			0			0	90	1.7	153														
			0			0	94	5.0	470														
			0			0	88	5.0	440														
							96	1.3	124.8														
							98	3.7	355.2														
							87	5.1	443.7														
							86	5.0	430														
							65	4.3	279.5														
C-04-9	100	2.2	220			0	92	4.2	386.4	98	1.5	147	86	0.6	51.6	49	0.2	9.8					
	88	2.2	189.2			0	98	2.7	264.6	100	1.2	120	49	3.8	186.2								
			0			0	100	3.5	350				49	1.0	49								
			0			0	80	5.0	400				92	0.9	82.8								
			0			0	98	5.0	490														
			0			0	94	5.0	470														
			0			0	88	5.0	430														
			0			0	86	5.0	430														
			0			0	87	3.0	261														
			0			0																	
C-04-10	49	1.3	63.7	100	2.8	280	76	2.1	159.6	98	4.9	480.2	82	1.6	131.2	67	0.1	6.7					
	82	3.3	270.6	90	5.0	450	93	5.1	474.3	100	2.3	230	67	2.3	154.1								
				76	2.8	212.8	78	2.6	202.8				67	2.7	180.9								
							78	2.4	187.2														
							84	5.0	420														
							88	5.0	430														
						60	1.0	60															
C-04-11	22	1.5	33										22	1.0	22	22	0.7	15.4			0		
													0	2.5	0								
													0	2.5	0								
C-04-12													19	2.1	39.9								
													0	0.8	0								
													0	5.0	0								
													27	1.3	35.1								
													27	3.5	94.5								
C-04-13	78	1.4	109.2	99	1.1	108.9	100	4.4	440			0	98	0.7	69.3	99	0	0	100	3.3	330		
	78	2.0	156	92	5.0	460							78	1.4	109.2	78	0.8	62.4			0		
	90	4.8	432	93	5.2	483.6							100	0.8	80	80	0.3	24			0		
	96	0.7	67.2	100	5.0	500							100	0.9	90								
				100	5.0	500							100	5.0	500								
				82	4.9	303.8							100	5.0	500								
				52	0.5	26							100	5.1	510								
				52	4.5	234							100	5.0	500								
				78	0.2	15.6							90	0.1	9								
													96	4.4	422.4								
													80	0.4	32								
													80	4.2	336								
C-04-14													100	0.7	70								
	82	0.5	41	72	1.3	93.6	74	0.3	22.2				94	2.0	188	72	1.0		72	0.1	7.2		
	72	0.6	43.2	94	2.9	272.6	100	5.0	500				82	4.5	369	68	0.3		100	3.7	370		
	92	1.1		100	5.1	510							100	1.0	100	30	0.3						
	86	4.4		100	4.9	490							100	5.1	510								
				98	5.2	509.6							100	5.0	500								
				85	4.8	408							88	5.0	440								
				30	2.1	63							92	3.9	358.8								
													72	2.0	144								
													30	0.6	18								
													86	0.5	43								
													68	3.8	258.4								
												68	1.0	68									
													74	4.6	340.4								
Totals	82.1	5977.8		220.9	17103.7		303.4	25463.1		36.8	3385.5		240.7	12478.5		60.8	362.7		7.1	707.2			
Weighted RQD's	72.81			77.43			83.93			92.00			51.84			5.97				99.61			


	Limestone Unit Weight (pcf)	Upper Sandstone Unit Weight (pcf)	Sandy Siltstone Unit Weight (pcf)	Siltstone Unit Weight (pcf)	Shale Unit Weight (pcf)
SAMPLE 1	170.1	154.2	165.1	162.1	161.3
SAMPLE 2	168.0	156.3	172.1	167.6	162.1
SAMPLE 3	168.8	145.8	143.8	167.4	161.4
SAMPLE 4	168.6	140.8	155.9	164.7	161.3
SAMPLE 5	167.3	143.2	161.6	167.3	
Average Unit Weight=	168.56	148.06	159.70	165.82	161.53

EXHIBIT II-7

UPLIFT



NOTE: SEE P.I. REPORT NO. 4 FOR ADDITIONAL UPLIFT
CELL AND MONOLITH DETAILS.



LEGEND

- FULL RESEVOIR HEAD TO FULL TAILWATER HEAD
 16 JANUARY 2005
 FULL RESEVOIR HEAD TO FULL TAILWATER HEAD
 14 JANUARY 2005
 FULL RESEVOIR HEAD TO FULL TAILWATER HEAD
 14 JULY 1969
 OBSERVED UPLIFT (POOL OF RECORD)
 16 JANUARY 2005
 OBSERVED UPLIFT (LAST READING PRIOR TO CELL CLEANOUT)
 14 JANUARY 2005
 OBSERVED UPLIFT
 14 JULY 1969
 ⑧ UPLIFT CELL NUMBER
 FOUNDATION DRAIN



US Army Corps
of Engineers
Huntington District

[illegible]

U.S. ARMY CORPS OF ENGINEERS HUNTINGTON DISTRICT HUNTINGTON, WEST VIRGINIA	Designed by:	Dollar	Rev.
	Drawn by: Cald by: JOS	Design file no.	
	Reviewed by: COB	Drawing code	
	Submitted by:	File number (FD-Drawing, Doc Proc code)	1" = 32'

TUSCARAWAS RIVER
DOVER, OH
DOVER DAM
DAM SAFETY ASSURANCE

DOVER DAM
INSTRUMENTATION
UPLIFT CELLS

Sheet
reference
number:

Sheet 1 of 1

EXHIBIT II-8

MAPPING OF FAULTS AND JOINTS



DOVER Dam, Ohio
JOINTS AND FRACTURES AS MAPPED FROM ANGEE BORINGS G-4 TO G-15, 1963

EXHIBIT II-9

ANCHOR EMBEDMENT

Summary of Anchor Calculations

Anchor depth (feet) **46**
 Bond length (feet) **45**

		Design 60%	Max Test 80%	Lock Off 70%	GUTS
.06 inch strand, with design load 35.2 kips	# of strands	Load kips	Load kips	Load kips	kips
Per strand	1	35.2	46.8	41.0	58.6
Per anchor	61	2144.76	2853	2502	
Anchors Per area	3	6434.28			

ANALYSIS FOR TENSION ANCHOR SYSTEMS : ANCHOR DEPTHS (EM 1110-1-2908)**Description**

pcf effective unit weight of rock
 FS = factor of safety
 c = rock mass cohesion intercept*
 F = anchor force required for stability
 w = unit weight of rock
 s = anchor spacing
 l = row spacing (for anchors with multiple rows)

Symbol**Value**

160
 FS= 4
 c= 4355.1 psf
 F= 2144760 pounds
 w= 97.6 pcf Buoyant Weight
 s= 22 ft
 l= 8 ft

Application

single anchors in competent rock
 single row of anchors in competent rock
 multiple row of anchors in competent rock, with a factor of safety of 1.5
 single anchor in fractured rock, with a factor of safety of 1.5
 single row of anchors in fractured rock, with a factor of safety of 1.5
 multiple row of anchors in fractured rock, with a factor of safety of 1.5

Formula**Results**

$\sqrt{FS \cdot F / c \cdot 3.14159}$ 25
 $(FS \cdot F) / cs$ 90
 $(FS \cdot F) / wls$ 187
 $\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$ 32
 $\sqrt{FS \cdot F / ws}$ 39
 $(FS \cdot F) / wls$ 187

* c= a weighted average of the cross bed shear strength

single anchor in fractured rock with the combined force of all the anchors in that monolith

$\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$

45.5

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	SHEAR STRENGTH (psi)
limestone	4.00	150 (test)
Upper Sandstone	0.00	88 (test)
Siltstone / Sandy	25.00	20 (test)
Siltstone	8.00	15 (test)
Shale	4.00	5 (test)
TOTAL THICKNESS BENEATH FAILURE	41.00 feet	
WEIGHTED MEAN:		30 psi
		rock mass cohesion*

* c= a weighted average of the cross bed shear strength

CALCULATING BOND LENGTHS FOR ROCK ANCHOR SYSTEM

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	BOND STRENGTH (psi)
Limestone	0.00	85 (test)
Sandstone	0.00	110 (test)
Siltstone / Sandy	45.00	95 (test)
Siltstone	0.00	90 (test)
Shale	0.00	50 (test)
TOTAL THICKNESS OF BOND ZONE:	45.00 feet	
WEIGHTED MEAN:		95 psi
		Working Bond Strength

COMPARISONS - VARYING HOLE DIAMETERS:**COMPOSITE LITHOLOGY using working bond strength, and various diameters**

LOCK OFF KIPS:	2502	2502	2502	2502
ANCHOR BOND STRENGTH (CHOSEN):	95	95	95	95
HOLE DIAMETER (in.):	14.00	15.00	16.00	16.25
RADIUS	7.00	7.50	8.00	8.13
BOND AREA REQ'D. (sq. in.):	26339.16	26339.16	26339.16	26339.16
ANCHOR BOND LENGTH (in.):	599	559	524	516
ANCHOR BOND LENGTH (ft.):	49.9	46.6	43.7	43.0
			45	

THE GRAY HIGHLIGHTED BOND LENGTH REPRESENTS THE LENGTH CHOSEN FOR THIS ANCHOR
 BASED ON THE DIAMETER OF THE HOLE

Summary of Anchor Calculations

Anchor depth (feet)	27
Bond length (feet)	25

Area of Bar	3.14	Design 60%	Max Test 80%	Lock Off 70%	GUTS
Bar Size in Inches	2	Load kips	Load kips	Load kips	kips
Bar strength ksi	150	283	376	330	471
Anchors Per area	4	1131			

ANALYSIS FOR TENSION ANCHOR SYSTEMS : ANCHOR DEPTHS (EM 1110-1-2908)

Description	Symbol	Value
pcf effective unit weight of rock		160
FS = factor of safety	FS=	4
c = rock mass cohesion intercept*	c=	4355.1 psf
F = anchor force required for stability	F=	282743 pounds
w = unit weight of rock	w=	97.6 pcf Buoyant Weight
s = anchor spacing	s=	15 ft
l = row spacing (for anchors with multiple rows)	l=	15 ft

Application	Formula	Results
single anchors in competent rock	$\sqrt{FS \cdot F / c \cdot 3.14159}$	9
single row of anchors in competent rock	$(FS \cdot F) / cs$	17
multiple row of anchors in competent rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19
single anchor in fractured rock, with a factor of safety of 1.5	$\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$	16
single row of anchors in fractured rock, with a factor of safety of 1.5	$\sqrt{FS \cdot F / ws}$	17
multiple row of anchors in fractured rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19

* c= a weighted average of the cross bed shear strength

single anchor in fractured rock with the combined force of all the anchors in that monolith	$\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$	25.5
---	--	------

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	SHEAR STRENGTH (psi)
limestone	4.00	150 (test)
Upper Sandstone	0.00	88 (test)
Siltstone / Sandy	25.00	20 (test)
Siltstone	8.00	15 (test)
Shale	4.00	5 (test)
TOTAL THICKNESS BENEATH FAILURE	41.00 feet	
WEIGHTED MEAN:		30 psi
		rock mass cohesion*

* c= a weighted average of the cross bed shear strength

CALCULATING BOND LENGTHS FOR ROCK ANCHOR SYSTEM

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	BOND STRENGTH (psi)
Limestone	0.00	85 (test)
Sandstone	0.00	110 (test)
Siltstone / Sandy	25.00	95 (test)
Siltstone	0.00	90 (test)
Shale	5.00	50 (test)
TOTAL THICKNESS OF BOND ZONE:	30.00 feet	
WEIGHTED MEAN:		88 psi
		Working Bond Strength

COMPARISONS - VARYING HOLE DIAMETERS:

COMPOSITE LITHOLOGY using working bond strength, and various diameters

LOCK OFF KIPS:	330	330	330	330
ANCHOR BOND STRENGTH (CHOSEN):	88	88	88	88
HOLE DIAMETER (in.):	3.00	4.00	5.00	6.00
RADIUS	1.50	2.00	2.50	3.00
BOND AREA REQ'D. (sq. in.):	3769.91	3769.91	3769.91	3769.91
ANCHOR BOND LENGTH (in.):	399	300	240	200
ANCHOR BOND LENGTH (ft.):	33.3	25.0	20.0	16.6
			25	

THE GRAY HIGHLIGHTED BOND LENGTH REPRESENTS THE LENGTH CHOSEN FOR THIS ANCHOR BASED ON THE DIAMETER OF THE HOLE

Summary of Anchor Calculations

Anchor depth (feet)	31
Bond length (feet)	25

Area of Bar	3.14	Design 60%	Max Test 80%	Lock Off 70%	GUTS
Bar Size in Inches	2	Load kips	Load kips	Load kips	kips
Bar strength ksi	150	283	376	330	471
Anchors Per area	6	1696			

ANALYSIS FOR TENSION ANCHOR SYSTEMS : ANCHOR DEPTHS (EM 1110-1-2908)

Description	Symbol	Value
pcf effective unit weight of rock		160
FS = factor of safety	FS=	4
c = rock mass cohesion intercept*	c=	4355.1 psf
F = anchor force required for stability	F=	282743 pounds
w = unit weight of rock	w=	97.6 pcf Buoyant Weight
s = anchor spacing	s=	15 ft
l = row spacing (for anchors with multiple rows)	l=	15 ft

Application	Formula	Results
single anchors in competent rock	$\sqrt{(FS \cdot F / c \cdot 3.14159)}$	9
single row of anchors in competent rock	$(FS \cdot F) / cs$	17
multiple row of anchors in competent rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19
single anchor in fractured rock, with a factor of safety of 1.5	$\sqrt[3]{(3FS \cdot F) / (w \cdot 3.14159)}$	16
single row of anchors in fractured rock, with a factor of safety of 1.5	$\sqrt{(FS \cdot F / ws)}$	17
multiple row of anchors in fractured rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19

* c= a weighted average of the cross bed shear strength

single anchor in fractured rock with the combined force of all the anchors in that monolith $\sqrt[3]{(3FS \cdot F) / (w \cdot 3.14159)}$ **29.2**

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	SHEAR STRENGTH (psi)
limestone	4.00	150 (test)
Upper Sandstone	0.00	88 (test)
Siltstone / Sandy	25.00	20 (test)
Siltstone	8.00	15 (test)
Shale	4.00	5 (test)
TOTAL THICKNESS BENEATH FAILURE	41.00 feet	
WEIGHTED MEAN:		30 psi
		rock mass cohesion*

* c= a weighted average of the cross bed shear strength

CALCULATING BOND LENGTHS FOR ROCK ANCHOR SYSTEM

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	BOND STRENGTH (psi)
Limestone	0.00	85 (test)
Sandstone	0.00	110 (test)
Siltstone / Sandy	25.00	95 (test)
Siltstone	0.00	90 (test)
Shale	5.00	50 (test)
TOTAL THICKNESS OF BOND ZONE:	30.00 feet	
WEIGHTED MEAN:		88 psi
		Working Bond Strength

COMPARISONS - VARYING HOLE DIAMETERS:**COMPOSITE LITHOLOGY using working bond strength, and various diameters**

LOCK OFF KIPS:	330	330	330	330
ANCHOR BOND STRENGTH (CHOSEN):	88	88	88	88
HOLE DIAMETER (in.):	3.00	4.00	5.00	6.00
RADIUS	1.50	2.00	2.50	3.00
BOND AREA REQ'D. (sq. in.):	3769.91	3769.91	3769.91	3769.91
ANCHOR BOND LENGTH (in.):	399	300	240	200
ANCHOR BOND LENGTH (ft.):	33.3	25.0	20.0	16.6

25

THE GRAY HIGHLIGHTED BOND LENGTH REPRESENTS THE LENGTH CHOSEN FOR THIS ANCHOR BASED ON THE DIAMETER OF THE HOLE

Summary of Anchor Calculations

Anchor depth (feet) **27**
 Bond length (feet) **25**

Area of Bar	3.14	Design 60%	Max Test 80%	Lock Off 70%	GUTS
Bar Size in Inches	2	Load kips	Load kips	Load kips	kips
Bar strength ksi	150	283	376	330	471
Anchors Per area	4	1131			

ANALYSIS FOR TENSION ANCHOR SYSTEMS : ANCHOR DEPTHS (EM 1110-1-2908)

Description	Symbol	Value
pcf effective unit weight of rock		160
FS = factor of safety	FS=	4
c = rock mass cohesion intercept*	c=	4355.1 psf
F = anchor force required for stability	F=	282743 pounds
w = unit weight of rock	w=	97.6 pcf Buoyant Weight
s = anchor spacing	s=	15 ft
l = row spacing (for anchors with multiple rows)	l=	15 ft

Application	Formula	Results
single anchors in competent rock	$\sqrt{(FS \cdot F / c \cdot 3.14159)}$	9
single row of anchors in competent rock	$(FS \cdot F) / cs$	17
multiple row of anchors in competent rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19
single anchor in fractured rock, with a factor of safety of 1.5	$\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$	16
single row of anchors in fractured rock, with a factor of safety of 1.5	$\sqrt{(FS \cdot F / ws)}$	17
multiple row of anchors in fractured rock, with a factor of safety of 1.5	$(FS \cdot F) / wls$	19

* c= a weighted average of the cross bed shear strength

single anchor in fractured rock with the combined force of all the anchors in that monolith $\text{cbrt}((3FS \cdot F) / (w \cdot 3.14159))$ **25.5**

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	SHEAR STRENGTH (psi)
limestone	4.00	150 (test)
Upper Sandstone	0.00	88 (test)
Siltstone / Sandy	25.00	20 (test)
Siltstone	8.00	15 (test)
Shale	4.00	5 (test)
TOTAL THICKNESS BENEATH FAILURE	41.00 feet	
WEIGHTED MEAN:		30 psi
		rock mass cohesion*

* c= a weighted average of the cross bed shear strength

CALCULATING BOND LENGTHS FOR ROCK ANCHOR SYSTEM

ROCK TYPES PRESENT	AVG. THICKNESS (ft.)	BOND STRENGTH (psi)
Limestone	0.00	85 (test)
Sandstone	0.00	110 (test)
Siltstone / Sandy	25.00	95 (test)
Siltstone	0.00	90 (test)
Shale	5.00	50 (test)
TOTAL THICKNESS OF BOND ZONE:	30.00 feet	
WEIGHTED MEAN:		88 psi
		Working Bond Strength

COMPARISONS - VARYING HOLE DIAMETERS:

COMPOSITE LITHOLOGY using working bond strength, and various diameters

LOCK OFF KIPS:	330	330	330	330
ANCHOR BOND STRENGTH (CHOSEN):	88	88	88	88
HOLE DIAMETER (in.):	3.00	4.00	5.00	6.00
RADIUS	1.50	2.00	2.50	3.00
BOND AREA REQ'D. (sq. in.):	3769.91	3769.91	3769.91	3769.91
ANCHOR BOND LENGTH (in.):	399	300	240	200
ANCHOR BOND LENGTH (ft.):	33.3	25.0	20.0	16.6
			25	

THE GRAY HIGHLIGHTED BOND LENGTH REPRESENTS THE LENGTH CHOSEN FOR THIS ANCHOR
 BASED ON THE DIAMETER OF THE HOLE